

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE 0021			
				QUANTITY	QUANTITY	QUANTITY	QUANTITY
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	2234	767	1467		
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1995		1995		
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	2050		2050		
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	39		39		
87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	538		538		
87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	4		4		
87700210	STEEL MAST ARM ASSEMBLY AND POLE, 34 FT.	EACH	1		1		
87700230	STEEL MAST ARM ASSEMBLY AND POLE, 38 FT.	EACH	2		2		
87700240	STEEL MAST ARM ASSEMBLY AND POLE, 40 FT.	EACH	1		1		
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	16		16		
87800150	CONCRETE FOUNDATION, TYPE C	FOOT	4		4		
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	46		46		
88030020	SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST-ARM MOUNTED	EACH	16	9	7		
88030100	SIGNAL HEAD, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	5	2	3		

\* SPECIALTY ITEMS

Rev. 2-18-14

FILE NAME * MICROST\252189\05-SUMMARY.DGN	USER NAME * JOC	DESIGNED - BPT	REVISED -
		DRAWN - RDS/JGC	REVISED -
		CHECKED - BPT	REVISED -
		DATE - 11-29-13	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES  
U.S. ROUTE 6 (159TH STREET) AT OAK PARK AVENUE AND 71ST COURT

SCALE: 1"=20' SHEET NO. OF SHEETS STA. TO STA.

PREPARED BY:  
**CEMCON, Ltd.**  
Consulting Engineers, Land Surveyors & Planners  
2280 White Oak Circle, Suite 100  
Aurora, Illinois 60504-9675  
PH: 630.862.2100 FAX: 630.862.2199  
E-Mail: cec@cemcon.com Website: www.cemcon.com

F.A.P. RTE. 351	SECTION 2013-061TS	COUNTY COOK	TOTAL SHEETS 30	SHEET NO. 5
FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT			CONTRACT NO. 60X33	