

INDEX OF SHEETS

STATE STANDARDS

GENERAL NOTES

SHEET NO.	DESCRIPTION	STANDARD NO.	DESCRIPTION
1	COVER SHEET	000001-06	TYPICAL SYMBOLS, ABBREVIATIONS AND PATTERNS
2	INDEX OF SHEETS, STATE STANDARDS, GENERAL NOTES	424001-07	PERPENDICULAR CURB RAMPS FOR SIDEWALKS
3	LOCATION MAP - MCHENRY COUNTY	424006-01	DIAGONAL CURB RAMPS FOR SIDEWALKS
4-5	SUMMARY OF QUANTITIES	424011-01	CORNER PARALLEL CURB RAMPS FOR SIDEWALKS
6	SCHEDULE OF QUANTITIES	424016-01	MID-BLOCK RAMPS FOR SIDEWALKS
7-8	ROADWAY PLAN - IL 173 AT ALDEN ROAD	424021-02	DEPRESSED CORNER FOR SIDEWALKS
9-22	ROADWAY PLAN - IL 176 (US 14 TO IL 131)	424031-01	MEDIAN PEDESTRIAN CROSSINGS
23-28	ROADWAY PLAN - IL 173 (KENNEDY STREET TO CENTER STREET)	442201-03	CLASS C AND D PATCHES
29-34	ROADWAY PLAN - IL 47 (PRAIRIE AVENUE TO MCKINLEY AVENUE)	604086-02	FRAME & GRATE, TYPE 23
35-40	ROADWAY PLAN - IL 23 (US 20 TO COURTNEY LANE)	604091-02	FRAME & GRATE, TYPE 24
41-43	ROADWAY PLAN - IL 31 (VETERANS PARKWAY TO BULL VALLEY ROAD)	606001-05	CONCRETE CURB AND COMBINATION CONCRETE CURB AND GUTTER
44-47	ROADWAY PLAN - US 12 (ELM STREET TO IL 173)	606301-04	PC CONCRETE ISLAND AND MEDIANS
48-53	ROADWAY PLAN - IL 47 (IL 120 TO IL 176)	701006-05	OFF-RD OPERATIONS 2L, 2W, 15' TO 24" FROM PAVEMENT EDGE
54	CURB OR CURB AND GUTTER REMOVAL AND REPLACEMENT (BD-24)	701011-04	OFF-RD MOVING OPERATIONS 2L, 2W, DAY ONLY
55	TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS (TC-10)	701101-04	OFF-RD OPERATIONS MULTILANE, 15' TO 24" FROM PAVEMENT EDGE
56	TYPICAL APPLICATIONS - RAISED REFLECTIVE PAVEMENT MARKERS (SNOW-PLOW RESISTANT) (TC-11)	701301-04	LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS
57	DISTRICT ONE - TYPICAL PAVEMENT MARKINGS (TC-13)	701306-03	LANE CLOSURE, 2L, 2W, SLOW MOVING OPERATIONS DAY ONLY, FOR SPEEDS > 45 MPH
58	ARTERIAL ROAD INFORMATION SIGN (TC-22)	701311-03	LANE CLOSURE, 2L, 2W MOVING OPERATIONS - DAY ONLY
		701701-09	URBAN LANE CLOSURE, MULTILANE INTERSECTION
		701801-05	SIDEWALK, CORNER OR CROSSWALK CLOSURE
		701901-03	TRAFFIC CONTROL DEVICES
		720001-01	SIGN PANEL MOUNTING DETAILS
		720006-04	SIGN PANEL ERECTION DETAILS
		720011-01	METAL POSTS FOR SIGNS, MARKERS & DELINEATORS
		729001-01	APPLICATION OF TYPES A & B METAL POSTS (FOR SIGNS & MARKERS)
		814001-02	HANDHOLES

886001-01 DETECTOR LOOP INSTALLATIONS
886006-01 TYPICAL LAYOUTS FOR DETECTOR LOOPS

BEFORE STARTING ANY EXCAVATION THE CONTRACTOR SHALL CALL "JULIE" AT 800-892-0123 OR 811 FOR BURIED ELECTRIC, TELEPHONE, AND GAS FACILITIES. (48 HOUR NOTIFICATION REQUIRED)

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.

THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH THE UTILITY COMPANIES, THE CITIES OF CRYSTAL LAKE, MARENGO, WOODSTOCK, AND THE VILLAGES OF HEBRON, AND RICHMOND.

WHEN ARTIFICIAL LIGHTING IS UTILIZED IN NIGHT OPERATIONS, THE CONTRACTOR SHALL EXERCISE THE UTMOST PRECAUTIONS IN PREVENTING ADVERSE VISABILITY TO MOTORING PUBLIC AND ADJOINING RESIDENTIAL AREAS.

ALL PAVEMENT PATCHING LOCATIONS WILL BE DETERMINED IN THE FIELD BY THE ENGINEER.

WHEN EXISTING SIDEWALK IS TO BE REMOVED WITHOUT PROPOSED SIDEWALK REPLACEMENT, IT SHALL BE REPLACED WITH TOPSOIL AND SOD.

ALL PROPOSED SIDE CURB QUANTITIES ARE INCLUDED IN THE PCC SIDEWALK 5" AND SHALL BE PAID AS SUCH.

BEFORE BEGINNING ANY WORK, THE CONTRACTOR SHALL RETAIN AND RECORD FOR FUTURE REFERENCE, ALL EXISTING PAVEMENT MARKING LINES (AND RAISED REFLECTIVE PAVEMENT MARKERS) IN ORDER THAT THESE LOCATIONS CAN BE RE-ESTABLISHED FOR STRIPING. EXACT LOCATIONS OF ALL PAVEMENT MARKINGS SHALL BE AS DIRECTED BY THE ENGINEER.

DOUBLE LANE MARKERS ARE TO BE USED AS SHOWN ON THE DISTRICT ONE DETAIL "TYPICAL APPLICATIONS - RAISED REFLECTIVE PAVEMENT MARKERS (SNOW-PLOW RESISTANT)" SHOWN IN THE PLANS.

THE RESIDENT ENGINEER SHALL CONTACT MR. WALLY CZARNY, AREA TRAFFIC FIELD ENGINEER, AT (773) 685-8386 A MINIMUM OF 2 WEEKS PRIOR TO PLACING PERMANENT PAVEMENT MARKINGS.

THE CONTRACTOR SHALL CONTACT THE DISTRICT ONE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470 A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK.

THE GENERAL CONTRACTOR IS REQUIRED TO HIRE AN ENVIRONMENT FIRM TO CONTINUOUSLY MONITOR FOR WORKER SAFETY AND SOIL CONTAMINATION AT SEVERAL LOCATIONS. SEE SPECIAL PROVISION AND SUPPLEMENTAL SPECIFICATIONS FOR DETAILS.

Rev. 2-18-14

FILE NAME: c:\pwork\p1dot\bilgramia\0362927\037714-shr-cover.dgn	USER NAME: bilgramia	DESIGNED: -	REVISED: -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	VARIOUS PEDESTRIAN RAMPS (ADA) IN MCHENRY CO. INDEX OF SHEETS, STATE STANDARDS & GENERAL NOTES	F.A. RITE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		DRAWN: -	REVISED: -			VAR	2013-0581	MCHENRY	58	2	
		CHECKED: -	REVISED: -			SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT CONTRACT NO. 60X36		
		DATE: 12/18/2013	REVISED: -								

SUMMARY OF QUANTITIES				URBAN CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES				URBAN CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE 0021					CODE NO	ITEM	UNIT	TOTAL QUANTITIES	100% STATE 0021				
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1					X6061311	CONCRETE MEDIAN SURFACE, 5 INCH	SO FT	196	196				
* 72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	11	11					Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1597	1597				
* 72400500	RELOCATE SIGN PANEL ASSEMBLY - TYPE A	EACH	11	11					Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	50	50					Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	103	103				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3296	3296					Z0076604	TRAINEES - TRAINING PROGRAM GRADUATE	HOUR	500	500				
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1309	1309													
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	583	583													
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	294	294													
* 78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	76	76													
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	4	4													
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1838	1838													
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	4	4													
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	500	500													
* 89502376	REBUILD EXISTING HANDHOLE	EACH	7	7													
X4402020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	196	196													



* 88600600 DETECTOR LOOP REPLACEMENT FOOT 500 500

* 89502376 REBUILD EXISTING HANDHOLE EACH 7 7

X4402020 CONCRETE MEDIAN SURFACE REMOVAL SQ FT 196 196

*specialty Items

Rev. 2-18-14

Rev.