

SCHEDULE OF QUANTITIES

20100110 TREE REMOVAL (6 TO 15 UNITS DIAMETER)

UNIT	LOCATION			
	IL 75			
9	Sta 409 + 91	29'	-	LT
14	Sta 410 + 42	32'	-	LT
6	Sta 411 + 31	31'	-	LT
7	Sta 411 + 31	31'	-	LT
10	Sta 411 + 31	31'	-	LT
8	Sta 411 + 31	31'	-	LT
11	Sta 412 + 02	34'	-	LT
15	Sta 412 + 58	34'	-	LT
8	Sta 412 + 58	34'	-	LT
8	Sta 412 + 58	34'	-	LT
96	TOTAL			

25000750 MOWING

ACRE	LOCATION			
	IL 75			
0.35	Sta 409 + 32.5 - 415 + 67.5			LT
0.40	Sta 409 + 32.5 - 415 + 67.5			RT
0.75	TOTAL			

28000250 TEMPORARY EROSION CONTROL SEEDING

POUND	LOCATION			
	IL 75			
70	Sta 409 + 32.5 - 415 + 67.5			LT
80	Sta 409 + 32.5 - 415 + 67.5			RT
150	TOTAL			

20100210 TREE REMOVAL (OVER 15 UNITS DIAMETER)

UNIT	LOCATION			
	IL 75			
21	Sta 409 + 85	29'	-	LT
17	Sta 411 + 22	30'	-	LT
17	Sta 411 + 95	34'	-	LT
16	Sta 412 + 58	34'	-	LT
71	TOTAL			

25100125 MULCH METHOD 3

ACRE	LOCATION			
	IL 75			
0.25	As Needed & Directed by Resident (Apply in Field Areas that is now Proposed R. O. W.)			
0.25	TOTAL			

28000305 TEMPORARY DITCH CHECKS

FOOT	LOCATION			
	IL 75			
16	Sta 410 + 25			LT
16	Sta 411 + 00			LT
16	Sta 411 + 50			LT
16	Sta 412 + 00			LT
16	Sta 412 + 50			LT
16	Sta 410 + 50			RT
16	Sta 411 + 50			RT
16	Sta 412 + 00			RT
16	Sta 412 + 50			RT
16	Sta 412 + 75			RT
16	Sta 413 + 75			RT
16	Sta 414 + 75			RT
192	TOTAL			

25100630 EROSION CONTROL BLANKET

SQ YD	LOCATION			
	IL 75			
1,694	Sta 409 + 32.5 - 415 + 67.5			LT
1,936	Sta 409 + 32.5 - 415 + 67.5			RT
3,630	TOTAL			

25000210 SEEDING, CLASS 2A

ACRE	LOCATION			
	IL 75			
0.50	Sta 409 + 32.5 - 415 + 67.5			LT
0.50	Sta 409 + 32.5 - 415 + 67.5			RT
1.00	TOTAL			

25100900 TURF REINFORCEMENT MAT

SQ YD	LOCATION			
	IL 75			
71.1	Sta 412 + 60.5			RT (Around Drop Box)
71.1	TOTAL			

28000400 PERIMETER EROSION BARRIER

FOOT	LOCATION			
	IL 75			
300	Sta 412 + 60.5 - 415 + 50			LT
300	TOTAL			