

SCHEDULE OF QUANTITIES

28000500 INLET AND PIPE PROTECTION

<u>EACH</u>	<u>LOCATION</u>
	IL 75
1	Sta 412 + 60.5 RT
1	TOTAL

28100107 STONE RIPRAP, CLASS A4

<u>SQ YD</u>	<u>LOCATION</u>
	IL 75
67	Sta 412 + 60.5 LT (20' x 30')
67	TOTAL

28200200 FILTER FABRIC

<u>SQ YD</u>	<u>LOCATION</u>
	IL 75
67	Sta 412 + 60.5 LT (20' x 30')
67	TOTAL

30300112 AGGREGATE SUBGRADE IMPROVEMENT 12"

<u>SQ YD</u>	<u>LOCATION</u>
	IL 75
465.9	Sta 410 + 00 - 415 + 00 LT
465.9	Sta 410 + 00 - 415 + 00 RT
931.8	TOTAL

40600990 TEMPORARY RAMP

<u>SQ YD</u>	<u>LOCATION</u>
	IL 75
14.4	Sta 409 + 32.5 (26' x 5')
14.4	Sta 415 + 67.5 (26' x 5')
28.8	TOTAL

44201383 CLASS C PATCHES, TYPE IV, 12 INCH

<u>SQ YD</u>	<u>LOCATION</u>
	IL 75
101.1	Sta 412 + 43 - 412 + 78 (35' x 26')
101.1	TOTAL

48102100 AGGREGATE WEDGE SHOULDER, TYPE B

<u>TON</u>	<u>LOCATION</u>
	IL 75
6	Sta 409 + 32.5 - 410 + 00 LT
6	Sta 409 + 32.5 - 410 + 00 RT
6	Sta 415 + 00 - 415 + 67.5 LT
6	Sta 415 + 00 - 415 + 67.5 RT
10	As Needed & Directed by Resident (Place Around Temporary Pavement)
34	TOTAL

50100300 REMOVAL OF EXISTING STRUCTURES NO. 1

<u>EACH</u>	<u>LOCATION</u>
	IL 75
1	Sta 412 + 60.5 (Double Cell 3'x2.5')
1	TOTAL

51500100 NAME PLATES

<u>EACH</u>	<u>LOCATION</u>
	IL 75
1	Sta 412 + 60.5
1	TOTAL

54001001 BOX CULVERT END SECTIONS, CULVERT NO. 1

<u>EACH</u>	<u>LOCATION</u>
	IL 75
1	Sta 412 + 60.5 LT
1	TOTAL

54010704 PRECAST CONCRETE BOX CULVERT 7' X 4'

<u>FOOT</u>	<u>LOCATION</u>
	IL 75
60	Sta 412 + 60.5
60	TOTAL

54215408 CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 8"

<u>EACH</u>	<u>LOCATION</u>
	IL 75
1	As Needed & Directed by the Resident
1	TOTAL

54215410 CAST-IN-PLACE REINFORCED CONCRETE END SECTIONS 10"

<u>EACH</u>	<u>LOCATION</u>
	IL 75
1	As Needed & Directed by the Resident
1	TOTAL