

# EARTHWORK SCHEDULE

EARTHWORK SCHEDULE						20200100
LOCATION	EARTH	EARTH		EARTH WORK		
	EXC	EXC ADJ	EMBANK	BALANCE	EARTH	
	(CUT)	SHRINK	(FILL)	WASTE (+)	EXCAVATION	
	25%			SHORTAGE (-)		
	CU YD	CU YD	CU YD	CU YD	CU YD	
<b>IL 75</b>						
409 + 50 - 414 + 00	1527	1145	350	795	1527	
414 + 00 - 415 + 50	240	180	91	89	240	
<b>TOTAL</b>	<b>1767</b>	<b>1325</b>	<b>441</b>	<b>884</b>	<b>1767</b>	