44. TREE PLANTING LAYOUT SHALL BE PERFORMED BY THE DISTRICT LANDSCAPE ARCHITECT, MULCH SHALL BE PLACED 4" THICK AND TO THE DIAMETER AROUND THE TREE AS SHOWN ON DISTRICT STANDARD 92.1. THE MULCH SHALL BE HARDWOOD WOOD CHIPS PLACED ON WEED BARRIER FABRIC, THIS WORK SHALL BE INCLUDED IN THE COST OF THE TREE.

45. RICHT-OF-WAY MARKERS WILL BE ERECTED PER HIGHWAY STANDARD 666001 WITH THE BACK FACE OF THE MARKER ON THE RICHT-OF-WAY LINE, UNLESS THE NEW RICHT-OF-WAY LINE HAS BEEN SURVEYED AND PINNED, IN WHICH INSTANCE THE RICHT-OF-WAY MARKERS WILL BE ERECTED 12 INCHES INSIDE THE NEW RICHT-OF-WAY LINE, THE METHOD OF INSTALLATION SHALL BE APPROVED BY THE ENGINEER.

46. CULVERT & BRIDGE FLOWS MUST BE MAINTAINED THROUGHOUT THE PROJECT. NORMAL FLOW SHALL BE ALLOWED TO PASS AT THE RATE IT ENTERS THE JOBSITE. HIGH FLOWS SHALL BE ALLOWED TO PASS WITHOUT CAUSING DAMAGE TO UPSTREAM PROPERTIES.

47. NOSES OF CURBED CORNER ISLANDS NOTED AS 1 & 2 ON HIGHWAY STANDARD 606301 SHALL BE RAMPED UNLESS THE CURB FUNCTION IS FOR THE PROTECTION OF PEDESTRIANS, SIGNALS, LIGHT STANDARDS OR SIGN TRUSS SUPPORTS,

48. THE TEMPORARY CONCRETE BARRIER SHALL BE ANCHORED TO THE PAVEMENT WITH 6 ANCHORS PER SECTION AT THE FOLLOWING LOCATIONS:

EXISTING IL 2 STA. 970+82.57 TO 974+81.58

ENCOUNTERS.

49. This work shall be done in accordance with Section 704 of the Standard Specifications. Temporary Concrete Barrier will be measured in feet along the centerline of the borrier and shall include the cost of renting/owning the barrier for the time required on the job plus houling to and from the project site, as well as one placement and removal from the roadway in occordance with Section 704 of the Standard Specification. This shall be paid for at the contract unit price per Foot for TEMPORARY CONCRETE BARRIER.

Relocate Temporary Concrete Borrier will be paid for in Feet along the centerline of the barrier, and will be paid for each time the barrier is required by staging to be picked up and moved to a different location on the project, whether it is to another location on the roadway or to a starage/staging location for the project. This shall be paid for at the contract unit price per Foot for RELOCATE TEMPORARY CONCRETE BARRIER.

GENERAL NOTES

50. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING UTILITY PROPERTY DURING CONSTRUCTION OPERATIONS AS OUTLINED IN ARTICLE 107.31 OF THE STANDARD SPECIFICATIONS. A MINIMUM OF 48 HOURS ADVANCE NOTICE IS REQUIRED FOR NON-EMERGENCY WORK, THE JULIE NUMBER IS 800-892-0123. THE FOLLOWING ARE THE KNOWN UTILITIES LOCATED WITHIN THE PROJECT LIMITS OR IMMEDIATELY ADJACENT TO THE PROJECT CONSTRUCTION LIMITS WHICH ARE MEMBERS OF JULIE:

TYDE OF

NAME AND ADDRESS OF UTILITY	TYPE OF UTILITY	TELEPHONE	MEMBER (
NORA FERNANDEZ COMMONWEALTH EDISON COMPANY 123 ENERGY AVENUE ROCKFORD, ILLINOIS 61109	ELECTRIC	(815) 490-2869	YES
KALIN HINSHAW FRONTIER 112 WEST ELM STREET SYCAMORE, ILLINOIS 60178	TELEPHONE	(815) 895-1515	YES
CONSTANCE LANE NICOR GAS CO 1844 FERRY ROAD NAPERVILLE, ILLINOIS 60563	GAS	(630) 983-8676	YES
TOM PHILIPS CHARTER COMMUNICATIONS 1348 PLAINFIELD AVENUE JANESVILLE, WISCONSIN 53547	COMMUNICATIONS	(608) 373-7538	YES
GORDON NYGREN VILLAGE OF ROCKTON 110E. MAIN STREET ROCKTON, ILLINOIS 61072	WATER & SEWER	(815) 624-7600	NO

IDOT IS NOT A MEMBER OF JULIE. IF YOU ARE NEAR ANY OVERHEAD LIGHTING, INTERSECTION LIGHTING OR TRAFFIC SIGNALS, CONTACT THE IDOT TRAFFIC OFFICE AT 815/284-5469 AT LEAST 48 HOURS PRIOR TO WORK.

51. THE APPLICABLE PORTIONS OF ARTICLE 105.07 OF THE STANDARD SPECIFICATION SHALL APPLY EXCEPT FOR THE FOLLOWING; THE CONTRACTOR SHALL BE RESPONSIBLE TO LOCATE THE VERTICAL DEPTHS OF THE UNDERGROUND UTILITIES WHICH MAY INTERFERE WITH CONSTRUCTION OPERATIONS. THIS WORK WILL NOT BE MEASURED OR PAID SEPARATELY, BUT SHALL BE CONSIDERED AS INCLUDED IN THE UNIT BID PRICE FOR THE ITEM OF CONSTRUCTION INVOLVED.

52. PER SB 699 (90 DAY UTILITY RELOCATION LAW), ONCE RIGHT-OF-WAY IS CLEAR TO AWARD THE PROJECT, A NOTICE WILL BE SENT TO THE UTILITY COMPANIES INSTRUCTING THEM TO HAVE THEIR FACILITIES RELOCATED WITHIN 90 DAYS, ESTIMATED DATE RELOCATION COMPLETE = AWARD DATE + 100 DAYS,

53. TREE PLANTING LAYOUT SHALL BE PERFORMED BY THE DISTRICT ROADSIDE MANAGEMENT SPECIALIST.
MULCH SHALL BE PLACED 40 THICK AND TO THE DIAMETER AROUND THE TREE AS SHOWN ON DISTRICT
STANDARD 92.1. THE MULCH SHALL BE HARDWOOD WOOD CHIPS PLACED ON WEED BARRIER FABRIC,
THIS WORK SHALL BE INCLUDED INTHE COST OF THE TREE.

EXCESS TREES THAT CANNOT BE PLANTED ALONG THE IL 2 PROJECT LIMITS SHALL BE PLANTED AT ALTERNATIVE LOCATIONS AS DETERMINED BY THE DISTRICT ROADSIDE MANAGEMENT SPECIALIST.

54. THE SUBGRADE ON THIS PROJECT, EXCLUSIVE OF ROCK CUT AREAS IS SCHEDULED TO BE IMPROVED TO A 12" DEPTH ACCORDING TO MECHANISTIC PAVEMENT DESIGN. THE AREAS SCHEDULED TO BE IMPROVED TO A DEPTH GREATER THAN 12" ARE ESTIMATED BASED ON THE ORIGINAL GEOTECHNICAL INVESTIGATION. THE SUBGRADE SHALL BE PROCESSED IN ACCORDANCE WITH ARTICLE 301.04 OF THE STANDARD SPECIFICATIONS BEFORE THE ENGINEER SHALL DETERMINE THE LIMITS AND THE ADDITIONAL THICKNESS OF IMPROVEMENT REQUIRED, IF ANY. ANY ADDITIONAL UNDERCUTTING REQUIRED AFTER THIS EVALUATION SHALL BE PAID FOR AS EARTH EXCAVATION.

55. THE CROSS SECTIONS SHOW AREAS WHERE EXCESS EARTH EXCAVATION FROM THIS PROJECT CAN BE STORED TO BE USED LATER ON THE FOUR LANE EXPRESSWAY. THAT IS TO BE CONSTRUCTED AT A LATER DATE. THE RESIDENT CAN STORE ADDITIONAL MATERIAL OR CHANGE LOCATION OF THIS MATERIAL IF NEEDED. THIS WORK SHALL BE INCLUDED IN THE COST OF EARTH EXCAVATION.

56. WINNEBAGO COUNTY WILL REMOVE THE CONCRETE SALT STORAGE BINS LOCATED AT STA. 1002+00 BY APRIL 1, 2014.

<u>COMMITMENTS</u>

→ ® → Z

- 1. NO TREES SHALL BE REMOVED OTHER THAN THOSE SHOWN ON THE PROJECT PLANS.
- TREES CLOSE TO THE CONSTRUCTION LIMITS SHALL BE PROTECTED WITH TREE TRUNK PROTECTION PER STANDARD SPECIFICATION SECTION 201.10(C)(2).
 THE CONTRACT SHALL CONTAIN 20 PAY ITEMS (EACH). THE EXACT LOCATION SHALL BE DETERMINED DURING A FIELD MEETING.
- MITIGATION TREES WHICH CANNOT BE PLANTED IN THE PROJECT LIMITS SHALL BE PLANTED IN WINNEBAGO COUNTY FOREST PRESERVE SITES AS DIRECTED BY THE FOREST PRESERVE SUPERINTENDENT.
- 4. TREE REMOVAL SHALL BE LIMITED BETWEEN SEPTEMBER 30 AND APRIL 1 TO AVOID IMPACTING ANY NESTING BIRDS. ONCE TREES ARE REMOVED THEY SHALL BE REPLACED WITHIN THE NESTING AREA.
- 5. CARE SHALL BE TAKEN DURING WORK BEING PERFORMED BY THE CONTRACTOR IN THE VICINITY OF THE EXISTING DRAIN FIELD LOCATED AT STA 938+75 RT. THE LOCATION OF THE DRAIN FIELD IS APPROXIMATE AND IS BASED ON A SKETCH PROVIDED BY THE PROPERTY OWNER TO THE DEPARTMENT. ANY DAMAGE INCURRED TO THE DRAIN FIELD BY THE CONTRACTOR SHALL BE REPAIRED BY THE CONTRACTOR AT NO EXPENSE TO THE DEPARTMENT OR THE PROPERTY OWNER.

LEGEND:

BOXED ITEMS INDICATE WORK NOT PAID FOR SEPARATELY, BUT INCLUDED AS PART OF ANOTHER PAY ITEM OR COST ASSOCIATED WITH THE CONTRACT,

	***************************************				1 Rev. Sheet	2-18-14		
USER NAME .	DESIGNEO - RDT	REVISED -		MILINOID DOUTE A	F.A.P.	SECTION	COUNTY	TOTAL SHEET
264H78+sht-gennote-81,dgn	DRAWN - ROT	REVISED -	STATE OF ILLINOIS		RTE.	560.7011	 	SHEETS NO.
PLOT SCALE >	CHECKED - GC	REVISED -	DEPARTMENT OF TRANSPORTATION	GENERAL NOTES AND COMMITMENTS	734	77R-1		179 5
PLOT DATE -	DATE - 10/05/2012	REVISED -		SCALE; NTS SHEET NO. 5 OF 179 SHEETS STA. TO ST.	, 	HEINOIS FED. A		NO. 64H70
Į.	14H78-sht-gennote-Eldgn UT SERLE >		CHT/8-sht-gennota-Eldgn ORAWN - RDT REVISED - LOT SEALE > CHECKED - GC REVISED -	APPROPRIATE OF ILLINOIS OF SEALE OF CHECKED - GC REVISED - STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	ANT/8-sht-gennote-Eldyn ORAWN - HOT REVISED - OLICI SEGLE > OLIC SEGLE > OLICI SEGLE > OLIC	ANTI-SPAN OF THE PROPERTY OF T	AMY8-sht-genote-El.dgo ORAWN - RDT REVISED - STATE OF ILLINOIS GENERAL NOTES AND COMMITMENTS OLD DATE - 10/05/2012 REVISED - DEPARTMENT OF TRANSPORTATION OLD DATE - 10/05/2012 REVISED - DEPARTMENT OF TRANSPORTATION	ANTIGORISH OF THE PROPERTY OF