44. TREE PLANTING LAYOUT SHALL BE PERFORMED BY THE DISTRICT LANDSCAPE ARCHITECT, MULCH SHALL BE PLACED 4" THICK AND TO THE DIAMETER AROUND THE TREE AS SHOWN ON DISTRICT STANDARD 92.1. THE MULCH SHALL BE HARDWOOD WOOD CHIPS PLACED ON WEED BARRIER FABRIC. THIS WORK SHALL BE INCLUDED IN THE COST OF THE TREE.

45. RICHT-OF-WAY MARKERS WILL BE ERECTED PER HIGHWAY STANDARD 666001 WITH THE BACK FACE OF THE MARKER ON THE RIGHT-OF-WAY LINE, UNLESS THE NEW RIGHT-OF-WAY LINE HAS BEEN SURVEYED AND PINNED, IN WHICH INSTANCE THE RIGHT-OF-WAY MARKERS WILL BE ERECTED 12 INCHES INSIDE THE NEW RIGHT-OF-WAY LINE, THE METHOD OF INSTALLATION SHALL BE APPROVED BY THE ENCINEED.

46. CULVERT & BRIDGE FLOWS MUST BE MAINTAINED THROUGHOUT THE PROJECT.

NORMAL FLOW SHALL BE ALLOWED TO PASS AT THE RATE IT ENTERS THE

JOBSITE. HIGH FLOWS SHALL BE ALLOWED TO PASS WITHOUT CAUSING DAMAGE
TO UPSTREAM PROPERTIES.

47. NOSES OF CURBED CORNER ISLANDS NOTED AS 1 & 2 ON HIGHWAY STANDARD 606301 SHALL BE RAMPED UNLESS THE CURB FUNCTION IS FOR THE PROTECTION OF PEDESTRIANS, SIGNALS, LIGHT STANDARDS OR SIGN TRUSS SUPPORTS,

48. THE TEMPORARY CONCRETE BARRIER SHALL BE ANCHORED TO THE PAVEMENT WITH 6 ANCHORS PER SECTION AT THE FOLLOWING LOCATIONS:

EXISTING IL 2 STA. 970+82.57 TO 974+81.58

ENCOUNTERS.

49. This work shall be done in accordance with Section 704 of the Standard Specifications. Temporary Concrete Barrier will be measured in feet along the centerline of the borrier and shall include the cost of renting/owning the barrier for the time required on the job plus houling to and from the project site, as well as one placement and removal from the roadway in occordance with Section 704 of the Standard Specification. This shall be paid for at the contract unit price per Foot for TEMPORARY CONCRETE BARRIER.

Relocate Temporary Concrete Barrier will be paid for in Feet along the centerline of the barrier, and will be paid for each time the barrier is required by staging to be picked up and moved to a different location on the project, whether it is to another location on the roadway or to a storage/staging location for the project. This shall be paid for at the contract unit price per Foot for RELOCATE TEMPORARY CONCRETE BARRIER.

GENERAL NOTES

50. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTING UTILITY PROPERTY DURING CONSTRUCTION OPERATIONS AS OUTLINED IN ARTICLE 107.31 OF THE STANDARD SPECIFICATIONS. A MINIMUM OF 48 HOURS ADVANCE NOTICE IS REQUIRED FOR NON-EMERGENCY WORK, THE JULIE NUMBER IS 800-892-0123. THE FOLLOWING ARE THE KNOWN UTILITIES LOCATED WITHIN THE PROJECT LIMITS OR IMMEDIATELY ADJACENT TO THE PROJECT CONSTRUCTION LIMITS WHICH ARE MEMBERS OF JULIE:

TYDE OF

NAME AND ADDRESS OF UTILITY	TYPE OF UTILITY	TELEPHONE	MEMBER (
NORA FERNANDEZ COMMONWEALTH EDISON COMPANY 123 ENERGY AVENUE ROCKFORD, ILLINOIS 61109	ELECTRIC	(815) 490-2869	YES
KALIN HINSHAW FRONTIER 112 WEST ELM STREET SYCAMORE, ILLINOIS 60178	TELEPHONE	(815) 895-1515	YES
CONSTANCE LANE NICOR GAS CO 1844 FERRY ROAD NAPERVILLE, ILLINOIS 60563	GAS	(630) 983-8676	YES
TOM PHILIPS CHARTER COMMUNICATIONS 1348 PLAINFIELD AVENUE JANESVILLE, WISCONSIN 53547	COMMUNICATIONS	(608) 373-7538	YES
GORDON NYGREN VILLAGE OF ROCKTON 110E. MAIN STREET ROCKTON, ILLINOIS 61072	WATER & SEWER	(815) 624-7600	МО

IDOT IS NOT A MEMBER OF JULIE. IF YOU ARE NEAR ANY OVERHEAD LIGHTING, INTERSECTION LIGHTING OR TRAFFIC SIGNALS, CONTACT THE IDOT TRAFFIC OFFICE AT 815/284-5469 AT LEAST 48 HOURS PRIOR TO WORK.

51. THE APPLICABLE PORTIONS OF ARTICLE 105.07 OF THE STANDARD SPECIFICATION SHALL APPLY EXCEPT FOR THE FOLLOWING; THE CONTRACTOR SHALL BE RESPONSIBLE TO LOCATE THE VERTICAL DEPTHS OF THE UNDERGROUND UTILITIES WHICH MAY INTERFERE WITH CONSTRUCTION OPERATIONS. THIS WORK WILL NOT BE MEASURED OR PAID SEPARATELY, BUT SHALL BE CONSIDERED AS INCLUDED IN THE UNIT BID PRICE FOR THE ITEM OF CONSTRUCTION INVOLVED.

52. PER SB 699 (90 DAY UTILITY RELOCATION LAW), ONCE RIGHT-OF-WAY IS CLEAR TO AWARD THE PROJECT, A NOTICE WILL BE SENT TO THE UTILITY COMPANIES INSTRUCTING THEM TO HAVE THEIR FACILITIES RELOCATED WITHIN 90 DAYS, ESTIMATED DATE RELOCATION COMPLETE = AWARD DATE + 100 DAYS,

53. TREE PLANTING LAYOUT SHALL BE PERFORMED BY THE DISTRICT ROADSIDE MANAGEMENT SPECIALIST. MULCH SHALL BE PLACED 40 THICK AND TO THE DIAMETER AROUND THE TREE AS SHOWN ON DISTRICT STANDARD 92.1. THE MULCH SHALL BE HARDWOOD WOOD CHIPS PLACED ON WEED BARRIER FABRIC. THIS WORK SHALL BE INCLUDED INTHE COST OF THE TREE.

EXCESS TREES THAT CANNOT BE PLANTED ALONG THE IL 2 PROJECT LIMITS SHALL BE PLANTED AT ALTERNATIVE LOCATIONS AS DETERMINED BY THE DISTRICT ROADSIDE MANAGEMENT SPECIALIST.

54. THE SUBGRADE ON THIS PROJECT, EXCLUSIVE OF ROCK CUT AREAS IS SCHEDULED TO BE IMPROVED TO A 12" DEPTH ACCORDING TO MECHANISTIC PAVEMENT DESIGN. THE AREAS SCHEDULED TO BE IMPROVED TO A DEPTH GREATER THAN 12" ARE ESTIMATED BASED ON THE ORIGINAL GEOTECHNICAL INVESTIGATION. THE SUBGRADE SHALL BE PROCESSED IN ACCORDANCE WITH ARTICLE 301.04 OF THE STANDARD SPECIFICATIONS BEFORE THE ENGINEER SHALL DETERMINE THE LIMITS AND THE ADDITIONAL THICKNESS OF IMPROVEMENT REQUIRED, IF ANY. ANY ADDITIONAL UNDERCUTTING REQUIRED AFTER THIS EVALUATION SHALL BE PAID FOR AS EARTH EXCAVATION.

55. THE CROSS SECTIONS SHOW AREAS WHERE EXCESS EARTH EXCAVATION FROM THIS PROJECT CAN BE STORED TO BE USED LATER ON THE FOUR LANE EXPRESSWAY THAT IS TO BE CONSTRUCTED AT A LATER DATE. THE RESIDENT CAN STORE ADDITIONAL MATERIAL OR CHANGE LOCATION OF THIS MATERIAL IF NEEDED. THIS WORK SHALL BE INCLUDED IN THE COST OF EARTH EXCAVATION.

56. WINNEBAGO COUNTY WILL REMOVE THE CONCRETE SALT STORAGE BINS LOCATED AT STA. 1002+00 BY APRIL 1, 2014.

<u>COMMITMENTS</u>

→ ® → Z

- 1. NO TREES SHALL BE REMOVED OTHER THAN THOSE SHOWN ON THE PROJECT PLANS.
- 2. TREES CLOSE TO THE CONSTRUCTION LIMITS SHALL BE PROTECTED WITH TREE TRUNK PROTECTION PER STANDARD SPECIFICATION SECTION 201.10(C)(2). THE CONTRACT SHALL CONTAIN 20 PAY ITEMS (EACH). THE EXACT LOCATION SHALL BE DETERMINED DURING A FIELD MEETING.
- MITIGATION TREES WHICH CANNOT BE PLANTED IN THE PROJECT LIMITS SHALL BE PLANTED IN WINNEBAGO COUNTY FOREST PRESERVE SITES AS DIRECTED BY THE FOREST PRESERVE SUPERINTENDENT.
- 4. TREE REMOVAL SHALL BE LIMITED BETWEEN SEPTEMBER 30 AND APRIL 1 TO AVOID IMPACTING ANY NESTING BIRDS. ONCE TREES ARE REMOVED THEY SHALL BE REPLACED WITHIN THE NESTING AREA.
- 5. CARE SHALL BE TAKEN DURING WORK BEING PERFORMED BY THE CONTRACTOR IN THE VICINITY OF THE EXISTING DRAIN FIELD LOCATED AT STA 938+75 RT. THE LOCATION OF THE DRAIN FIELD IS APPROXIMATE AND IS BASED ON A SKETCH PROVIDED BY THE PROPERTY OWNER TO THE DEPARTMENT. ANY DAMAGE INCURRED TO THE DRAIN FIELD BY THE CONTRACTOR SHALL BE REPAIRED BY THE CONTRACTOR AT NO EXPENSE TO THE DEPARTMENT OR THE PROPERTY OWNER.

LEGEND:

BOXED ITEMS INDICATE WORK NOT PAID FOR SEPARATELY, BUT INCLUDED AS PART OF ANOTHER PAY ITEM OR COST ASSOCIATED WITH THE CONTRACT,

		<u> </u>				A Rev. Sheet	2-18-14		
FILE NAME >	USER NAME .	DESIGNEO - RDT	REVISED -		WILLIAM DOUTE O	F.A.P.	SECTION	COUNTY	TOTAL SHEET
ci\px.work\px;dot\runabladarrr\dC33{847\	3264H78·sht-gennote-Bl.dgn	DRAWN - ROT	REVISED -	STATE OF ILLINOIS	ILLINOIS ROUTE 2	RIE.			SHEETS NO.
	PLOT SCALE >	CHECKED - GC	REVISED -	DEPARTMENT OF TRANSPORTATION	GENERAL NOTES AND COMMITMENTS	734	77R-1	WINNEBAGO	179 5
1	PLOT DATE :	DATE - 10/05/2012	REVISED -	DEL WILLIAM OF TUNIABLOW WINDIN				CONTRAC	T NO. 64H70
<u> </u>	rear ance	DATE - 10/03/2012	WEATSED -		SCALE: NTS SHEET NO. 5 OF 179 SHEETS STA. TO S	TA,	THE INDIS FED. A	ID PROJECT	

EARTHWORK SCHEDULE - IL 2

	LOCATI	ON	20200100 EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE 25%	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	WEATHERED	ROCK EXCAVATION, WEATHERED ADJUSTED FOR SWELL 15%	21101625 TOPSOIL FURNISH AND PLACE, 6-INCHES	21101645 TOPSOIL FURNISH AND PLACE, 12-INCHES
	10	RE-STAGE 1	CU YD	CU YD	CU YD	CU YD	CU YD	CU YD	SQ VD	SQ YD
	961+00	965+00	270	202	 	450	····	 	_	
	965 + 00	970+00	1,218	203	-50	153		ļ	533	ļ
	970+00	975+00	2,991	914	-117	797		ļ	1,444	217
		TAGE 1 SUBTOTAL	4,479	2,243 3,359	-33	2,210			667	1,239
1		STAGE 1	4,475	2,339	-200	3,159		ļ	2,644	1,456
	961 + 00	965+00	262	197	-30	167				ļ
1	965+00	970+00	7,007	5,255	-78				633	
	970 + 00	975 + 00	12,998	9,749	-33	5,177			5,541	250
ĺ	975+00	980 + 00	4,958	3,719	-576	9,716			700	1,939
	980+00	985 + 00	9,971	7,478	-819	3,143			2,844	722
	985 + 00	990 + 00	16,637	12,478	-1.807	6,659			1,089	3,850
~	990+00	995+00	7,005	5,254	~20,689	10,671	- 8	9	1,400	7,372
ROUTE	995+00	1000+00	3,960	2,970	~53,038	-15,435 -50,068	************		9,281	3,200
2	1000+00	1005+00	2,290	1,718	-17,670		···	<u> </u>	13,348	1,767
#	1005+00	1009 + 00	1,022	767	-842	-15,953 -76			8,664	2,167
		E 1 SUBTOTAL	68,110	49,583	-95,582	-46,000			3,111	
		TAGE 2		40,000	-50,002	-40,000	8	9	46,611	21,267
	965+23	970+00	1,058	794	-7	787			4.430	
	970+00	975+00	3,421	2,566	-56	2,510			1,178	733
	975+00	978+00	1,275	956		956			633 1.733	2,011
	STAG	E 2 SUBTOTAL	5,754	4,316	-63	4,253			3,544	394 3,139
		ES 2 AND 3				1,200			3,344	3,135
	994+00	1000 + 00	7,080	5.310	-45	5,265			7,544	1,650
	1900+00	1005+00	7,035	5,276	-116	5,160			3,433	1,939
	1005+00	1010+00	7,838	5,879	-371	5,508			5,683	1,022
	1010+00	1015+00	10,359	7,769	-289	7,480			4,117	5,833
	1015+00	1018+00	1,913	1,435	-128	1,307			3.222	0,000
	STAGES 2 A	ND 3 SUBTOTAL	34,225	25,669	-949	24,720				
	IL ROU	TE 2 SUBTOTAL	110,568	82,926	-96,794	-13,868	8	9	76,800	36.306
	S1	TAGE 1						<u>-</u>		74,555
AD AD	9017+66	9020+00	772	579	-209	370			911	
2	9020+00	9025+00	2,307	1,730		1,730			1,989	
ĕ	9028+00	9035+00	14,700	11,025		11,025		<u>-</u>		4,333
ROSCOE ROAD	9035+00	9040 + 00	2,549	1,912	-31	1,881				1,289
*	STAGE	1 SUBTOTAL	21,462	16,097	-240	15,857			2,900	6.206
	ROSCOE RO	AD SUBTOTAL	21,462	16,097	-240	15,857			2,900	6,206
	ST.	AGE 1A								
ROAD	2975+00	2980+00	3,326	2,495	0	2,495			1,267	394
&	2980+00	2985+00	5,446	4,085	-510	3,575			722	3,106
FRONTAGE	STAGE	1 SUBTOTAL	8,772	6,579	-510	6,069		<u>-</u>	1,989	3,500
E L		AGE 2							1	
£	2985+00	2990+00	2,725	2,844	-58	1,986			967	1,511
_ [STAGE	2 SUBTOTAL	2,725	2,044	-58	1,986		~ <u>-</u>	967	1,511
		AD SUBTOTAL	11,497	8,623	-568	8,055			2,956	5,011
	70	TAL	143,527	107,645	-97,602	10,043	8	9	82,656	47,522

EARTHWORK SUMMARY

BOADWAY	20200100 - EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE 25%	EMBANKMENT	EARTHWORK BALANCE WASTE () OR SHORTAGE (-)	204008DO - FURNISHED EXCAVATION	20200200 ROCK EXCAVATION	ROCK EXCAVATION, ADJUSTED FOR SWELL 15%	21101625 – TOPSOK FURNISH AND PLACE, 6"	21101645 - TOPSOIL FURNISH AND PLACE, 12"
	CU YD	CU YD	CU YD	CU YD	CU YD	CU YO	CU YD	SQ YD	SQ YD
IL 2 MAINLINE	110,568	82,926	-96,794	-13,868		8	9	76,800	35,306
ROSCOE ROAD	21,462	18,097	-240	15,857				2,900	6,206
FRONTAGE ROAD	11,497	8,623	-568	8,055				2,956	5,011
TOTAL	143,527	107,645	-97,602	10,043	-10,043	8	9	82,656	47,522

в	(_ : _ : : . : . :						
Į	FILE MAME :	USER NAME .	DESIGNED	-	RDT	REVISED	-
	c1/bH-k0rk/bH:dos/lopszds/d3331847/0264i		DRAWN		RDT	REVISED	-
		PLOT SCALE +	CHECKED	^	GC	REVISED	-
		PLOT DATE #	DATE	-	10/05/2012	REVISED	-

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

LANDSCAPING QUANTITIES

LOCATION		TOTAL TOPSOIL AREA PER 1500' INTERVALS	SEEDING. CLASS 2A	SEEDING. CLASS 4	SEEDING, CLASS 1	TEMPORARY EROSION CONTROL SEEDING
·····		SO YD	ACRES	ACRES	ACRES	POUNDS
	960+00 975+00	13, 578	2. 31	0.49		1, 964
IL ROUTE 2	976+00 990+00	18, 744	2.63	1.24		2, 711
IL RUUIC 2	991+00 1005+00	52, 400	10,53	0.29		7,579
-	1006+00	27,044	4.99	0, 06	0.54	3, 911
DAGAAS DAAD	9018+00	4, 744	0.87	0.11		686
ROSCOE ROAD	9028+00 9040+00	5, 661	0.85	0.32		819
FRONTAGE ROAD	2977+00 2990+00	7850	0.99	0. 63		1, 135
	TOTAL	130,022	23, 25	3, 25	0.50	18, 805
		SO YD	ACRES	ÁCRES	ACRES	POUNDS

25000100 SEEDING CLASS 1 1011+76.6 - 1018+4.4	0.50	ACRES
25000210 SEEDING CLASS ZA	23. 25	ACRES
25000310 SEEDING CLASS 4	3. 25	ACRES
25000400 NITROGEN FERTILIZER NUTRIENTS	2, 430	POLINDS
25000500 PHOSPHOROUS FERTILIZER NUTRIENTS	2, 430	POUNDS
25000600 POTASSIUM FERTILIZER NUTRIENTS	2, 430	POUNDS
25000750 MOWING	23, 75	ACRES
25100125 MULCH METHOD 3	27.00	ACRES
28000250 TEMPORARY EROSION CONTROL SEEDING	18, 805	POUNDS

EROSION CONTROL QUANTITIES

LOCATION	28000305 - TEMPORARY DITCH CHECKS (FOOT)	28000315 - AGGREGATE DITCH CHECKS (TON)	28000400 - PERIMETER EROSION BARRIER (FOOT)	28000500 - INLET AND PIPE PROTECTION (EACH)
IL 2 STA 965+00 TO 978+50 (SHT 1)	656			
IL 2 STA 978+50 TO 993+00 (SHT 2)	648	12		2
LL 2 STA 993+00 TO 1007+00 (SHT 3)	264	2	682	
IL 2 STA 1007+00 TO 1018+04, 37 (SHT 4)	80		1387	
ROSCOE STA 9017+66, 34 TO 9026+00 (SHT 5)	153		255	
ROSCOE STA 9026+00 TO 9039+60 (SHT 6)	207		261	
LATOTAL	2.008	14	2,585	1.8

NOTES: IL 2 AND ROSCOE SHEETS INCLUDE FRONTAGE ROAD QUANTITIES

SCALE: NTS

AGGREGATE MEDIAN DITCH CHECK CONVERSION TO TON, DITCH X-SECTION AREA (12 SO FT) X 2, 25'/27

RIPRAP AND FILTER FARRIC

ILLINOIS ROUTE 2

SCHEDULE OF QUANTITIES 2

TO STA.

LOCATION	28100107 - STONE RIPRAP, CLASS A4 (SO YD)	28100109 - STONE RIPRAP, CLASS A5 (SO YD)	28200200 - FILTER FABRIC
ILLINOIS ROUTE 2			3,07
985+00 LT TO 996+01,54 LT	2227		2227
988+00 RT TO 1002+00 RT	2505		2505
996+11, 18 LT		72	72
998+42, 74 RT		72	72
1001+38, 22 LT		128	128
1001+38, 22 RT		128	128
1006+40.51 RT	24		24
L015+00.00 RT	24		24
NW FRONTAGE ROAD		······································	
2987+93, 25 TO 2989+47	145		145
TOTAL	4925	400	5, 325

SHEET NO. 14 OF 179 SHEETS STA.

Rev. Sheet 2-18-14

