

LOCATION	4" YELLOW SOLID	6" WHITE SKIP DASH	4" WHITE SOLID	4" DOUBLE YELLOW	4" YELLOW SKIP DASH	8" WHITE SOLID	12" WHITE DIAG.	12" YELLOW DIAG.	24" WHITE STOP BAR	WORDS & ARROWS (RURAL)	ONEWAY RAISED REFLECTIVE PAVEMENT MARKERS, CRYSTAL	TWO-WAY RAISED REFLECTIVE PAVEMENT MARKERS, AMBER	DELINEATORS
SHT STA. TO STA.	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SO FT	EACH	EACH	EACH
IL ROUTE 2													
1 959+83.72 TO 973+00.00	305		2,633	1,589	192			80					29
2 973+00.00 TO 986+90.00	1,441		3,047	2,178		1,571	507	212		187	51	86	
3 986+90.00 TO 1000+85.00	131		2,790	518	300			7				25	2
4 1000+85.00 TO 1014+80.00	809	114	2,794		211	408	172				5	11	3
5 1014+80.00 TO 1036+15.00	2,460	714	2,460								36		3
ROSCOE ROAD													
6 9017+66.34 TO 9021+50.00	60		768	1,019	25			80				14	
2 9021+50.00 TO 9030+00.00	1,030		1,136	642		469		67	88	109	24	49	
6 9030+00.00 TO 9039+60.00	454		1,920	1,945	62	147		157		31	7	53	
CUL-DE-SAC FRONTAGE RD													
2 2976+20.83 TO 2987+35.00	199		2,017	2,275				47	24				
3 2987+35.00 TO 2990+40.00			610	610									
3 2999+25.00 TO 3000+92.68			335	335									
4 3000+92.68 TO 3006+55.00			1,125	1,125									2
<b>Totals</b>	<b>6,890</b>	<b>828</b>	<b>21,634</b>	<b>12,236</b>	<b>790</b>	<b>2,595</b>	<b>679</b>	<b>650</b>	<b>112</b>	<b>328</b>	<b>124</b>	<b>267</b>	<b>10</b>

78009000 - MODIFIED URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS	328	SO FT
78009004 - MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	41,549	FOOT
78009006 - MODIFIED URETHANE PAVEMENT MARKING - LINE 6"	828	FOOT
78009008 - MODIFIED URETHANE PAVEMENT MARKING - LINE 8"	2,595	FOOT
78009012 - MODIFIED URETHANE PAVEMENT MARKING - LINE 12"	1,329	FOOT
78009024 - MODIFIED URETHANE PAVEMENT MARKING - LINE 24"	112	FOOT
78100100 - RAISED REFLECTIVE PAVEMENT MARKERS	391	EACH
63500105 - DELINEATORS	10	EACH

78201000 - TERMINAL MARKER - DIRECT APPLIED

LOCATION	QTY (EACH)
CUL-DE-SAC FRONTAGE RD	
3000+70.00 LT	1
3002+57.50 LT	1

TERMINAL MARKER - DIRECT APPLIED, TOTAL = 2 EACH

78300100 - PAVEMENT MARKING REMOVAL

LOCATION	4" YELLOW DASH (SQ FT)	4" WHITE SOLID (SQ FT)
959+44.00 TO 973+00.00	41.4	848.3
973+00.00 TO 986+90.00	31.4	133.3
<b>TOTAL</b>	<b>73</b>	<b>982</b>

PAVEMENT MARKING REMOVAL, TOTAL = 1,054 SQ. FT.

78300200 - RAISED REFLECTOR PAVEMENT MARKER REMOVAL

LOCATION	SPACING	TWO-WAY RAISED REFLECTIVE PAVEMENT MARKERS, AMBER
SHT STA. TO STA.	FT	EACH
IL ROUTE 2		
1 960+00.00 TO 978+57.87	80	22
2 978+57.87 TO 990+40.00	80	15
3 999+25.00 TO 1005+88.94	80	9
4 1005+72.00 TO 1018+04.32	80	16

RAISED REFLECTOR PAVEMENT MARKER REMOVAL, TOTAL = 62 EACH

X0322352 - SEEDING MOBILIZATION

TOTAL SEEDING AREA (ACRES)	MAXIMUM ACRES DISTURBED (ACRES)	QUANTITIES (EACH)
27	10	3

SEEDING MOBILIZATION, TOTAL = 3 EACH

X4400110 - TEMPORARY PAVEMENT REMOVAL

LOCATION	AREA (SQ. YD.)
PRE-STAGE 1 CONSTRUCTION	
IL ROUTE 2	1,836
STAGE 1 CONSTRUCTION	
IL ROUTE 2	7,691
STAGE 1A CONSTRUCTION	
IL ROUTE 2	708
STAGE 2 CONSTRUCTION	
IL ROUTE 2	235
NW FRONTAGE ROAD	264

TEMPORARY PAVEMENT REMOVAL, TOTAL = 10,735 SQ. YD.

X5420672 - PIPE CULVERT TO BE CLEANED 72"

LOCATION	FOOT
STA. 1001+38.51 IL RTE 2	246

PIPE CULVERT TO BE CLEANED 72", TOTAL = 246 FOOT

Z0005305 - BOX CULVERT TO BE CLEANED 10X6

LOCATION	FOOT
STA. 1001+38.51 IL RTE 2	89

BOX CULVERT TO BE CLEANED, TOTAL = 89 FOOT

Z0030250 IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE) TEST LEVEL 3

LOCATION	EACH
EX. IL ROUTE 2	
970+82.57 RT	1
974+81.58 RT	1

IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3 TOTAL = 2 EACH

Z0034105 - MATERIAL TRANSFER DEVICE

AREA (SQ YD)	QUANTITIES (TONS)
22,516	13,870

MATERIAL TRANSFER DEVICE, TOTAL = 13,870 TONS

NOTE: AREA EQUALS FULL DEPTH HOT-MIX ASPHALT PAVEMENT AREA

Z0062456 - TEMPORARY PAVEMENT

LOCATION	AREA (SQ. YD.)
PRE-STAGE 1 CONSTRUCTION	
IL ROUTE 2	1,836
STAGE 1 CONSTRUCTION	
IL ROUTE 2	7,691
STAGE 1A CONSTRUCTION	
IL ROUTE 2	708
STAGE 2 CONSTRUCTION	
IL ROUTE 2	235
NW FRONTAGE ROAD	264

TEMPORARY PAVEMENT, TOTAL = 10,735 SQ. YD.

Z0025505 - PROPERTY MARKERS

LOCATION	QUANTITY (EACH)
ROSCOE ROAD	
9019+90.94 60.00' LT	1
FRONTAGE ROAD	
982+10.66 217.37' LT	1
2987+45.60 82.49' LT	1
9023+20.90 60.00' LT	1
9026+25.11 98.36' LT	1

PROPERTY MARKERS, TOTAL = 5 EACH

SEE PLAT OF HIGHWAYS FOR EXACT LOCATION OF PROPERTY MARKERS.

Z0049300 - REFERENCING LAND SECTION MARKERS

LOCATION	OFFSET	QUANTITY (EACH)
IL ROUTE 2		
977+46.02	36.13 LT	1
977+41.42	168.2 LT	1
3003+99.71	1.66' RT	1

REFERENCING LAND SECTION MARKERS, TOTAL = 3 EACH

SEE PLAT OF HIGHWAYS FOR EXACT LOCATION OF

66700305 - PERMANENT SURVEY MARKERS, TYPE II

LOCATION	EACH
(IL RTE 2) *	2

PERMANENT SURVEY MARKERS, TYPE II, TOTAL = 2 EACH

\* EXACT LOCATION WILL BE DETERMINED BY THE ENGINEER IN THE FIELD.