



REMOVALS LEGEND

	PAVEMENT REMOVAL
	PAVED SHOULDER REMOVAL
	TREE REMOVAL ACRES
	TREE REMOVAL (UNIT DIAMETER)
	FENCE REMOVAL
	GUARDRAIL REMOVAL

EXISTING UTILITIES LEGEND

	UNDERGROUND TELEPHONE LINE
	UNDERGROUND FIBER OPTIC LINE
	UNDERGROUND GAS LINE
	AERIAL LINE

EXISTING PLAN AND REMOVAL NOTES

ADDITIONAL REMOVALS SHOWN IN THE DRAINAGE PLANS.

ALL FENCE MATERIAL OTHER THAN CHAIN LINK WILL BE INCLUDED IN CLEARING.

BITUMINOUS DRIVEWAYS ON AGGREGATE BASE COURSE REMOVAL WILL BE PART OF EARTH EXCAVATION.

ANY HOT-MIX ASPHALT REMOVAL WHICH IS LESS THAN 6" IN THICKNESS WILL BE INCLUDED IN EARTH EXCAVATION.

MAILBOX LOCATIONS WILL BE UPDATED BASED ON DISTRICT 2 STANDARDS (SEE GENERAL NOTES).

FOR ROW, TEMPORARY AND PERMANENT EASEMENTS INFORMATION SEE PLAT OF HIGHWAYS.

•0.30 ACRE TREE REMOVAL

STATION	OFFSET
981+90.91	242.65' LT
982+25.53	221.51' LT
982+49.69	246.73' LT
983+03.52	205.05' LT
983+96.40	251.96' LT
984+26.63	254.33' LT
984+41.22	214.08' LT
984+96.88	261.08' LT
984+97.24	217.90' LT
985+10.19	242.12' LT

•0.50 ACRE TREE REMOVAL

STATION	OFFSET
985+33.93	347.26' LT
985+38.28	267.48' LT
985+48.47	230.70' LT
985+67.48	343.26' LT
986+01.10	224.16' LT
986+32.81	339.55' LT
987+10.25	282.48' LT
987+49.96	233.45' LT
987+93.43	247.37' LT
988+15.52	233.84' LT
988+73.70	235.60' LT
988+84.34	244.86' LT
989+69.97	241.63' LT
989+75.88	238.97' LT
989+84.18	251.34' LT
990+24.00	245.79' LT
990+24.28	239.48' LT

•4.21 ACRE TREE REMOVAL REMOVAL SHEET 2

STATION	OFFSET
985+33.20	70.44' LT
985+60.12	0.00' LT
985+72.00	84.88' RT
987+00	93.01' LT
987+63.39	177.16' LT
988+00	168.28' LT
988+00	63.79' RT
988+70.19	183.08' LT
990+26.28	186.37' LT
991+00	94.35' RT
991+67.32	189.27' LT
992+00	111.95' RT
992+99.05	196.60' LT
993+00	121.00' RT

FILE NAME = e:\pwork\p1dot\undbladerrr\d0331855\0264h70-sht-rem-02.dgn	USER NAME =	DESIGNED - RDT	REVISED -
PLOT SCALE =	CHECKED - GC	DRAWN - RDT	REVISED -
PLOT DATE	DATE - 10/05/2012		REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**ILLINOIS ROUTE 2
EXISTING PLAN AND REMOVAL SHEET 2**

SCALE: 1"=50' SHEET NO. 27 OF 179 SHEETS STA. 978+50 TO STA. 993+00

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
734	77R-1	WINNEBAGO	179	27
CONTRACT NO. 64H70				
ILLINOIS FED. AID PROJECT				