

FURNISHED EXCAVATION SCHEDULE			
LOCATION	OFFSET LT / RT	LENGTH	FURNISHED EXCAVATION
STA TO STA		FOOT	CU YD
0+00 to 2+50	LT	370	3.4
0+00 to 2+50	RT	270	2.5
2+50 to 11+47	LT	1010	9.4
2+50 to 11+47	RT	915	8.5
GRAND TOTAL		2565	24

NOTE: QUANTITIES MEASURED FROM CADD. ALL AREAS OF FURNISHED EXCAVATION SHALL BE SEEDED, FERTILIZED, AND COVERED WITH MULCH. THE SEED, FERTILIZER, AND MULCH SHALL BE INCLUDED IN THE COST OF FURNISHED EXCAVATION.

PAVEMENT MARKING SCHEDULE															
LOCATION	DISTANCE	TEMP PVT MK 4"	TEMP PVT MK 6"	TEMP PVT MK 8"	TEMP PVT MK 12"	TEMP PVT MK 24"	THERMO PVT MK 4"	THERMO PVT MK 6"	THERMO PVT MK 8"	THERMO PVT MK 12"	THERMO PVT MK 24"	SHORT- TERM MARK	WORK ZONE PAVT MARK REM	RAISED REFLECTIVE PVT MARKERS	REMOVAL RAISED REFLECTIVE PVT MARKERS
STA	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ. FT.	EACH	EACH
RURAL															
0+00 TO 11+47	1147	2500.0	340.0	332.0	106.0	140.0	2500.0	340.0	332.0	106.0	140.0	460.0	40.0	12	12
NPZ															
8+47 TO 11+47	300	600.0					600.0								
GRAND TOTALS	1447	3100	340	332	106	140	3100	340	332	106	140	460	40	12	12

(1) R.E. TO VERIFY NO PASSING ZONES PRIOR TO MILLING OPERATION