

PAVEMENT MARKING SCHEDULE														
LOCATION		THERMOPLASTIC PVMT MARKING		THERMO PVMT MARK	THERMO PVMT MARK	THERMO PVMT MARK	THERMO PVMT MARK	THERMO PVMT MARK	PAINT PVMT MARKING		PAINT PVMT MARKING	RAISED REF PVMT MARKER	RAISED REFLECT PVMT MARKER	
		WHITE 4"	YELLOW 4"	WHITE 8"	WHITE 12"	WHITE 24"	WHITE 24"	LETTERS & SYMBOLS	WHITE 4"	YELLOW 4"	YELLOW 6"	REMOVAL EACH	WHITE EACH	YELLOW EACH
		FOOT	FOOT	FOOT	FOOT	FOOT	SO FT	FOOT	FOOT	FOOT	WHITE		YELLOW	
2079+00 TO 2082+64.50	364.5	729										5		5
0+00 TO 43+50	4350	8700	876	794	65		65	156		17400		67	13	54
43+50 TO 323+00	27950								111,800	2600	13650			
MALTA RD							26							
<b>SUB TOTAL</b>		9429	876	794	65		91	156	111,800	20000	13650	72	13	59
<b>TOTAL</b>			10305	794	65		91	156		131,000	13650	72		72

THE PERMANENT PAINT PAVEMENT MARKING SHALL BE APPLIED TWICE TO INCREASE THE THICKNESS. ADDITIONAL QUANTITY HAS BEEN INCLUDED.  
NO PASSING ZONES SHALL BE REPLACED IN THE SAME LOCATIONS.

TEMPORARY PAVEMENT MARKING SCHEDULE									
LOCATION		TEMPORARY PVMT MARKING		TEMPORARY PVMT MARK	TEMPORARY PVMT MARK	TEMPORARY PVMT MARK	TEMPORARY PVMT MARK	TEMPORARY PVMT MARK	TEMPORARY PVMT MARK
		WHITE 4"	YELLOW 4"	YELLOW 6"	WHITE 8"	WHITE 12"	WHITE 24"	WHITE 24"	LETTERS & SYMBOLS
		FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	WHITE SO FT
2079+00 TO 2082+64.50	364.5	1458							
0+00 TO 43+50	4350	17400	1753		1149	98		99	312
43+50 TO 323+00	27950	111800	5200	27300					
MALTA RD								52	
<b>SUB TOTAL</b>		130658	6953	27300	1149	98		151	312
<b>TOTAL</b>			137611	27300	1149	98		151	312

\* TEMPORARY PAINT SHOULD BE APPLIED TO THE MILLED SURFACE AND ALSO AFTER THE LEVEL BINDER

SHORT-TERM PAVEMENT MARKING SCHEDULE			
LOCATION		SHORT-TERM PAVEMENT MARKING	WORK ZONE PVMT MARKING REMOVAL
		FOOT	SO FT
2079+00 TO 2082+64.50	364.5	109	36
0+00 TO 43+50	4350	1305	435
43+50 TO 323+00	27950	8385	2795
<b>TOTAL</b>		9799	3266

**STATION EQUATION**

STA 2082+64.5 BK = 0+00 AH

FILE NAME :	USER NAME = carpenterd	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULES</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.			
c:\pwwork\pavidot\carpenterd\0366282	0366036-shr-schedule.dgn	DRAWN -	REVISED -		SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	17	(124) & RS-3	DEKALB	26	10
	PLOT SCALE = 1/80,000 / in.	CHECKED -	REVISED -										CONTRACT NO. 66036		
	PLOT DATE = 12-6-2013	DATE -	REVISED -												

Key