



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

February 18, 2014

SUBJECT: FAU 7152 & FAS 1512 Route (US 150)
Project ACM-ACRS-0005(951)
Section (2X,3)RS-3 & 2RS-4
Champaign County
Contract No. 70663
Item No. 139, February 18, 2014-Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised Pages 38-40 of special provisions

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

John D. Baranzelli, P.E.
Acting Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger, P.E.".

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: J. E. Crowe, Region 3, District 5; N.R. Stoner; Matt Mueller, Tim Kell; D. Carl Puzey; Estimates

HM/kp

Method of Measurement. DUCTILE IRON WATERMAIN PIPE INSTALLATION shall be measured for payment per LINEAL FOOT.

Basis of Payment. This work will be paid for at the contract unit price per lineal foot for DUCTILE IRON WATERMAIN PIPE INSTALLATION, which price shall include all equipment, material, labor shown within the accompanying plan's, estimated schedule of quantities, and other items required to complete the construction of the water main.

STATUS OF UTILITIES TO BE ADJUSTED

The following utilities are involved in this project. The utility companies have provided the estimated dates.

<u>Name & Address of Utility</u>	<u>Type & Location</u>	<u>Estimated Date Relocation Completed</u>
Mr. Mike Murphy * AT & T Corp 201 S. Neil Street Champaign, IL 61820 (217) 398-7979 Mob: (217) 891-1793	Local telephone throughout jobsite along south ROW.	During construction
Rob Valentine * Comcast 303 Fairlawn Urbana, Il. 61801 217/383-8030 Mob: (217) 202-2644	In Conxxus conduit pack along south ROW.	During construction
Mr. Joe McKennon * Conxxus 607 S. State Street Jerseyville, IL 62052 618/498-6099 Ext 4	Conduit pack along the south ROW. No communication lines – conduit only	During construction
Mr. Mark Mills * Windstream, Inc. 102 East Shafer Street Forsyth, IL 62535 (217) 876-7194 ext 240	Fiber optic along south ROW	During construction

Revised 2/18/14

<p>Mr. Peter Folk * Volo Broadband Suite 200 312 W. Springfield Ave. Urbana, IL 61801 (217) 367-8656</p>	<p>In Conxxus conduit pack along south ROW.</p>	<p>During construction</p>
<p>Mr. Zak Horn * Metro Communications Co., Inc. 8 S. Washington Street, Suite 200 Sullivan, IL 61951 (217) 728-2827 Mob: (217) 254-6302</p>	<p>In Conxxus conduit pack along south ROW.</p>	<p>During construction</p>
<p>Mr. Shawn Spillman * Ameren Illinois 1112 West Anthony Drive P.O. Box 17070 Urbana, IL 61803-7070 (217) 383-7219 Mob: (217) 979-9316</p>	<p>6" gas - LT. 97+00 to 115+15 on public ROW.</p>	<p>Not required</p>
<p>Mr. Steve Wegman * Illinois-American Water Company Champaign County District 201 Devonshire Drive Champaign, IL 61820-7226 (217) 373-3255</p>	<p>12" water main throughout jobsite. To be relocated at various location in Roadway contract by State's Contractor</p>	<p>Required</p>
<p>Mr. Kurt Schinzler * Ameren Illinois Mail Code D-50 370 South Main Street Decatur, IL 62521 (217) 424-6734 Mob: no phone</p>	<p>4" 125# gas line CR 1975E AR 291+05+/-</p>	<p>Not required</p>
	<p>4" 125# gas line CR 2075E AR 343+95+/-</p>	<p>Not required</p>

Revised 2/18/14

Mr. Mick Braddock * Trunkline Gas Company 10483 W 600 South Ambia, IN 47917 (765) 869-5521 ext 211 Mob: (765) 714-9413	20" gas pipeline at AR 262+62+/- in 24" casing to the toe of the ditches.	Not Required
	4" gas line CR1975E AR 290+95+/-	Not Required

Mr. Zack Michael * Ameren Illinois 1112 West Anthony Drive P.O. Box 17070 Urbana, IL 61803-7070 (217) 383-7282	Aerial Electric throughout jobsite. Utility agreement UT514003 and permit #5-xxxxx	Required Required
---	--	----------------------

The above represents the best information of the Department and is only included for the convenience of the bidder. The applicable provisions of Sections 102, 103, and Articles 105.07, 107.20, 107.31, and 108.02 of the Standard Specifications for Road and Bridge Construction shall apply.

The estimated utility relocation dates should be part of the progress schedule submitted by the contractor. If any utility adjustments or relocations have not been completed by the above dates specified and when required by the contractor's operations after these dates, the contractor should notify the Engineer in writing. A request for an extension of time will be considered to the extent the Contractor's critical path schedule is affected.

Toll Free J.U.L.I.E. Telephone Number (800) 892-0123 or 811

* = J.U.L.I.E. Member

AUTOMATED FLAGGER ASSISTANCE DEVICES (BDE)

Effective: January 1, 2008

Description. This work shall consist of furnishing and operating automated flagger assistance devices (AFADs) as part of the work zone traffic control and protection for two-lane highways where two-way traffic is maintained over one lane of pavement. Use of these devices shall be at the option of the Contractor.

Revised 2/18/14