

PIATT STRUCTURE SCHEDULE OF QUANTITIES TRAFFIC CONTROL & PROTECTION

COUNTY STRUCTURES TRAFFIC CONTROL & PROTECTION SCHEDULE																			
SN			RAILROAD COORDINATION, N. A. ; MAINTENANCE ACTIVITY					TRAFFIC CONTROL & PROTECTION							PROSECUTION & PROGRESS		RURAL	URBAN	
			OWNER	DOT/AAR NO.	MILE POST	FLAGGERS	INSURANCE (RRPLI)	701400	701406	701411 (DRIVING LANE ONLY)	701201	70200000	LOC.	SUMMARY	CHANGEABLE MESSAGE SIGN (Calendar Days)	WORKING DAYS			PROSECUTION
074-0001	I-72 (EB)	IC RR					2	2				P17	4 - 701400 SET-UPS (2 DL; 2 PL) 4 - 701406 SET-UPS (2 DL; 2 PL) 2 - WD'S (1 DL; 1 PL) 2 STRUCTURES	SEE SN 0740063	2	1 DAY DRIVING LANES EB & WB; 1 DAY PASSING LANES EB & WB	X		
074-0002	I-72 (WB)	IC RR					2	2									X		
074-0005	IL 10 (FAP 721)	MADDEN CREEK									2	P6	2-701201 (1 EB; 1 WB) 1/2 - WD 1 STRUCTURE		0.5	1/4 DAY EB; 1/4 DAY WB	X		
074-0007	IL 10 (FAP 721)	I-72									2	P8	2-701201 (1 EB; 1 WB) 1/2 - WD 1 STRUCTURE		0.5	1/4 DAY EB; 1/4 DAY WB	X		
074-0013	IL 48(FAP 760)	CREEK									2	P12	2-701201 (1 NB; 1 SB) 1 - WD 2 STRUCTURES INCLUDING SN 0740081		1	1/2 DAY NB; 1/2 DAY SB	X		
074-0015	IL 48(FAP 760)	CREEK									2	P13	2-701201 (1 NB; 1 SB) 1 - WD 3 STRUCTURES INCLUDING SN 0740082		1	1/2 DAY NB; 1/2 DAY SB	X		
074-0016	IL 48(FAP 760)	CREEK									INCL.							X	
074-0021	FAS 538(BRIDGE ST)	SANGAMON RIVER									2	P19	2-701201 (1 EB; 1 WB) 1 - WD 1 STRUCTURE INCLUDING MEDIAN & RAMPS		1	1/2 DAY EB; 1/2 DAY WB		X	
074-0030	IL 105(FAP 741)	CREEK									2	P23	2-701201 (1 NB; 1 SB) 1 - WD 1 STRUCTURE		1	1/2 DAY SB ; 1/2 DAY NB	X		
074-0035	TR 87	I-72										1	P18	1-70200000 1/2 - WD 1 STRUCTURE		0.5	1/2 DAY CLOSURE	X	
074-0036	FAS 1532 (TR 154)	I-72										1	P9	1-70200000 1/2 - WD 1 STRUCTURE		0.5	1/2 DAY CLOSURE	X	
074-0040	TR 80	I-74										1	P1	1-70200000 1/2 - WD 1 STRUCTURE		0.5	1/2 DAY CLOSURE	X	
074-0041	TR 96	I-74										1	P2	1-70200000 1/2 - WD 1 STRUCTURE		0.5	1/2 DAY CLOSURE	X	
074-0044	FAS 495	I-74									2	P3	2-701201 (1 NB; 1 SB) 1 - WD 1 STRUCTURE INCLUDING MEDIAN & RAMPS		1	1/2 DAY NB; 1/2 DAY SB	X		
074-0055	IL 48 (FAP 760)	I-72									2	P14	2-701201 (1 NB; 1 SB) 1 - WD 1 STRUCTURE INCLUDING MEDIAN & RAMPS		1	1/2 DAY NB; 1/2 DAY SB	X		
074-0063	I-72 (EB)	WILDCAT CREEK					2	2				P22	4 - 701400 SET-UPS (2 DL; 2 PL) 4 - 701406 SET-UPS (2 DL; 2 PL) 2 - WD'S (1 DL; 1 PL) 2 STRUCTURES	2 - CMS (1 EB; 1 WB); 7 CALENDAR DAYS PRIOR; 6 WORKING DAYS; 13 DAYS EACH DIRECTION; TOTAL 26 CALENDAR DAYS; 6 PIATT COUNTY STRUCTURES ON FAI-72	2	1 DAY DRIVING LANES EB & WB; 1 DAY PASSING LANES EB & WB	X		
074-0064	I-72 (WB)	WILDCAT CREEK					2	2											
074-0067	I-72 (EB)	SANGAMON RIVER					2	2				P10	4 - 701400 SET-UPS (2 DL; 2 PL) 4 - 701406 SET-UPS (2 DL; 2 PL) 2 - WD'S (1 DL; 1 PL) 2 STRUCTURES		2	1 DAY DRIVING LANES EB & WB; 1 DAY PASSING LANES EB & WB		X	
074-0068	I-72 (WB)	SANGAMON RIVER					2	2											
074-0076	IL 10(FAP 721)	SANGAMON RIVER									2	P7	2-701201 (1 EB; 1 WB) 1/2 - WD 1 STRUCTURE		0.5	1/4 DAY EB; 1/4 DAY WB	X		
074-0079	IL 105(FAP 741)	CREEK									2	P21	2-701201 (1 EB; 1 WB) 1/2 - WD 1 STRUCTURE		0.5	1/4 DAY EB ; 1/4 DAY WB	X		
074-0080	IL 105(FAP 741)	STREAM									2	P20	2-701201 (1 EB; 1 WB) 1/2 - WD 1 STRUCTURE		0.5	1/4 DAY EB ; 1/4 DAY WB	X		
074-0081	IL 48(FAP 760)	STREAM										INCL.	SEE SN 0740013		INCL.	INCL.	X		
074-0082	IL 48(FAP 760)	FRIENDS CREEK DITCH										INCL.	SEE SN 0740016		INCL.	INCL.	X		
074-0084	FAS 1517(US 150)	MADDEN CREEK									2	P5	2-701201 (1 EB; 1 WB) 1/2 - WD 1 STRUCTURE		0.5	1/4 DAY EB; 1/4 DAY WB	X		
074-0086	US 150 (FAS 1517)	N & W RR	NSRR	479 064 M	131.86						2	P4	2-701201 (1 EB; 1 WB) 1/2 - WD 1 STRUCTURE		0.5	1/4 DAY EB; 1/4 DAY WB	X		
074-0087	FAS 1517 (US 150)	S BRANCH SALT CREEK									2	P11	2-701201 (1 EB; 1 WB) 1/2 - WD 1 STRUCTURE		0.5	1/4 DAY EB; 1/4 DAY WB	X		
074-2003	FAP 758(IL 32)	STREAM									2	P16	2-701201 (1 NB; 1 SB) 1/2 - WD 1 STRUCTURE		0.5	1/4 DAY SB ; 1/4 DAY NB	X		
074-3171	FAP 760 (CH 17)	SANGAMON RIVER									2	P15	2-701201 (1 NB; 1 SB) 1/2 - WD 1 STRUCTURE		0.5	1/4 DAY SB ; 1/4 DAY NB	X		

TOTAL TC&P SET-UPS; LOCATIONS; CMS CALENDAR DAYS; ESTIMATED WORKING DAYS:	12	12	0	32	4
---	----	----	---	----	---

19

•FY2014 BRIDGE DECK SEALING
•DOUGLAS, EDGAR, & PIATT COUNTIES