

SCHEDULE OF QUANTITIES

F.A.I. 74

CLASS A PATCHES, TYPE II, 17 INCH (44200637)

STATION	RUR URB	STRUCTURE/ COUNTY	DIRECTION	LANE	PRIORITY	LENGTH	WIDTH	ROUTE	AREA SQ.YD	TYPE	SAW CUTS (44213200)	TIE BARS 3/4" (44213204)	PATCHING REINFORCEMENT 44213000
											FOOT	EACH	SQ. YD
1645+51	URB	CHAMP.	EASTBOUND	DRIVING	1	10.0	12.0	I-74	13.3	II	68.0	0.0	13.3
1820+07	URB	CHAMP.	WESTBOUND	PASSING	1	6.0	12.0	I-74	8.0	II	60.0	0.0	8.0
URBAN SUB-TOTAL									22.0		128.0	0.0	22.0
1807+48	RUR	CHAMP.	WESTBOUND	PASSING	1	6.0	12.0	I-74	8.0	II	60.0	0.0	8.0
1807+48	RUR	CHAMP.	WESTBOUND	DRIVING	1	6.0	12.0	I-74	8.0	II	60.0	0.0	8.0
RURAL SUB-TOTAL									16.0		120.0	0.0	16.0
1584+84	URB	CHAMP.	WESTBOUND	DRIVING	1	10.0	12.0	I-74	13.3	II	68.0	0.0	13.3
1571+73	URB	CHAMP.	WESTBOUND	DRIVING	1	10.0	12.0	I-74	13.3	II	68.0	0.0	13.3
URBAN SUB-TOTAL									27.0		136.0	0.0	27.0
TOTAL									65.0		384.0	0.0	65.0
USE									65.0		384.0	0.0	65.0

CLASS A PATCHES, TYPE III, 17 INCH (44200641)

STATION	RUR URB	STRUCTURE/ COUNTY	DIRECTION	LANE	PRIORITY	LENGTH	WIDTH	ROUTE	AREA SQ.YD	TYPE	SAW CUTS (44213200)	TIE BARS 3/4" (44213204)	PATCHING REINFORCEMENT 44213000
											FOOT	EACH	SQ. YD
1699+88	URB	CHAMP.	EASTBOUND	DRIVING	1	15.0	12.0	I-74	20.0	III	78.0	0.0	20.0
1515+50	URB	CHAMP.	WESTBOUND	DRIVING	1	12.0	12.0	I-74	16.0	III	72.0	0.0	16.0
TOTAL									36.0		150.0	0.0	36.0
USE									36.0		150.0	0.0	36.0

CLASS A PATCHES, TYPE IV, 17 INCH (44200643)

STATION	RUR URB	STRUCTURE/ COUNTY	DIRECTION	LANE	PRIORITY	LENGTH	WIDTH	ROUTE	AREA SQ.YD	TYPE	SAW CUTS (44213200)	TIE BARS 3/4" (44213204)	PATCHING REINFORCEMENT 44213000
											FOOT	EACH	SQ. YD
1519+89	URB	CHAMP.	WESTBOUND	PASSING	3	80.0	12.0	I-74	106.7	IV	208.0	40.0	106.7
1519+89	URB	CHAMP.	WESTBOUND	DRIVING	3	80.0	12.0	I-74	106.7	IV	208.0	40.0	106.7
TOTAL									214.0		416.0	80.0	214.0
USE									214.0		416.0	80.0	214.0