

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE		
				80% FEDERAL 20% STATE ROADWAY	80% FEDERAL 20% STATE ROADWAY	80% FEDERAL 20% STATE BRIDGE
				0004	0004	0040
				ADAMS CO.	PIKE CO.	PIKE CO.
28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	275		275	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1196	149	1047	
28000315	AGGREGATE DITCH CHECKS	TON	2023	247	1776	
28000400	PERIMETER EROSION BARRIER	FOOT	5215	4563	652	
28000500	INLET AND PIPE PROTECTION	EACH	27	3	24	
28001000	AGGREGATE (EROSION CONTROL)	TON	896		896	
28100107	STONE RIPRAP, CLASS A4	SO YD	2200		2200	
28100109	STONE RIPRAP, CLASS A5	SO YD	9778		9778	
28100125	STONE RIPRAP, CLASS B3	SO YD	220		220	
28200200	FILTER FABRIC	SO YD	11008		11008	
31101000	SUBBASE GRANULAR MATERIAL, TYPE B	TON	1000	92	908	
35101400	AGGREGATE BASE COURSE, TYPE B	TON	775	19	756	
35501310	HOT-MIX ASPHALT BASE COURSE, 6 1/2"	SO YD	872	148	724	
35501324	HOT-MIX ASPHALT BASE COURSE, 10"	SO YD	2074		2074	

*SPECIALTY ITEM

FILE NAME *	USER NAME * mikel	DESIGNED - PSBA	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.S RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
Z:\NR\2810\10-013.12-IL-76 Pike Co to IL	S7\MSV8\Design\SUMMARY OF QUANTITIES.dgn	DRAWN - NEL	REVISED -					1597	14 (W, RS-7)	ADAMS/PIKE	152	4
PLOT SCALE * 100.0000 / in.	CHECKED - DBS	REVISED -			SCALE: SHEET 2 OF 10 SHEETS STA. TO STA.			ILLINOIS FED. AID PROJECT				
PLOT DATE * 8/22/2013	DATE - 08/15/2013	REVISED -										