CONTRACT 72781

F.A.S RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1597	14 (W, RS-7)	ADAMS/PIKE	152	38
STA. 1416+00.00	TO STA. 1432+00.00			
FED. ROAD DIST. NO. 6	ILLINOIS	FED. AID PROJECT		

N.E. 1/4, SEC 3, T.4S., R.7W., 4TH P.M.

CARL B. & KATHLEEN S. HENDRICKS
PARCEL NO. 6161168

SEE TR 95 INTERSECTION DETAILS FOR GEOMETRICS

S.E. 1/4, SEC 34, T.3S., R.7W., 4TH P.M.

SCALE IN FEET: 50 0 50 100

WAYNE & REX CLARK
PARCEL NO. 6161167

POTENTIAL SOIL CONTAMINATION AREA STA. 1425+40 TO 1426+90, 0' TO 50' LT

NOTE: SAVE AS MANY TREES AS POSSIBLE

SE COR SE 1/4, SEC 34, T3S, R7W

GARY E & CATHY JO AND ARLENE FESLER
PARCEL NO. 6161107

1425+85.00
67.39 LT
PR 4' BIT SHLD

SEE TR 95 (0003N) FOR CULVERT INSTALLATION DETAILS

1425+67.29
135.00 LT
EX 18" CMP TBR

1425+23.37
135.00 LT

PR TYPE A GUTTER INLET

1422+93.27
50.00 LT

STA 1423+28.3 LT
1-PRCFES 18"
FL 660.27, 28.02' LT

STA 1417+38.2
16' AGG FE

EX 12" CONC TBR

CONST LIMITS

PR TYPE A GUTTER OUTLET

SEC LINE

18" PLASTIC TBR

STA 1423+99.0
24" AGG PE

PR ROW

EX ROW

VERIZON

1425+21.28
30.00 LT

+10.0
+22.0
23'
27'

1425+00.00
50.00 LT

18" CMP TBR

48" (GAS)

68°-06'-21"

1431+40.54
50.00 LT

EX ROW

SEC LINE

PR 3' AGG SHLD

MATCHLINE STA 1416+00

1420+00

℄ FAS RTE 1597 (IL RTE 96)

1425+00

1430+00

MATCHLINE STA 1432+00

EX ROW

PR ROW

194' STORM SEWER CL A TYPE 1 24"
USFL 661.27, STA 1425+28.3, 27.9' LT
DSFL 660.30, STA 1423+34.3, 28.1' LT

PR TYPE A GUTTER

1425+00.00
40.00 RT

1425+00.00
50.00 RT

EX 15" CONC TBR

1425+37.41
30.00 RT

1425+37.20
40.00 RT

STA 1425+41.91 (IL RTE 96)
= STA 10+00.00 (TR 0003N)

COUNTY LINE
1425+38.03 ℄

NE COR NE 1/4, SEC 3, T4S, R7W

STA 1425+41.9, RT
40' P CUL, CLASS D, TYPE 1, 15"
2-MFES, 15"
USFL 662.36, STA 1425+61.9, 27.9' RT
DSFL 661.99, STA 1425+21.9, 28.1' RT

STA 1417+38.2, LT
PR PIPE CULVERT
CS/A, TY 1, 18" X 26'
USFL 655.31, STA 1417+51.2, 28.1' LT
DSFL 655.10, STA 1417+25.2, 28.8' LT

RONALD D. & BECKY K. WOODWARD
PARCEL NO. 6161165

BM "111 - SET CHSLD "□" ON S. HDW ON EAST SIDE OF IL 96 AT COUNTY LINE
STA 1425+27.7, 19.3' RT, EL = 664.83

JOHN J. & RUTH C. PETERS
PARCEL NO. 6161108

S.W. 1/4, SEC 35, T.3S., R.7W., 4TH P.M.

N.W. 1/4, SEC 2, T.4S., R.7W., 4TH P.M.

COUNTY LINE PIKE COUNTY
SEC LINE ADAMS COUNTY

STA 1425+41.9
16' AGG PE

PL

PLAN
SCANNED
PLOTTED
AS-BUILT CHECKED
R.T. OF WAY CHECKED
CADD FILE NAME
NOTE BOOK
NO. _____
BY
DATE

PROFILE
SCANNED
PLOTTED
AS-BUILT CHECKED
S.M. NOTED
STRUCTURE NOTATIONS CHKD
NOTE BOOK
NO. _____
BY
DATE

PR PROFILE GRADE
1'-4" ABOVE EX

EX PROFILE GRADE

+0.80% LT SD

STA 1418+40.0 RT SD
ELEV 655.66

+0.90% RT SD

+1.00% LT SD

STA 1423+00.0 LT SD
ELEV 659.70

STA 1423+30.0 LT SD
ELEV 660.00

MANHOLE

18" PIPE CULV

+1.00% LT SD

STA 1425+84.9 LT SD
ELEV 662.55

+1.00% RT SD

STA 1428+50.0 RT SD
ELEV 664.95

670
665
660
655
650
645
640

657.10 657.25 657.31 657.46 657.52 657.67 657.74 657.88 657.95 658.10 658.11 658.26 658.27 658.42 658.64 658.79 659.04 659.18 659.10 659.25 659.15 659.30 659.39 659.54 659.65 659.79 659.85 660.00 660.06 660.21 660.24 660.39 660.42 660.57 660.63 660.78 660.85 660.99 661.06 661.20 661.27 661.41 661.47 661.62 661.68 661.82 661.91 662.06 662.15 662.29 662.35 662.50 662.56 662.70 662.76 662.90 662.96 663.10 663.19 663.33 663.41 663.56 663.67 663.82 663.93 664.01 664.15 664.30 664.37 664.51 664.58 664.73 664.80 664.95 664.95 665.09 665.10 665.25 665.30 665.45 665.52 665.67 665.76 665.90 666.00 666.14 666.25 666.40 666.51 666.66 666.76 666.91 667.02 667.16 667.28 667.43 667.55 667.70 667.82 667.97 668.10 668.24 668.37 668.52 668.65 668.80 668.96 669.11 669.27 669.42 669.60 669.75 669.93 670.08 670.23 670.38 670.53 670.68 670.84 670.99 671.16 671.31 671.46 671.60 671.75 671.90 672.09 672.24 672.43 672.57

1416+00 1417+00 1418+00 1419+00 1420+00 1421+00 1422+00 1423+00 1424+00 1425+00 1426+00 1427+00 1428+00 1429+00 1430+00 1431+00 1432+00

FAS 1597 (IL 96) STA 1416+00 TO STA 1432+00