

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ACNHPP	ACHSIP
				CONSTRUCTION CODE	
				SMART 80/20 ROADWAY	SAFETY 90/10 ROADWAY
				0005 URBAN	0005 URBAN
40600300	AGGREGATE (PRIME COAT)	TON	79	72	7
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	612	425	187
40600990	TEMPORARY RAMP	SQ YD	100	63	37
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	690	690	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3,323	3,029	294
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	34,683	32,091	2,592
44000300	CURB REMOVAL	FOOT	836	836	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	759	759	
44003100	MEDIAN REMOVAL	SQ FT	211	211	
44004250	PAVED SHOULDER REMOVAL	SQ YD	556	391	165
44200180	PAVEMENT PATCHING, TYPE II, 15 INCH	SQ YD	120	120	
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	100	100	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	711	695	16