

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ACNHPP	ACHSIP
				CONSTRUCTION CODE	
				SMART 80/20 ROADWAY	SAFETY 90/10 ROADWAY
				0005 URBAN	0005 URBAN
48203023	HOT-MIX ASPHALT SHOULDERS, 6 1/2"	SO YD	1.478	816	662
48203100	HOT-MIX ASPHALT SHOULDERS	TON	1.069	1.008	61
50104400	CONCRETE HEADWALL REMOVAL	EACH	1		1
50300225	CONCRETE STRUCTURES	CU YD	35.3	35.3	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	3.030	3.030	
542A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"	FOOT	317		317
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	3		3
54248510	CONCRETE COLLAR	CU YD	2.5		2.5
60218300	MANHOLES, TYPE A, 4' -DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1		1
60221100	MANHOLES, TYPE A, 5' -DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1		1
60600605	CONCRETE CURB, TYPE B	FOOT	786	786	
60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	FOOT	271	271	
60609800	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.18	FOOT	6	6	
60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	361	361	

14