

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				ACHHPF	ACHSIP
				SMART 80/20 ROADWAY 0005 URBAN	SAFETY 90/10 ROADWAY 0005 URBAN
* 81603034	UNIT DUCT, 600V, 2-1C NO. 6, 1/C NO. 6 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE	FOOT	1,825		1,825
* 82103900	LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, 250 WATT	EACH	9		9
* 82500300	LIGHTING CONTROLLER, POLE MOUNTED, 240VOLT, 30AMP	EACH	2		2
* 83062730	LIGHT POLE, WEATHERING STEEL, 45 FT. M. H., TENON MOUNT	EACH	9		9
* 83600355	LIGHT POLE FOUNDATION, METAL, 15" BOLT CIRCLE, 8" X 6'	EACH	10		10
* 83800650	BREAKAWAY DEVICE, COUPLING WITH STAINLESS STEEL SCREEN	EACH	40		40
* 84200804	REMOVAL OF POLE FOUNDATION	EACH	1		1
* 84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	1		1
X4402020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	3,293	3,293	
Z0012500	CONCRETE CURB REPAIR	FOOT	50	50	
Z0016702	DETOUR SIGNING	L SUM	1	1	
Ø Z0076600	TRAINEES	HOOR	1000		1000
□ Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	3	3	
Ø Z0076604	TRAINEES TRAINING PROGRAM GRADUATE	HOOR	1000		1000
15 Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	

* SPECIALTY ITEM
 □ NON-PART. (100% STATE)
 Ø 0042

FILE NAME #	USER NAME = sparkgr	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
...	...	DRAWN -	REVISED -		SCALE:	SHEET	OF	SHEETS	STA.	TO STA.	666	1261RSJ	SANGAMON	116	9
...	...	CHECKED -	REVISED -												
...	...	DATE -	REVISED -												
Default	PLOT DATE = 06-05-2013 09:56:15AM													CONTRACT NO. 72F50	
														ILLINOIS FED. AID PROJECT	