

PAVING SCHEDULE

STATION	NB/SB	HMA BASE COURSE-10" SQ YDS	POLYMERIZED HMA SURFACE COURSE MIX "E" N90 TONS	HMA BINDER COURSE IL-19.0 FG N90 TONS	PCC SURFACE REMOVAL-BUTT JOINT SQ YDS	HMA SURFACE REMOVAL-BUTT JOINT SQ YDS	PCC SURF REMOVAL VAR. DEPTH SQ YDS	PAVED SHOULDER REMOVAL SQ YDS	HMA SHOULDERS TONS	SHOULDER RUMBLE STRIPS, 16 INCH FOOT	CLASS A PATCH TYPE II, 10" (SPECIAL) SQ YDS	CLASS A PATCH TYPE III, 10" (SPECIAL) SQ YDS	AGGREGATE WEDGE SHOULDER, TY B TONS	COMMENTS	
688+00.00	TO	693+00.00	NB	271.7	0.0	0.0	0.0	271.7	0.0	0.0	0.0	0.0	11.5	ENTRANCE RAMP FROM MOUSETTE LANE	
693+00.00	TO	699+38.00	NB	1032.0	0.0	0.0	0.0	1032.0	0.0	1038.0	0.0	0.0	33.0	INSIDE AND OUTSIDE SHOULDER	
699+38.00	TO	699+78.00	NB	71.1	18.0	0.0	160.0	71.1	8.0	80.0	0.0	0.0	1.0	BUTT JOINT	
699+78.00	TO	700+08.00	NB	53.3	13.5	0.0	0.0	53.3	6.0	60.0	24.0	0.0	1.0	APPROACH SLAB (WFBJ*)	
700+08.00	TO	748+96.00	NB	124.4	45.0	89.5	0.0	160.0	124.4	19.9	200.0	0.0	3.0	APPR. PAVT SETTLEMENT CORRECTION	
748+96.00	TO	761+17.20	NB											SEE BRIDGE PLANS	
761+17.20	TO	762+24.70	NB	166.9	48.5	96.5	0.0	0.0	166.9	26.9	215.0	0.0	3.0	APPR. PAVT SETTLEMENT CORRECTION	
762+24.70	TO	762+54.70	NB	66.7	13.5	0.0	0.0	66.7	7.5	60.0	24.0	0.0	1.0	APPROACH SLAB (WFBJ*)	
762+54.70	TO	762+94.80	NB	88.9	18.0	0.0	160.0	88.9	10.0	80.0	0.0	0.0	1.0	BUTT JOINT	
762+94.80	TO	765+30.00	NB	522.7	0.0	0.0	0.0	522.7	0.0	470.0	0.0	0.0	7.0	INSIDE AND OUTSIDE SHOULDER	
765+30.00	TO	767+16.00	NB	206.7				206.7		186.0			5.0	OUTSIDE SHOULDER	
690+54.00	TO	693+00.00	SB	273.3	0.0	0.0	0.0	273.3	0.0	246.0	0.0	0.0	7.0	OUTSIDE SHOULDER	
693+00.00	TO	699+38.00	SB	1382.3	0.0	0.0	0.0	1382.3	0.0	942.0	0.0	0.0	11.5	INSIDE AND OUTSIDE SHOULDER	
699+38.00	TO	699+78.00	SB	81.0	26.0	0.0	231.1	81.0	12.6	40.0	0.0	0.0	1.0	BUTT JOINT	
699+78.00	TO	700+08.00	SB	57.5	19.5	0.0	0.0	57.5	8.7	30.0	11.5	26.7	1.0	APPROACH SLAB (WFBJ*)	
700+08.00	TO	748+96.00	SB	77.8	65.0	140.0	0.0	160.0	77.8	19.9	100.0	0.0	3.0	APPR. PAVT SETTLEMENT CORRECTION	
748+96.00	TO	761+33.80	SB											SEE BRIDGE PLANS	
761+33.80	TO	762+41.30	SB	171.8	48.5	97.0	0.0	0.0	171.8	27.0	215.0	0.0	3.0	APPR. PAVT SETTLEMENT CORRECTION	
762+41.30	TO	762+71.30	SB	66.7	13.5	0.0	0.0	66.7	7.5	60.0	24.0	0.0	1.0	APPROACH SLAB (WFBJ*)	
762+71.30	TO	763+11.50	SB	88.9	18.0	0.0	160.0	88.9	10.0	80.0	0.0	0.0	1.0	BUTT JOINT	
763+11.50	TO	767+27.00	SB	923.3	0.0	0.0	0.0	923.3	103.4	831.0	0.0	0.0	12.0	INSIDE AND OUTSIDE SHOULDER	
SUBTOTAL				5726.9	347.0	423.0	711.1	329.9	676.1	5726.9	267.2	4933.0	83.5	26.7	107.0
ROUNDED TOTAL				5727.0	347.0	423.0	711.0	330.0	676.0	5727.0	268.0	4933.0	84.0	27.0	107.0

\*WFBJ - WIDE FLANGE BEAM JOINT

PAVEMENT MARKING SCHEDULE

STATION		THERMOPLASTIC PAVEMENT MARKING, LINE - 4" (FOOT)			TEMPORARY PAVEMENT MARKING LINE - 4" (FOOT)			SHORT TERM PAVEMENT MARKING (FOOT)	RAISED RELECTIVE PAVEMENT MARKERS (EACH)	RAISED RELECTIVE PAVEMENT MARKERS (BRIDGE) (EACH)	RAISED RELECTIVE PAVT. MRK. REMOVAL (EACH)	PAVEMENT MARKING REMOVAL SQ YDS	WORK ZONE PAVEMENT MRK. REM. (SQ FT)	COMMENT	
		SOLID WHITE	SKIP-DASH WHITE	SOLID YELLOW	SOLID WHITE	SKIP-DASH WHITE	SOLID YELLOW								
680+32.00	TO	690+32.00	140	250	0	140	250	0	115.0	25	0	25	130	38.3	NB LANE (STAGE 1)
690+32.00	TO	693+00.00	535	67	0	535	67	0	30.8	7	0	7	201	10.3	NB LANE (STAGE 1)
693+00.00	TO	695+32.00	464	58	0	464	58	0	26.7	6	0	6	174	8.9	NB LANE (STAGE 1)
695+32.00	TO	698+58.00	326	82	0	326	82	0	37.5	8	0	8	136	12.5	NB LANE (STAGE 1)
698+58.00	TO	700+11.95	154	38	0	154	38	0	40.0	4	0	4	64	13.3	NB LANE (STAGE 1)
748+00.00	TO	748+96.00	96	24	0	96	24	0	25.0	2	0	2	40	8.3	NB LANE (STAGE 1)
748+96.00	TO	755+00.00	604	151	0	604	151	0	157.0	15	15	15	252	52.3	NB LANE (STAGE 1)
755+00.00	TO	761+16.00	616	154	0	616	154	0	249.5	16	16	16	257	83.2	NB LANE (STAGE 1)
761+16.00	TO	763+20.50	205	51	0	205	51	0	82.8	5	5	5	85	27.6	NB LANE (STAGE 1)
763+20.50	TO	766+96.00	376	94	0	376	94	0	152.1	9	9	9	156	50.7	NB LANE (STAGE 1)
690+54.00	TO	693+00.00	246	62	0	246	62	0	64.0	6	6	6	103	21.3	SB LANE (STAGE 1)
693+00.00	TO	694+78.50	179	45	0	179	45	0	46.4	4	4	4	74	15.5	SB LANE (STAGE 1)
694+78.50	TO	700+11.95	533	133	0	533	133	0	138.7	13	13	13	222	46.2	SB LANE (STAGE 1)
748+00.00	TO	748+96.00	96	24	0	96	24	0	25.0	2	0	2	40	8.3	SB LANE (STAGE 1)
748+96.00	TO	755+00.00	604	151	0	604	151	0	157.0	15	15	15	252	52.3	SB LANE (STAGE 1)
755+00.00	TO	761+22.00	622	156	0	622	156	0	161.7	16	16	16	259	53.9	SB LANE (STAGE 1)
761+22.00	TO	763+91.50	217	67	0	217	67	0	70.1	7	7	7	95	23.4	SB LANE (STAGE 1)
763+91.50	TO	767+16.50	217	81	0	217	81	0	84.5	8	8	8	99	28.2	SB LANE (STAGE 1)
767+16.50	TO	770+00.00	284	71	0	284	71	0	32.6	-9	16	7	118	10.9	SB LANE (STAGE 1)
770+00.00	TO	772+16.50	217	54	0	217	54	0	24.9	5	5	5	90	8.3	SB LANE (STAGE 1)
772+16.50	TO	782+16.51	0	250	0	0	250	0	115.0	25	0	25	83	38.3	SB LANE (STAGE 1)
675+68.00	TO	678+00.00	0	58	0	0	58	0	26.7	6	0	6	19	8.9	NB LANE (STAGE 2)
678+00.00	TO	685+69.00	0	192	0	0	192	0	88.4	19	0	19	64	29.5	NB LANE (STAGE 2)
685+69.00	TO	690+68.00	0	125	500	0	125	500	57.4	12	0	12	42	19.1	NB LANE (STAGE 2)
690+68.00	TO	693+00.00	0	58	232	0	58	232	60.3	6	0	6	19	20.1	NB LANE (STAGE 2)
693+00.00	TO	698+42.50	0	136	543	0	136	543	141.1	14	0	14	45	47.0	NB LANE (STAGE 2)
698+42.50	TO	700+11.95	0	42	169	0	42	169	44.1	4	0	4	14	14.7	NB LANE (STAGE 2)
748+00.00	TO	748+96.00	0	24	96	0	24	96	25.0	2	0	2	8	8.3	NB LANE (STAGE 2)
748+96.00	TO	755+00.00	0	151	604	0	151	604	157.0	15	15	15	50	52.3	NB LANE (STAGE 2)
755+00.00	TO	761+22.00	0	156	622	0	156	622	161.7	16	16	16	52	53.9	NB LANE (STAGE 2)
761+22.00	TO	763+70.50	0	62	249	0	62	249	64.6	6	0	6	21	21.5	NB LANE (STAGE 2)
763+70.50	TO	765+96.00	0	56	226	0	56	226	58.6	6	0	6	19	19.5	NB LANE (STAGE 2)
694+56.00	TO	699+28.00	0	118	472	0	118	472	122.7	12	0	12	39	40.9	SB LANE (STAGE 2)
699+28.00	TO	700+11.95	0	21	84	0	21	84	21.8	2	0	2	7	7.3	SB LANE (STAGE 2)
748+00.00	TO	748+96.00	0	24	96	0	24	96	25.0	2	0	2	8	8.3	SB LANE (STAGE 2)
748+96.00	TO	755+00.00	0	151	604	0	151	604	157.0	15	15	15	50	52.3	SB LANE (STAGE 2)
755+00.00	TO	761+29.00	0	157	629	0	157	629	163.5	16	16	16	52	54.5	SB LANE (STAGE 2)
761+29.00	TO	765+41.50	0	103	413	0	103	413	107.3	10	0	10	34	35.8	SB LANE (STAGE 2)
765+41.50	TO	767+16.50	0	44	175	0	44	175	45.5	4	0	4	15	15.2	SB LANE (STAGE 2)
767+16.50	TO	770+00.00	0	71	284	0	71	284	32.6	7	0	7	24	10.9	SB LANE (STAGE 2)
770+00.00	TO	772+16.50	0	54	217	0	54	217	24.9	5	0	5	18	8.3	SB LANE (STAGE 2)
772+16.50	TO	782+16.50	0	250	0	0	250	0	115.0	25	0	25	83	38.3	SB LANE (STAGE 2)
SUBTOTAL			6728	4116	6212	6728	4116	6212	3536	273	139	404	3615	1179	
TOTAL			17056			17056			3536	273	139	404	3615	1179	