

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		80% FED 20% STATE 0005		
20200100	EARTH EXCAVATION	CU YD	1075	1075		
25000210	SEEDING, CLASS 2A	ACRE	1.5	1.5		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	131	131		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	131	131		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	131	131		
25100115	MULCH, METHOD 2	ACRE	6	6		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	636	636		
28000400	PERIMETER EROSION BARRIER	FOOT	544	544		
28000500	INLET AND PIPE PROTECTION	EACH	21	21		
40300200	BITUMINOUS MATERIALS (PRIME COAT)	TON	5.6	5.6		
40600300	AGGREGATE (PRIME COAT)	TON	26	26		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	989	989		
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	965	965		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		80% FED 20% STATE 0005		
40600990	TEMPORARY RAMP	SQ YD	1014	1014		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2050	2050		
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	103	103		
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	14	14		
44000400	GUTTER REMOVAL	FOOT	4902	4902		
44022027	PARTIAL DEPTH REMOVAL 2 1/2"	SQ YD	100	100		
44200069	PAVEMENT PATCHING, TYPE III, 6 INCH	SQ YD	24	24		
44200071	PAVEMENT PATCHING, TYPE IV, 6 INCH	SQ YD	23	23		
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SQ YD	506	506		
44201299	DOWEL BARS 1 1/2"	EACH	690	690		
44213200	SAW CUTS	FOOT	3105	3105		
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	4662	4662		
50105220	PIPE CULVERT REMOVAL	FOOT	80	80		
60500060	REMOVING INLETS	EACH	2	2		

FILE NAME :	USER NAME : dntelmarjn	DESIGNED -	REVISED -
o:\p\work\p\p\dot\dntelmarjn\08081061	876789-ahs-plan.dgn	DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in	CHECKED -	REVISED -
	PLOT DATE = 12/9/2013	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
312	74-JRS-1	RANDOLPH	28	3
CONTRACT NO. 76F89				
ILLINOIS FED. AID PROJECT				