

PAVEMENT MARKING SCHEDULE

LOCATION			THERMOPLASTIC PAVEMENT MARKING				RAISED REFLECTIVE PAVEMENT MARKERS	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	SHORT TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL
			4"		24"					
			SOLID WHITE	SOLID YELLOW	SKIP-DASH YELLOW CENTERLINE	SOLID WHITE STOP BARS				
STA.	TO	STA.	FOOT	FOOT	FOOT	FOOT	EACH	EACH	FOOT	SQ FT
422+67	TO	434+00	2266	100	284		14	14	113	38
434+00	TO	448+00	2177	1753	262		18	18	140	47
448+00	TO	462+00	2635	1685	278		18	18	140	47
462+00	TO	476+00	2330	50	350		18	18	140	47
476+00	TO	481+35	1070		268		7	7	54	18
ROOTS RD.			230		20	14	1	1	8	3
SUB-TOTAL			10708	3588	1462	14	74	74	595	198
TOTAL			15758			14	74	74	595	198

PERIMETER EROSION BARRIER SCHEDULE

LOCATION			RT/LT	PERIMETER EROSION BARRIER
STA.	TO	STA.		FOOT
434+00	TO	345+00	LT	172
434+00	TO	437+00	RT	372
TOTAL				544

TEMPORARY PAVEMENT MAKING MARKING SCHEDULE

LOCATION			TEMPORARY PAVEMENT MARKING			
			4"		24"	
			SOLID WHITE	SOLID YELLOW	SKIP-DASH YELLOW CENTERLINE	SOLID WHITE STOP BARS
STA.	TO	STA.	FOOT	FOOT	FOOT	FOOT
422+67	TO	481+35	2266	100	284	14
TOTAL			15758			14

INLET & PIPE PROTECTION SCHEDULE

LOCATION	RT/LT	INLET AND PIPE PROTECTION
STATION		EACH
431+11	LT	1
434+11	LT	1
436+21	LT	1
437+45	RT	1
439+31	LT	1
440+68	LT	1
444+14	LT	1
451+00	LT	1
451+81	RT	1
453+48	LT	1
454+44	LT	1
457+22	RT	1
460+17	LT	1
465+15	RT	1
466+87	LT	1
468+10	RT	1
471+18	RT	1
475+81	RT	1
474+84	RT	1
475+12	LT	1
476+51	LT	1
TOTAL		21