

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE						
				M230L	M232C	M230L	M230L	M232C	M232C	
				ROADWAY	ROADWAY	URBAN	URBAN	RURAL	RURAL	
				0005	0005	0014	0014	0040	0040	
URBAN	RURAL	S. N. 060-0129	S. N. 060-0130	S. N. 060-2455	S. N. 060-2456					
20200500	EARTH EXCAVATION (WIDENING)	CU YD	23	23						
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	220	68	152					
28100707	STONE DUMPED RIPRAP, CLASS A4	SQ YD	656	78		12	24	266	276	
35600708	HOT-MIX ASPHALT BASE COURSE WIDENING, 8"	SQ YD	958	958						
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	70	25.6	44.4					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	29.3	9.1	20.2					
40600300	AGGREGATE (PRIME COAT)	TON	140	43.5	96.5					
40600990	TEMPORARY RAMP	SQ YD	195	98	97					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	10617	3309	7211	56	41			
40800020	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.2	0.07	0.13					
40800030	AGGREGATE (PRIME COAT)	TON	1	0.35	0.65					
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	23	7.5	15.5					
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	89661	26074	63587					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	2984	2984						
44004250	PAVED SHOULDER REMOVAL	SQ YD	413	413						

FILE NAME =	USER NAME = challandeske	DESIGNED -	REVISED -
o:\pwwork\psidat\challandeske\08332817	0876G25-en-S00.dgn	DRAWN -	REVISED -
	PLOT SCALE = 100.0000' / 1"	CHECKED -	REVISED -
	PLOT DATE = 12/10/2013	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE: N/A	SHEET	OF	SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
604	003,125/RS-2, 125-BR-2	MADISON	46	3
CONTRACT NO. 76G25				
ILLINOIS FED. AID PROJECT				