

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE					
				ROADWAY	ROADWAY	URBAN BRIDGE	URBAN BRIDGE	RURAL BOX CULVERT	RURAL BOX CULVERT
				0005	0005	0014	0014	0040	0040
				S. N. 060-0129	S. N. 060-0130	S. N. 060-2455	S. N. 060-2456		
44201815	CLASS D PATCHES TYPE II, 14 INCH	SQ YD	180	106	74				
44201821	CLASS D PATCHES TYPE III, 14 INCH	SQ YD	32		32				
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	2068	600	1468				
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	11882	5013	6869				
48203100	HOT-MIX ASPHALT SHOULDERS	TON	23	1	22				
50102400	CONCRETE REMOVAL	CU YD	33.5			23.4	10.1		
50105220	PIPE CULVERT REMOVAL	FOOT	16			8	8		
50300225	CONCRETE STRUCTURES	CU YD	34.6					8.6	26
50300255	CONCRETE SUPERSTRUCTURE	CU YD	36.7			25.7	11		
50300300	PROTECTIVE COAT	SO YD	369			204	165		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	3630			2460	1170		
50800515	BAR SPLICERS	EACH	56			28	28		
52000110	PREFORMED JOINT STRIP SEAL	FOOT	199			131	68		

FILE NAME =	USER NAME = ohallandska	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
c:\pwork\projdot\ohallandska\d8332817	0876025-shr-500.dgn	DRAWN -	REVISED -		SCALE: N/A	SHEET	OF	SHEETS	STA.	TO STA.	604	(103,125)RS-2, 125-BR-2	MADISON	46	4
	PLOT SCALE = 1/8"=1'-0"	CHECKED -	REVISED -						CONTRACT NO. 76G25						
	PLOT DATE = 12/10/2013	DATE -	REVISED -						ILLINOIS FED. AID PROJECT						