

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				100% STATE	
				BRIDGE 0014	BRIDGE 0014
				042-0018	042-0019
70600332	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	1	1	
70600350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	3	1	2
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3840	1870	1970
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	20	10	10
* 78200520	BARRIER WALL MARKERS, TYPE B	EACH	8	4	4
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	8	4	4
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	20	10	10
78300100	PAVEMENT MARKING REMOVAL	SO FT	1280	623	657
X5030530	FLOOR DRAIN EXTENSION	EACH	32	20	12
X5870015	BRIDGE DECK CONCRETE SEALER	SO FT	1986	1801	185
X7010202	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321 (SPECIAL)	EACH	1	1	
Z0004556	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SO YD	1120	648	472
Z0015802	PLUG EXISTING DECK DRAINS	EACH	68	48	20
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SO YD	20	10	10

* SPECIALTY ITEM

FILE NAME *	USER NAME * ehollandako	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\p\work\p\sd\ehollandako\0348922	0076044-ah-500.dgn	DRAWN -	REVISED -		325	113BR, 113BR-1	JERSEY	33	5				
	PLOT SCALE * 1/8"=1'-0"	CHECKED -	REVISED -		SCALE: SHEET 3 OF 4 SHEETS STA. TO STA.				CONTRACT NO. 76044				
	PLOT DATE * 12/20/2013	DATE -	REVISED -		ILLINOIS FED. AID PROJECT								