

PAVEMENT MARKING SCHEDULE																	
					THERMOPLASTIC PAVEMENT MARKING			TEMPORARY PAVEMENT MARKING			WORK ZONE PAVEMENT MARKING REMOVAL SQ FT	RAISED REFLECTIVE PAVEMENT MARKER EACH	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL EACH	BARRIER WALL MARKERS TYPE B EACH	BARRIER WALL MARKERS TYPE C EACH	SHORT TERM PAVEMENT MARKING FOOT	PAVEMENT MARKING REMOVAL SQ FT
					EDGE LINE	CENTERLINE	CENTERLINE	EDGE LINE	CENTERLINE	CENTERLINE							
					SOLID 4" WHITE FOOT	SKIP-DASH 4" YELLOW FOOT	SOLID 4" YELLOW FOOT	SOLID 4" WHITE FOOT	SKIP-DASH 4" YELLOW FOOT	SOLID 4" YELLOW FOOT							
SN 042-0018																	
STA	1182+00	TO	STA	1190+00	1600.0	200.0	70	1600.00	200.00	70.00	697.0	10	10	4	4	76	623
SN 042-0019																	
STA	1253+00	TO	STA	1261+00	1600.0	200.0	170.0	1600.00	200.00	170.00	730.0	10	10	4	4	76	657
SUB-TOTAL					3200	400	240	3200	400	240	1427	20	20	8	8	152	1280
GRAND TOTAL					3,840			3,840			1,427	20	20	8	8	152	1280

EARTH EXCAVATION	
STATION	EARTH EXCAVATION
042-0018	CU YD
STAGE 1	
WEST QUADRANT	24.0
EAST QUADRANT	31.2
STAGE 2	
WEST QUADRANT	33.1
EAST QUADRANT	23.6
042-0019	
STAGE 1	
WEST QUADRANT	23.6
EAST QUADRANT	18.9
STAGE 2	
WEST QUADRANT	37.8
EAST QUADRANT	33.1
TOTAL =	225.3
ROUNDED TOTAL =	230

PAVING SCHEDULE							
STATION				BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE MATERIALS (PRIME COAT)	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	
				TON	TON	TON	
042-0018							
STA.	1185+22	TO	STA.	1185+32	0.02	0.08	4.6
STA.	1186+86	TO	STA.	1186+96	0.02	0.08	4.6
042-0019							
STA.	1256+48	TO	STA.	1256+58	0.02	0.08	4.6
STA.	1257+70	TO	STA.	1257+80	0.02	0.08	4.6
TOTAL =				0.08	0.32	18.4	
ROUNDED =				0.1	1	19 *	

* SEE STRUCTURE PLANS FOR ADDITIONAL QUANTITY.

TEMPORARY RAMP SCHEDULE				
LOCATION	WIDTH	LENGTH	TEMPORARY RAMP	
			FOOT	SQ YD
042-0018				
STAGE 1				
STA	1185+32	21.25	2	5
STA	1186+87	21.25	2	5
STAGE 2				
STA	1185+32	21.25	2	5
STA	1186+87	21.25	2	5
042-0019				
STAGE 1				
STA	1256+58	21.25	2	5
STA	1257+70	21.25	2	5
STAGE 2				
STA	1256+58	21.25	2	5
STA	1257+70	21.25	2	5
TOTAL =				40

HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT				
STATION TO STATION				SQ YD
042-0018				
	1185+22	TO	1185+32	47.2
	1186+86	TO	1186+96	47.2
042-0019				
	1256+48	TO	1256+58	47.2
	1257+70	TO	1257+80	47.2
SUB-TOTAL -				188.8
TOTAL -				189