



Note:

* Existing transverse bars extending from deck into removed area shall be cut allowing 2'-0" to extend into the removed area. In addition, these cut bars shall be cleaned, straighten, and incorporated into the new construction.

Existing reinforcement bars extending into removal area shall be cleaned, straightened and incorporated into the new construction. Any reinforcement bars that are damaged during concrete removal shall be replaced with an approved bar splicer or anchorage system. Cost included with Concrete Removal.

See sheet 6 of 11 for Section B-B.

CONCRETE REPLACEMENT

DESIGNED - A.Y.V.	EXAMINED	DATE -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	JOINT REPLACEMENT (E. ABUT.) 042-0018	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CHECKED -	ENGINEER OF STRUCTURAL SERVICES	REVIS			325	113BR, 113BR-1	Jersey	33	18
DRAWN - A.Y.V.	PASSED	REVIS	SHEET NO. 5 OF 11 SHEETS		CONTRACT NO. 76G44				
CHECKED -	ENGINEER OF BRIDGES AND STRUCTURES	REVIS			ILLINOIS FED. AID PROJECT				