

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				100% STATE
				BRIDGE 0014 S. N. 042-0012
20200100	EARTH EXCAVATION	CU YD	58.6	58.6
28100109	STONE RIPRAP, CLASS A5	SQ YD	1626	1626
28200200	FILTER FABRIC	SQ YD	1626	1626
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	263.5	263.5
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.1	0.1
40600300	AGGREGATE (PRIME COAT)	TON	1	1
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	284.4	284.4
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	135	135
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	2	2
50102400	CONCRETE REMOVAL	CU YD	9.6	9.6
50300255	CONCRETE SUPERSTRUCTURE	CU YD	10.5	10.5
50606701	CLEANING AND PAINTING STRUCTURAL STEEL, LOCATION 1	L SUM	1	1
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1140	1140
50800515	BAR SPLICERS	EACH	24	24

FILE NAME =	USER NAME = m1010m	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
er\p\work\pilot\m1010m\08341031\0876	49-ent-500.dgn	DRAWN -	REVISED -					304	4-BY, 4B-1	JERSEY	26	3
PLOT SCALE = 1/8" = 100.0000' / 1"	CHECKED -	REVISED -	SCALE:		SHEET NO. 1 OF 3 SHEETS	STA.	TO STA.	CONTRACT NO. 76049				
PLOT DATE = 12/19/2013	DATE -	REVISED -	FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT							