

STAGING SCHEDULE								
LOCATION	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	TEMPORARY RUMBLE STRIP	TEMPORARY BRIDGE TRAFFIC SIGNALS
	FOOT	FOOT	EACH	EACH	EACH	EACH	EACH	EACH
STAGE I	437.5		1		1			
STAGE II		425		1		1		
STAGE I & II							6	1
TOTAL =	437.5	425	1	1	1	1	6	1

WIDENING FOR STAGING SCHEDULE										
LOCATION	EARTH EXCAVATION					HOT-MIX ASPHALT BASE COURSE, 8"				
	LEFT SHLD		RIGHT SHLD			LEFT SHLD		RIGHT SHLD		
	WIDTH	VOLUME	WIDTH	VOLUME	WIDTH	AREA	WIDTH	AREA		
STATION TO	STATION	FOOT	CU YD	FOOT	CU YD	FOOT	SQ YD	FOOT	SQ YD	
613+10	TO 613+99.71	4	8.9	4	8.9	4	39.87	4	39.87	
616+73.29	TO 618+30	4	15.5	4	15.5	4	69.65	4	69.65	
618+30	TO 618+70	5	4.9	5	4.9	5	22.22	5	22.22	
SUBTOTAL =			29.3		29.3		131.74		131.74	
TOTAL =		58.6				263.5				

HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT SCHEDULE				
LOCATION		*WIDTH	LENGTH	HMA SURF REMOVAL - BUTT JOINT
STATION TO	STATION	FOOT	FOOT	SQ YD
613+59.71	TO 613+99.71	32	40	142.22
616+73.29	TO 617+13.29	32	40	142.22
SUBTOTAL =				284.4
TOTAL =				284.4

*INCLUDES SHOULDERS

RESURFACING SCHEDULE							
LOCATION			AGGREGATE (PRIME COAT)	BITUMINOUS MATERIALS (PRIME COAT)	HOT-MIX ASPHALT SURFACE COURSE	AGGREGATE WEDGE SHOULDERS, TY B	
STATION TO	STATION	STATION	TON	TON	TON	LT	RT
613+59.71	TO	613+99.71	0.21	0.04	13.9	0.5	0.5
614+02.21	TO	616+70.79			107		
616+73.29	TO	617+13.29	0.21	0.04	13.9	0.5	0.5
SUBTOTAL =			0.43	0.09	134.9	1.0	1.0
TOTAL =			1	0.1	135	2	

PAVEMENT MARKING SCHEDULE													
LOCATION			THERMOPLASTIC PVMT MARKING - LINE 4"			SHORT TERM PVMT MARKING	TEMPORARY PVMT MARKING - LINE 4"			PAVEMENT MARKING REMOVAL	WORK ZONE PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER
			CENTERLINE SKIP-DASH YELLOW	EDGE LINE WHITE			CENTERLINE SKIP-DASH YELLOW	EDGE LINE WHITE					
STA TO	STA	STA	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	SQ FT	EACH	EACH
611+45	TO	613+59.71	60			24	60			20	28		
613+59.71	TO	617+13.29	90	353.6	353.6	36	90	353.6	353.6		278	5	5
617+13.29	TO	620+40	90			36	90			30	42		
TOTAL =			947			104	947			50	348	5	5