

PAVEMENT MARKING SCHEDULE (CONT.)

FAP 42 (IL 13/127)

STATION TO STATION				THERMOPLASTIC PAVEMENT MARKING						TEMPORARY				NOTES
				4 INCH WHITE	4 INCH YELLOW	4 INCH (SKIP-DASH YELLOW)	12 INCH (DIAGONALS)	24 INCH (STOP BARS)	LETTERS & SYMBOLS	4 INCH	12 INCH	24 INCH	LETTERS & SYMBOLS	
				FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT	FOOT	FOOT	SQ FT	
Private Dr. Ent. - Sta. 469+47.46														
L+	469+88.0	To	483+33.0		1,345						1,345			
L+	438+10.0	To	482+75.0	4,465							4,465			
L+	470+31.0								15.6			15.6		Left Turn Arrow
L+	470+89.0								20.8			20.8		"ONLY"
R+	480+82.0								20.8			20.8		"ONLY"
R+	481+40.0								15.6			15.6		Left Turn Arrow
R+	482+38.0								20.8			20.8		"ONLY"
R+	482+96.0								15.6			15.6		Left Turn Arrow
B.R. 13/Kimmel Bridge Rd. - Sta. 483+96.44														
R+	484+45.0	To	495+30.6	1,086							1,086			
R+	484+45.0	To	495+30.6		1,086						1,086			
L+	484+60.0								15.6			15.6		Left Turn Arrow
L+	485+18.0								20.8			20.8		"ONLY"
L+	486+30.0								15.6			15.6		Left Turn Arrow
L+	486+88.0								20.8			20.8		"ONLY"
L+	484+45.0	To	495+30.6		1,086						1,086			
L+	485+40.0	To	495+30.6	991							991			
R+	487+00.0								41.5			41.5		Drop Lane Arrow
R+	489+00.0								41.5			41.5		Drop Lane Arrow
Eq. Sta. 495+30.60 (bk.) = Sta. 159+75.70														
R+	159+75.7	To	160+26.0	50		13					63			
R+	159+75.7	To	160+26.0		50						50			
L+	159+75.7	To	160+26.0		50						50			
L+	159+75.7	To	160+26.0	50		13					63			
Turn Lanes														
L+	369+03.0	To	371+21.0	218							218			Left Turn Lane
R+	407+82.0	To	410+22.0	240							240			Left Turn Lane
R+	407+82.0	To	409+80.0	198							198			Right Turn Lane
R+	409+80.0	To	410+35.0	169							169			Painted Island
L+	410+80.0	To	413+17.0	237							237			Left Turn Lane
R+	434+79.0	To	437+08.0	229							229			Left Turn Lane
L+	437+88.0	To	440+72.0	284							284			Left Turn Lane
L+	469+88.0	To	471+07.0	119							119			
R+	480+72.0	To	483+33.0	261							261			
L+	484+45.0	To	487+06.0	261							261			
R+	484+45.0	To	495+30.6				540				540			
R+	159+75.7	To	160+26.0				5				5			
Sub-Totals FAP 42				26,220	24,496	6,268	545	104	556.2	56,984	545	104	556.2	
TOTALS				56,984			545	104	556.2	56,984	545	104	556.2	

*FAP 42(IL 13/127) & FAP 885(IL 146)

FILE NAME =	USER NAME = mccordkr	DESIGNED -	REVISED -
ei:\pw_work\p\dot\mccordkr\0342339\78366-sh1.pln.dgn		DRAWN -	REVISED -
Default		CHECKED -	REVISED -
	PLOT DATE = 12/4/2013	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PAVEMENT MARKING SCHEDULE
(CONTINUED)

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	D9 PAVT PRESERV 2014-1	JACKSON/POPE	23	11
			CONTRACT NO. 78366	
ILLINOIS FED. AID PROJECT				