REMOVAL SCHEDULE

LOCATION STATION TO STATION	LENGTH	PAVEMENT REMOVAL	PAVED SHOULDER REMOVAL	COMBINATION CURB AND GUTTER REMOVAL	REMARKS
	FOOT	SQ YD	SQ YD	FOOT	
IL 13					
1819+32.35 TO 1820+67.89	135.54	241			
1820+67.89 TO 1825+00.	432.11	768	193		
1825+00. TO 1830+10.98	510.98	804	227		
POSSIBLE CURB AND GUTTER				100	REMOVAL AND REPLACEMENT TO BE USED AS DIRECTED BY THE ENGINEER
SUBTOTALS	1079	1813	420	100	

PAVEMENT AND SHOULDER SCHEDULE

LOCATION STATION TO STATION	LENGTH	SUBBASE GRANULAR MATERIAL, TYPE A 12"	SUBBASE GRANULAR MATERIAL, TYPE C	AGGREGATE SHOULDERS, TYPE B	STABILIZED SUB-BASE 4"	PORTLAND CEMENT CONCRETE PAVEMENT 10 1/2" (JOINTED)	PORTLAND CEMENT CONCRETE SHOULDERS 10 1/2"	TIE BARS 3/4"	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	PROTECTIVE COAT	REMARKS
	FOOT	SQ YD	TON	TON	SQ YD	SQ YD	SQ YD	EACH	FOOT	SQ YD	
IL 13											
1819+24.65 TO 1820+01.68	77.03	137			137	137		68		137	
1820+01.68 TO 1824+98.79	497.11	1077	25	114	967	884	166	248		1050	
1824+98.79 TO 1827+00.	201.21	436	11	46	391	358	67	100		425	
POSSIBLE CURB AND GUTTER									100		REMOVAL AND REPLACEMENT TO BE USED AS DIRECTED BT ENGINEER
SUBTOTALS	775	1650	36	160	1495	1379	233	416	100	1612	

PAVEMENT MARKING SCHEDULE

LOCATION STATION TO STATION	PAINT PAVEMENT MARKING - LINE 4"		PAINT PAVEMENT MARKING - LINE 24"	REMARKS
	WHITE SOLID	YELLOW SOLID	WHITE	
	FOOT	FOOT	FOOT	
IL 13				
1819+55			16	STOP BAR
1820+01.68 TO 1827+00.	699			OUTSIDE EOP
1819+55. 1822+40.	285			STORAGE LANE LINE
1824+40. TO 1827+00.		260		INSIDE EOP
	984	260		
TOTALS	1244		16	

FILE NAME = c:\pw_work\pwidot\pritchettll\d0356227\IL13_1-wb-sht-pln.dgn	USER NAME = pritchettll	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
Default	PLOT DATE = 12/19/2013	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: SHEET OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	D9 CM PAVEMENT REPAIR 2014-1	GALLATIN	8	7
		CONTRACT NO. 78386		
		ILLINOIS FED. AID PROJECT		