

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	UNION COUNTY	
				ROADWAY	RURAL
CONSTRUCTION TYPE CODE				80% FEDERAL ; 20% STATE 0005	
X2020110	GRADING AND SHAPING SHOULDERS	UNIT	6	6	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	805	805	
40600300	AGGREGATE (PRIME COAT)	TON	13	13	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	1	1	
40600990	TEMPORARY RAMP	SQ YD	53	53	
40603320	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N90	TON	751	751	
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	8,837	8,837	
44201773	CLASS D PATCHES, TYPE I, 11 INCH	SQ YD	127	127	
44201777	CLASS D PATCHES, TYPE II, 11 INCH	SQ YD	270	270	
44201781	CLASS D PATCHES, TYPE III, 11 INCH	SQ YD	197	197	
44201783	CLASS D PATCHES, TYPE IV, 11 INCH	SQ YD	390	390	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	6,708	6,708	
67100100	MOBILIZATION	L SUM	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2	2	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	670	670	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	12,049	12,049	
* 78001110	PAINT PAVEMENT MARKING, LINE 4"	FOOT	12,049	12,049	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	42	42	

* 78001110

20

* SPECIALTY ITEM

FILE NAME *	USER NAME * Stoverpg	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.S. RTE. 1911	SECTION 12RS-2	COUNTY UNION	TOTAL SHEETS 10	SHEET NO. 5
Default	c:\pwork\lowdot\stoverpg\d0361304\03x-xxx-Cr00.dgn	DRAWN -	REVISED -							
	PLOT SCALE * 1/8"=1'-0"	CHECKED -	REVISED -		SCALE: _____					
	PLOT DATE * 12/5/2013	DATE -	REVISED -		SHEET _____ OF _____ SHEETS					
					STA. _____ TO STA. _____					
										ILLINOIS FED. AID PROJECT CONTRACT NO. 78387