

	ROUTE ND.	SECTION	COUNTY		TOTAL SHEETS	9HIEET NO.	SHEET NO. S-2	
	P. e. I. 00/94	2626.2-0-1	~	саах		166	12 SHEETS	
		ILLINOIS	FED. ALD PROJECT-					
CONTRACT NO. 62113 INDOT DES. NO. 0100987								

INDEX OF SHEETS

SHEET TITLE NO.

S-1	General Plan
5-2	Index of Sheets, General Notes and Total Bill of Material
S-3	Plan and Elevation (1 of 6)
5-4	Plan and Elevation (2 of 6)
S-5	Plan and Elevation (3 of 6)
S-6	Plan and Elevation (4 of 6)
S-7	Plan and Elevation (5 of 6)
5-8	Plan and Elevation (6 of 6)
S-9	Wall Sections and Details
S-10	Rustication Finish Details
S-11	Boring Logs (1 of 2)
S-12	Boring Logs (2 of 2)

TOTAL BILL OF MATERIAL

ITEM	UNIT	QUANTITY	
Structure Excavation	m 3	1,284	1
Concrete Structures	m ³	498.6	1
Rustication Finish	m2	246	1
Protective Coat	m 2	208	1
Reinforcement Bars, Epoxy Coated	kg	35,620	1
Temporary Soll Retention System	m 2	328	⊢ ∕r`
Geocomposite Wall Drain	m²	258	1 -
Pipe Underdrains for Structures 150 mm	m	145.0	1
Noise Abatement Wall Anchor Rod Assembly	Each	39	1



