

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

FAI Route 80
D-3 OVD SIN STR REPL 2010-37
Bureau & LaSalle Counties
Sheet 3 of 19
Contract Number 46102

District 3
Schedule of Overhead Sign Structure Replacement

Location No.:	3-01	State I.D. No.:	3S006I080R060.7				
County:	Bureau	Route:	I-80	M.P.:	60.7	Direction:	EB
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00					
STRUCTURAL STEEL SUPPORT FOR OVERHEAD SIGN STRUCTURE	EACH	2.00					
OVERHEAD SIGN STRUCTURE-SPAN, TYPE II-A	FOOT	102.00					
REMOVE & REINSTALL SIGN PANEL	SQ FT	244.25					
REMOVE & REINSTALL WALKWAY	FOOT	35.50					
REPLACE / TIGHTEN CLIPS PER SIGN	EACH	2.00					
DISCONNECT/RECONNECT ELECTRIC SERVICE	EACH	1.00					
RELOCATE ELECTRIC SERVICE	EACH	1.00					
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	28.60					
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	2.00					
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00					
ATTENUATOR BASE	SQ YD	60.00					
IMPACT ATTENUATORS RELOCATE (NON RE-DIRECTIVE) TEST LEVEL	EACH	2.00					

Location No.:	3-02	State I.D. No.:	3S006I080L062.5				
County:	Bureau	Route:	I-80	M.P.:	62.5	Direction:	WB
Description of Work	Unit	Quantity					
REMOVE & RE-ERCT OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00					
STRUCTURAL STEEL SUPPORT FOR OVERHEAD SIGN STRUCTURE	EACH	2.00					
REPLACE / TIGHTEN CLIPS PER SIGN	EACH	2.00					
DISCONNECT/RECONNECT ELECTRIC SERVICE	EACH	1.00					
RELOCATE ELECTRIC SERVICE	EACH	1.00					
DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	25.40					
REMOVE CONCRETE FOUNDATION-OVERHEAD	EACH	2.00					
FURNISH & INSTALL INTERNAL TRUSS DAMPER	EACH	1.00					
OVERHEAD SIGN STRUCTURE WALKWAY	FOOT	89.00					
FURNISH & INSTALL SADDLE SHIM BLOCK	EACH	4.00					
ATTENUATOR BASE	SQ YD	60.00					
IMPACT ATTENUATORS RELOCATE (NON RE-DIRECTIVE) TEST LEVEL	EACH	2.00					

Location No.:	3-03	State I.D. No.:	3S050I080R078.1				
County:	LaSalle	Route:	I-80	M.P.:	78.1	Direction:	EB
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00					
OVERHEAD SIGN STRUCTURE-SPAN, TYPE II-A	FOOT	90.00					
REMOVE & REINSTALL SIGN PANEL	SQ FT	496.50					
REMOVE & REINSTALL WALKWAY	FOOT	48.00					
DISCONNECT/RECONNECT ELECTRIC SERVICE	EACH	1.00					
REPLACE / TIGHTEN CLIPS PER SIGN	EACH	3.00					
OVERHEAD SIGN SUPPORT GROUT REPAIR	EACH	4.00					
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	3.00					

Location No.:	3-04	State I.D. No.:	3S050I080L079.4				
County:	LaSalle	Route:	I-80	M.P.:	79.4	Direction:	WB
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00					
OVERHEAD SIGN STRUCTURE-SPAN, TYPE II-A	FOOT	80.00					
REMOVE & REINSTALL SIGN PANEL	SQ FT	396.25					
REMOVE & REINSTALL WALKWAY	FOOT	33.00					
DISCONNECT/RECONNECT ELECTRIC SERVICE	EACH	1.00					
REPLACE / TIGHTEN CLIPS PER SIGN	EACH	152.00					
OVERHEAD SIGN SUPPORT GROUT REPAIR	EACH	4.00					
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	2.00					

Location No.:	3-05	State I.D. No.:	3S050I080L080.0				
County:	LaSalle	Route:	I-80	M.P.:	80.0	Direction:	WB
Description of Work	Unit	Quantity					
REMOVE OVERHEAD SIGN STRUCTURE-SPAN	EACH	1.00					
OVERHEAD SIGN STRUCTURE-SPAN, TYPE II-A	FOOT	81.00					
REMOVE & REINSTALL SIGN PANEL	SQ FT	433.75					
REMOVE & REINSTALL WALKWAY	FOOT	33.00					
REPLACE / TIGHTEN CLIPS PER SIGN	EACH	1.00					
DISCONNECT/RECONNECT ELECTRIC SERVICE	EACH	1.00					
OVERHEAD SIGN SUPPORT GROUT REPAIR	EACH	4.00					
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00					

Location No.:	3-06	State I.D. No.:	3C050I080L075.2				
County:	La Salle	Route:	I-80	M.P.:	75.2	Direction:	WB
Description of Work	Unit	Quantity					
OVERHEAD SIGN SUPPORT GROUT REPAIR	EACH	1.00					
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	3.00					
TIGHTEN CANTILEVER CONNECTION	EACH	2.00					

Location No.:	3-07	State I.D. No.:	3S050I080R077.1				
County:	La Salle	Route:	I-80	M.P.:	77.1	Direction:	EB
Description of Work	Unit	Quantity					
OVERHEAD SIGN SUPPORT GROUT REPAIR	EACH	4.00					
REPLACE / TIGHTEN CLIPS PER SIGN	EACH	1.00					
FURNISH & INSTALL SAFETY CHAIN	EACH	2.00					

Location No.:	3-08	State I.D. No.:	3S050I080R077.6				
County:	La Salle	Route:	I-80	M.P.:	77.6	Direction:	EB
Description of Work	Unit	Quantity					
OVERHEAD SIGN SUPPORT GROUT REPAIR	EACH	4.00					
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	5.00					
REPLACE / TIGHTEN CLIPS PER SIGN	EACH	2.00					

Location No.:	3-09	State I.D. No.:	3C050I080L078.6				
County:	La Salle	Route:	I-80	M.P.:	78.6	Direction:	WB
Description of Work	Unit	Quantity					
OVERHEAD SIGN SUPPORT GROUT REPAIR	EACH	1.00					
REPAIR HANDRAIL LOCKING PIN CONNECTION	EACH	5.00					
TIGHTEN CANTILEVER CONNECTION	EACH	2.00					