

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

E.B. P.G.

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Back W. Abut.	644+18.47	3.00	684.93	684.93
⊘ Brg. W. Abut.	644+20.31	3.00	684.94	684.94
A	644+30.31	3.00	684.99	684.99
B	644+40.31	3.00	685.03	685.03
C	644+50.31	3.00	685.06	685.06
⊘ Brg. ⊙ Pier 1	644+61.81	3.00	685.09	685.09
D	644+71.81	3.00	685.11	685.13
E	644+81.81	3.00	685.12	685.16
F	644+91.81	3.00	685.13	685.17
G	645+01.81	3.00	685.13	685.17
H	645+11.81	3.00	685.12	685.15
I	645+21.81	3.00	685.11	685.12
⊘ Brg. ⊙ Pier 2	645+28.47	3.00	685.09	685.09
J	645+38.47	3.00	685.07	685.06
K	645+48.47	3.00	685.03	685.03
L	645+58.47	3.00	684.99	685.00
⊘ Brg. E. Abut.	645+69.97	3.00	684.94	684.94
Back E. Abut.	645+71.81	3.00	684.93	684.93

BEAM 8

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Back W. Abut.	644+18.36	7.67	684.86	684.86
⊘ Brg. W. Abut.	644+20.20	7.67	684.87	684.87
A	644+30.20	7.67	684.91	684.92
B	644+40.20	7.67	684.95	684.96
C	644+50.20	7.67	684.99	684.99
⊘ Brg. ⊙ Pier 1	644+61.70	7.67	685.02	685.02
D	644+71.70	7.67	685.04	685.06
E	644+81.70	7.67	685.05	685.08
F	644+91.70	7.67	685.06	685.10
G	645+01.70	7.67	685.05	685.10
H	645+11.70	7.67	685.05	685.08
I	645+21.70	7.67	685.03	685.04
⊘ Brg. ⊙ Pier 2	645+28.36	7.67	685.02	685.02
J	645+38.36	7.67	684.99	684.99
K	645+48.36	7.67	684.96	684.96
L	645+58.36	7.67	684.92	684.92
⊘ Brg. E. Abut.	645+69.86	7.67	684.87	684.87
Back E. Abut.	645+71.70	7.67	684.86	684.86

BEAM 9

Location	Station	Offset	Theoretical Grade Elevations	Theoretical Grade Elevations Adjusted For Dead Load Deflection
Back W. Abut.	644+18.04	14.00	684.76	684.76
⊘ Brg. W. Abut.	644+19.88	14.00	684.77	684.77
A	644+29.88	14.00	684.81	684.82
B	644+39.88	14.00	684.85	684.86
C	644+49.88	14.00	684.89	684.89
⊘ Brg. ⊙ Pier 1	644+61.38	14.00	684.92	684.92
D	644+71.38	14.00	684.94	684.96
E	644+81.38	14.00	684.95	684.98
F	644+91.38	14.00	684.96	685.00
G	645+01.38	14.00	684.96	685.00
H	645+11.38	14.00	684.95	684.98
I	645+21.38	14.00	684.93	684.95
⊘ Brg. ⊙ Pier 2	645+28.04	14.00	684.92	684.92
J	645+38.04	14.00	684.89	684.89
K	645+48.04	14.00	684.86	684.86
L	645+58.04	14.00	684.82	684.83
⊘ Brg. E. Abut.	645+69.54	14.00	684.77	684.77
Back E. Abut.	645+71.38	14.00	684.76	684.76

DESIGNED	JMT
CHECKED	BLB
DRAWN	JMT
CHECKED	BLB

TOP OF SLAB ELEVATIONS - V
STRUCTURE NO. 022-0033

rjngroup Excellence through Ownership 200 West Front Street Wheaton, IL 60187	SHEET NO. 8	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	27 SHEETS	311	10HB-R	Du Page	53	24
			CONTRACT NO. 60B92			
FED. ROAD DIST. NO. _ ILLINOIS FED. AID PROJECT						