

SUMMARY OF QUANTITIES			URBAN	80% FEDERAL, 20% STATE		SUMMARY OF QUANTITIES			URBAN	80% FEDERAL, 20% STATE	
CODE NO.	ITEM	UNIT	TOTAL	ROADWAY 1000	BOX CULVERT X028-2A	CODE NO.	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 1000	BOX CULVERT X028-2A
20200100	EARTH EXCAVATION	CU YD	284		284	44000100	PAVEMENT REMOVAL	SQ YD	599	599	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	147		147	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	22	22	
20800150	TRENCH BACKFILL	CU YD	14	14		44004250	PAVED SHOULDER REMOVAL	SQ YD	200	200	
21101815	COMPOST FURNISH AND PLACE, 4"	SQ YD	497	497		48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	472	316	156
25000310	SEEDING, CLASS 4	ACRE	0.1	0.1		50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1		1
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	9	9		50200100	STRUCTURE EXCAVATION	CU YD	240		240
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	9	9		50300300	PROTECTIVE COAT	SQ YD	15		15
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	9	9		50800105	REINFORCEMENT BARS	POUND	3523		3523
25100630	EROSION CONTROL BLANKET	SQ YD	497	497		50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	421		421
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	11	11		51500100	NAME PLATES	EACH	1		1
28000305	TEMPORARY DITCH CHECKS	FOOT	35	35		54003000	CONCRETE BOX CULVERTS	CU YD	47		47
28000400	PERIMETER EROSION BARRIER	FOOT	453	453		54010906	PRECAST CONCRETE BOX CULVERT 9'X6'	FOOT	103		103
28100107	STONE RIPRAP, CLASS A4	SQ YD	55		55	542A0220	PIPE CULVERTS, CLASS A, TYPE 1, 15"	FOOT	44	44	
28200200	FILTER FABRIC	SQ YD	111		111	54213450	END SECTIONS 15"	EACH	4	4	
31101900	SUB-BASE GRANULAR MATERIAL, TYPE C	TON	80	80		55100700	STORM SEWER REMOVAL 15"	FOOT	44	44	
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	48	48		60109641	BACKSLOPE DRAINS, TYPE 3 6"	FOOT	60		60
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	10	10		* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	380	380	
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	34		34	* 63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	44		44
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	306	215	91	* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	73	73		* 63200307	STEEL PLATE BEAM GUARD RAIL REMOVAL, ATTACHED TO STRUCTURE	FOOT	64		64

\* SPECIALTY ITEMS

**LONGO INC.**  
CONSULTING ENGINEERS  
1560 WALL ST, SUITE 222  
NAPERVILLE, ILLINOIS 60563 PH 630/577-9100

DESIGNED - MJY  
DRAWN - ST, TSC  
CHECKED - MJY, DC  
DATE - 11/23/2009

REVISED -  
REVISED -  
REVISED -  
REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES  
WEST RIVER ROAD OVER UN-NAMED TRIBUTARY TO KANKAKEE RIVER**

SCALE: NONE SHEET NO. 3 OF 17 SHEETS STA. 98+95.47 TO STA. 101+20

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0327	112 T-1	WILL	17	3
D-91-496-09			CONTRACT NO. 60654	
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

Rev.