

SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	CONSTRUCTION CODE 1000 TOTAL QUANTITY
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	88
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1055
40600300	AGGREGATE (PRIME COAT)	TON	22
x 40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	5
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	443
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	394
x 40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	886
x 42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	790
x 42400800	DETECTABLE WARNINGS	SQ FT	90
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	10547
44000600	SIDEWALK REMOVAL	SQ FT	840
x 44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	820
x 44201723	CLASS D PATCHES, TYPE IV, 6 INCH	SQ YD	391
67100100	MOBILIZATION	L SUM	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3800
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	540
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	18
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	96
x X0322256	TEMPORARY INFORMATIONAL SIGNING	SQ FT	52
x XX003435	PORTLAND CEMENT CONCRETE DRIVEWAY REMOVAL AND REPLACEMENT	SQ YD	112
x Z0017400	DRAINAGE AND UTILITY STRUCTURES TO BE ADJUSTED	EACH	13

* INDICATES SPECIALTY ITEM
 x INDICATES NON-STANDARD ITEM COVERED BY SPECIAL PROVISION

**COMBINATION
 CONCRETE CURB
 AND GUTTER REMOVAL
 AND REPLACEMENT**

STATION		LENGTH
7+40	RT	5
9+04	RT	20
9+68	LT	40
10+32	RT	30
12+54	LT	25
12+80	RT	20
13+24	RT	50
13+30	LT	10
15+26	RT	20
16+32	LT	50
16+70	RT	30
16+90	LT	50
17+06	RT	10
18+02	LT	25
18+53	LT	25
18+70	RT	20
18+96	RT	25
19+75	LT	70
19+94	RT	25
22+27	LT	25
22+36	RT	25
24+70	RT	35
25+62	LT	30
25+96	RT	25
26+12	LT	20
27+16	RT	35
27+65	RT	35
27+80	RT	20
27+80	LT	20
TOTAL = 820 FT		

STRUCTURE SCHEDULE

STATION	O/S	DRAINAGE & UTILITY STRUCTURES TO BE ADJUSTED
9+18	21' RT	T1 FRAME OPEN LID
9+84	21' RT	T1 FRAME OPEN LID
10+08	43' LT	T1 FRAME CLOSED LID
10+16	32' LT	T1 FRAME OPEN LID
10+21	26' LT	T1 FRAME OPEN LID
12+62	21' LT	T1 FRAME OPEN LID
13+46	21' RT	T1 FRAME OPEN LID
16+92	21' RT	T1 FRAME OPEN LID
16+93	33' LT	T1 FRAME CLOSED LID
17+03	21' LT	T1 FRAME OPEN LID
22+31	21' LT	T1 FRAME OPEN LID
22+55	21' RT	T1 FRAME OPEN LID
27+87	21' RT	T1 FRAME OPEN LID
27+92	21' LT	T1 FRAME OPEN LID
TOTAL = 13 EACH		

**PORTLAND CEMENT
 CONCRETE DRIVEWAY
 REMOVAL AND
 REPLACEMENT**

STATION		AREA SQ FT	AREA SQ YD
16+85	RT	100	11.1
18+14	LT	68	7.6
18+92	LT	88	9.8
19+09	RT	104	11.6
19+92	LT	112	12.4
20+06	RT	96	10.7
20+31	LT	80	8.9
22+43	LT	96	10.7
22+48	RT	88	9.8
25+76	RT	88	9.8
26+25	LT	80	8.9
TOTAL = 112.0 SY			

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
09-00027-00-RS	WILL	ILLINOIS	13	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED AID PROJECT		
C-91-727-09		ARA-M-9003(526)		

*FAU 0375 SOUTH RAVEN ROAD
 CONTRACT NO. 63326

SIDEWALK REPAIRS

STATION		SIDEWALK REMOVAL SQ FT	PCC SIDEWALK 5 INCH SQ FT	DETECTABLE WARNING
10+30	LT	52	52	6
10+30	RT	56	56	6
12+81	RT	34		
12+85	RT	44	44	6
13+25	RT	96	96	12
13+35	LT	16	66	6
16+46	LT	34		
16+46	LT	52	52	6
16+96	LT	68	68	6
17+07	LT	34		
17+11	LT	42	42	6
17+11	RT	16	66	6
27+19	RT	48		
27+19	RT	66	66	6
27+66	RT	116	116	12
27+76	LT	66	66	12
TOTALS =		840 SF	790 SF	90 SF

CLASS D PATCHES, TYPE IV 6 INCH

STATION	STATION		LENGTH FT	WIDTH FT	AREA SQ FT	AREA SQ YD
7+53	7+90	LT	37	7	259	28.8
9+90	10+05	LT	52	15	780	86.7
13+70	14+00	LT	30	15	450	50.0
14+00	14+40	LT	40	15	600	66.7
17+10	17+35	RT	25	21	525	58.3
19+30	19+60	RT	30	15	450	50.0
21+42	21+72	RT	30	15	450	50.0
TOTAL = 391.0 SY						

COPYRIGHT © 2009 BY BAXTER & WOODMAN, INC.
 #PLTDRV48
 STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM
 No. - BR 11/23/2009
 E:\Marketing\SHRMD\090303-Raven_LAPP\CADD\SURVEY\DRAWINGS\DWG\090303-S000.BHT
 4/8/2009 3:43:19 PM



USER NAME = #USER#	DESIGNED - JCH	REVISED - PER IDOT 11-23-09
FILE NAME = 090303-S000.bht	DRAWN - BCD	REVISED -
PLOT DATE = 11/23/2009	CHECKED - NJP	REVISED -
	DATE - 7-24-09	REVISED -

**VILLAGE OF SHOREWOOD, ILLINOIS
 FAU 0375 SOUTH RAVEN ROAD
 RESURFACING IMPROVEMENTS**

SUMMARY AND SCHEDULE OF QUANTITIES

SCALE: NONE

STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
09-00027-00-RS	WILL	ILLINOIS	13	3
FED. ROAD DIST. NO.		CONTRACT NO. 63326		
C-91-727-09		FED. AID PROJECT		