

SUMMARY OF QUANTITIES					PAVEMENT	MARKINGS	SIGNS	LANDSCAPE	LIGHTS	SIGNALS	TRAINING		
S.I.	CODE NO.	PAY ITEM	UNIT	QUAN	CONSTRUCTION TYPE CODE								
					1000	SFTY-1D	Y002-1C	Y003	Y030-1E	Y031	Y080		
	20101000	TEMPORARY FENCE	FOOT	3600				3600					
*	20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	74				74					
	20200100	EARTH EXCAVATION	CU YD	3165				3165					
	20200410	EARTH EXCAVATION (SPECIAL)	CU YD	500				500					
*	25200110	SODDING, SALT TOLERANT	SQ YD	1500				1500					
*	25300500	TOP SOIL FOR PLANTING	CU YD	3200				3200					
*	25300700	TRANSPLANTED SALVAGED SHRUBS	EACH	9				9					
	28000510	INLET FILTERS	EACH	20				20					
	31200600	STABILIZED SUBBASE - CEMENT AGGREGATE MIXTURE, 4"	SQ YD	136				136					
	35101100	AGGREGATE BASE COURSE, TYPE A 12"	SQ YD	100	100								
	40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	80	80								
	40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	180	180								
	44000100	PAVEMENT REMOVAL	SQ YD	100	100								
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	8100	8100								
	44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	10734	10734								
	44201353	CLASS C PATCHES, TYPE II, 10 INCH	SQ YD	100	100								
	60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	1				1					
	60107600	PIPE UNDERDRAINS 4"	FOOT	10				10					
	60109510	PIPE UNDERDRAINS, FABRIC LINED TRENCH 4"	FOOT	1525				1525					
	60201005	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 10 FRAME AND GRATE	EACH	1				1					
	60250200	CATCH BASINS TO BE ADJUSTED	EACH	10				10					
	60255500	MANHOLES TO BE ADJUSTED	EACH	5				5					
	60260100	INLETS TO BE ADJUSTED	EACH	5				5					
	60606300	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.12 (SPECIAL)	FOOT	8100	8100								
	67100100	MOBILIZATION	L SUM	1				1					
	70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1				1					
	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1				1					
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1				1					
	78000100	THERMOPLASTIC PAVEMENT MARKING- LETTERS AND SYMBOLS	SQ FT	1000	1000								
	78000200	THERMOPLASTIC PAVEMENT MARKING- LINE 4"	FOOT	8100	8100								
	78000400	THERMOPLASTIC PAVEMENT MARKING-LINE 6"	FOOT	1000	1000								
*	A2005620	TREE, OSTRYA VIRGINIANA (AMERICAN HOPHORNBEAM), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	5				5					
*	C2012136	SHRUB, VIBURNUM X JUDDII (JUDD VIBURNUM) 3' HEIGHT, BALLED AND BURLAPPED	EACH	65				65					
*	K1003680	MULCH	SQ YD	2410				2410					
	X0322903	SAW CUTTING, (FULL DEPTH)	FOOT	8300	8300								
*	X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	8100	8100								
*	X0325837	WET REFLECTIVE TEMPORARY TAPE TYPE III, 6 INCH	FOOT	2000	2000								
*	X0325842	WET REFLECTIVE TEMPORARY TAPE, TYPE III, LETTERS AND SYMBOLS	SQ FT	2000	2000								
	Z0017202	DOWEL BARS 1 1/2"	EACH	3000	3000								
	Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	LSUM	1				1					
	Z0075310	TIE BARS 3/4"	EACH	300	300								
△	Z0076600	TRAINEES	hour	500							500		
*	XX003868	WATER SERVICE CONNECTION, 2" COMPLETE	EACH	1				1					
*	XX005206	EXPLORATORY EXCAVATION	FOOT	100				100					
*	A2006618	TREE, QUERCUS IMBRICARIA (SHINGLE OAK), 2 1/2" CALIPER, BALLED AND BURLAPPED	EACH	12				12					
*	XX005653	AGGREGATE BACKFILL CA-7	CU YD	1703				1703					
	X2800400	PERIMETER EROSION BARRIER, SPECIAL	FOOT	8500				8500					

△ Y080

\* - INDICATES SPECIALTY ITEMS

FILE NAME = 09403-QUAN-01 - IDOT P01

USER NAME =	DESIGNED -	REVISIONS -
CHECKED - JSP	REVISIONS -	
PLOT SCALE =	DRAWN - PS	REVISIONS -
PLOT DATE = 11-30-09	CHECKED - AG	REVISIONS -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

HARLEM AVENUE BEAUTIFICATION - STREETSCAPING SUMMARY OF QUANTITIES		F.A.P. RTE. 348	SECTION 09-00108-00-LS	COUNTY COOK	TOTAL SHEETS 38	SHEET NO. 3
SCALE:	SHEET NO. 3 OF 38 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT ARA-00D1(809)		
CONTRACT NO. 63412						