

HIGHWAY STANDARDS

SUMMARY OF QUANTITIES

GENERAL NOTES

Item Number	Items	Y003 Quantity	Unit
701606-06	URBAN LANE CLOSURE, MULTILANE, 2W WITH MOUNTABLE MEDIAN		
42400430	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH, SPECIAL	400	SQ FT
42400460	PORTLAND CEMENT CONCRETE SIDEWALK 8 INCH , SPECIAL	1000	SQ FT
44004700	SIDEWALK REMOVAL, SPECIAL	50	SQ FT
50104600	CONCRETE RETAINING WALL REMOVAL	225	FOOT
701801-04	LANE CLOSURE, MULTILANE 1W OR 2W CROSSWALK OR SIDEWALK CLOSURE		
60266600	VALVE BOX TO BE ADJUSTED	6	EACH
60603451	PRECAST CONCRETE CURB	572	FOOT
67100100	MOBILIZATION	1	L SUM
70102625	TRAFFIC CONTROL AND PROTECTION, 701606	1	L SUM
70102640	TRAFFIC CONTROL AND PROTECTION, 701801	1	L SUM
X0322468	GAS VALVE TO BE ADJUSTED	3	EACH
X0323648	LIMESTONE MASONRY VENEER	385	SQ FT
X0325290	CORED DRAIN HOLES	56	EACH
X0326522	PRECAST MODULAR RETAINING WALL	234	FOOT
X0540000	BRICK PAVERS	20	SQ FT
XX000959	TRASH RECEPTACLE	6	EACH
XX001621	BRICK PAVER REMOVAL	1024	SQ FT
XX003313	REMOVE AND REINSTALL BRICK PAVER	307	SQ FT
44001760	COMBINATION CONCRETE CURB & GUTTER REMOVAL & REPLACEMENT	50	FOOT
XX003668	PRE-CONSTRUCTION VIDEO TAPING	1	L SUM
XX004101	ORNAMENTAL METAL FENCE	168	FOOT
X0444100	BENCHES	6	EACH
XX005963	ANTI-GRAFFITI COATING	1450	SQ FT
Z0013798	CONSTRUCTION LAYOUT	1	L SUM
Z0034100	MASONRY WALL CONSTRUCTION	252	SQ FT

\* Indicates specialty item  
 ^ Indicates special provision

NOTE: BOXED NOTES INDICATE INCIDENTAL ITEMS OF WORK.

7. THE RESIDENT ENGINEER SHALL CONTACT THE TRAFFIC CONTROL SUPERVISOR AT 847-705-4470 A MINIMUM OF 72 HOURS PRIOR TO THE PLACEMENT OF ANY TEMPORARY TRAFFIC CONTROL DEVICES.

4. THE CONTRACTOR WILL BE REQUIRED TO DISPOSE OF ALL SIDEWALK, CURB AND GUTTER, PAVEMENT, AND ALL OTHER MATERIALS EXCAVATED OR REMOVED DUE TO CONSTRUCTION OPERATIONS. ALL EXCESS EXCAVATED MATERIAL SHALL BE REMOVED FROM SITE ON THE DAY IT IS EXCAVATED. HAULING OR TRUCKING THE MATERIAL TO LOCATIONS, SHALL BE PROVIDED BY THE CONTRACTOR, OUTSIDE THE LIMITS OF IMPROVEMENT. THIS WORK SHALL BE INCLUDED IN THE COST OF THE REMOVED ITEMS.

5. ALL SAW CUTS REQUIRED FOR REMOVAL ITEMS SHALL BE INCLUDED IN THE COST OF THAT ITEM. ALL SAW CUTS FOR PROPOSED ITEMS SHALL BE INCLUDED IN THE COST OF THAT ITEM.

6. VILLAGE OF WEST DUNDEE WILL PROVIDE CONTRACTOR WITH OFFICE SPACE, WATER AND WATER METER, AND BATHROOM FACILITIES AT A LOCATION DESIGNATED BY THE VILLAGE. THERE SHALL BE NO PORTABLE RESTROOMS PROVIDED BY THE CONTRACTOR ON SITE.

1. VERIFY SITE CONDITIONS AND INFORMATION ON DRAWINGS. PROMPTLY REPORT ANY CONCEALED CONDITIONS, MISTAKES, DISCREPANCIES OR DEVIATIONS FROM THE INFORMATION SHOWN IN THE CONTRACT DOCUMENTS. THE OWNER IS NOT RESPONSIBLE FOR UNAUTHORIZED CHANGES OR EXTRA WORK REQUIRED TO CORRECT UNREPORTED DISCREPANCIES.
2. SECURE NON-FEE PERMIT REQUIRED BY VILLAGE OF WEST DUNDEE NECESSARY FOR THE PROPER EXECUTION OF THIS WORK. COMPLY WITH CODES APPLICABLE TO THIS WORK.
3. CONTRACTOR TO PROVIDE FOR AT LEAST ONE LANE OF TRAFFIC BOTH EAST-BOUND AND WEST-BOUND ON ILLINOIS ROUTE 72 AT ALL TIMES DURING CONSTRUCTION. ALL WORK ZONE TRAFFIC CONTROLS WILL CONFORM TO IDOT SECTION 700 WORK ZONE TRAFFIC CONTROL STANDARDS. OVERNIGHT LANE CLOSURES ARE PROHIBITED UNLESS WRITTEN PERMISSION IS OBTAINED FROM IDOT. SEE TRAFFIC CONTROL PLANS FOR MORE DETAILS.