SCHEDULE OF QUANTITIES

550A0380 STORM SEWERS, CLASS A, TYPE 2 18"

FOOT LOCATION

US 20 8 Sta 112+72 , 50' RT. 8 TOTAL

550A0410 STORM SEWERS, CLASS A, TYPE 2 24"

FOOT LOCATION

US 20
18 Sta 104+69 , 40' RT.
18 TOTAL

60242400 INLETS, SPECIAL

EACH LOCATION

US 20 1 Sta 107+84 , 27.6' RT. 1 TOTAL

60262510 INLETS TO BE ADJUSTED WITH NEW FRAME AND GRATE (SPECIAL)

EACH LOCATION

US 20
2 Sta 112+72
2 TOTAL

60500060 REMOVING INLETS

EACH LOCATION

US 20
_____1 Sta 107+84 , 27.6' RT.
1 TOTAL

63000001 STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS

FOOT LOCATION

362.5 Sta 104+97.0 - 108+59.5 EB
225.0 Sta 105+97.0 - 108+22.0 WB
587.5 TOTAL

63100167 TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT

 EACH
 LOCATION

 US 20
 1

 1
 Sta
 104+47
 EB GUARDRAIL TERMINATION

 1
 Sta
 109+09.5
 EB GUARDRAIL TERMINATION

 1
 Sta
 105+47
 WB GUARDRAIL TERMINATION

 1
 Sta
 108+72
 WB GUARDRAIL TERMINATION

 4
 TOTAL

63200310 GUARDRAIL REMOVAL

FOOT LOCATION

US 20

127.0 WB GUARDRAIL REMOVAL FOR BOX CULVERT REPLACEMENT
126.0 EB GUARDRAIL REMOVAL FOR BOX CULVERT REPLACEMENT
127.0 TOTAL

63500105 DELINEATORS

	<u>EACH</u>	LOCATIO	<u>N</u>		
		US 20			
	15.00	Sta	99+27	- 114+33	EASTBOUND SHOULDER
	1.00	Sta	104+69		EASTBOUND SHOULDER
	1.00	Sta	108+66		EASTBOUND SHOULDER
	1.00	Sta	109+48		EASTBOUND SHOULDER
	1.00	Sta	110+20		EASTBOUND SHOULDER
	1.00	Sta	112+72		EASTBOUND SHOULDER
	1.00				AS NEEDED & DIRECTED BY THE RESIDENT
-	21	TOTAL			

66700305 PERMANENT SURVEY MARKERS, TYPE II

EACH LOCATION

2.00 US 20 2.00 Sta 70TAL

AS NEEDED & DIRECTED BY THE RESIDENT

70300100 SHORT-TERM PAVEMENT MARKING

	FOOT	LOCATIO	<u>N</u>		
		US 20			
	151	Sta	99+27	- 114+33	WB SKIP DASH LANE LINES
	151	Sta	99+27	- 114+33	EB SKIP DASH LANE LINES
	60	Sta	99+27	- 114+33	EB EDGE LINE
	21	Sta	99+27	- 104+40	EB LEFT TURN LANE
	14	Sta	104+40	- 107+91	EB LEFT TURN LANE TAPER
	20	Sta	109+43	- 114+33	EB MEDIAN TAPER
	13	Sta	107+91	- 108+56	DOUBLE YELLOW CENTER LINE
	100	Sta		-	AS NEEDED & DIRECTED BY THE RESIDENT
_	520	TOTAL			

ILE NAME = US	SER NAME = \$USER\$	DESIGNED: KAC	REVISED -
:\ENG\06-6790-13_TASK7\C1v\Sht\DII64C68_9HT01	195b_Schedule3.dgn	DRAWN BY: CKL/TMF	REVISED -
PL	_OT SCALE = \$SCALE\$	CHECKED BY: KAC	REVISED -
PL.	OT DATE = 12/1/2009	DATE: 11/13/2009	REVISED -

	RTE.	SECTION	COUNTY	SHEETS	NO
SCHEDULE OF QUANTITIES 3	301	43T&M	JODAVIESS	80	9
			CONTRACT	NO. 6	6406
SHEET NO. 9 OF 80 SHEETS : STA. 99+27 TO STA. 114+33	FED. RO	DAD DIST, NO. ILLINOIS FED. AI	ID PROJECT		