

SCHEDULE OF QUANTITIES

CLASS B PATCHING SCHEDULE

Location	Remarks	44200970		44200974		44200976		44213200	Z0017100	Z0075300	42001200				
		Area of Patches										Saw Cuts	Dowel Bars	Tie Bars	Pavement Fabric
		Length		TYPE 1		TYPE 2		TYPE 3		TYPE 4					
		WB	EB	WB	EB	WB	EB	WB	EB	WB	EB				
		Foot	Foot	(Yd) ²	(Yd) ²	(Yd) ²	(Yd) ²	(Yd) ²	(Yd) ²	(Yd) ²	(Yd) ²	Foot	Each	Each	(Yd) ²
US 20 - Mainline															
Sta 107+18.0 - 108+18.0	MOT Stage 3,4	100.0	100.0							307.1	305.0	110.0	318.0	80.0	612.1
	Contingency quantity						14.0	24.0				10.0	40.0	20.0	
	Contingency quantity						14.0	24.0				10.0	40.0	10.0	
	Contingency quantity						14.0	24.0				10.0	40.0	10.0	
Median															
Sta 88+13.0 - 104+63.0	4' Median											8.0			
Sta 105+63.0 - 107+18.0	4' Median	155.0										12.0			
Sta 108+18.0 - 109+14.0	4' Median	96.0										12.0			
Lane Total															
TOTAL				0.0	0.0	0.0	42.0	72.0	0.0	418.7	305.0				
				0.0		42.0		72.0		724		172	438	120	612

PAVEMENT PATCHING SCHEDULE

Location	Remarks	Length	Proposed Surface		44001700	44003700	X0712400	X0919000	60620400	48301000
			Combination Concrete Curb & Gutter Removal & Replacement		Median Removal (Special)	Temporary Pavement	Temporary Pavement Removal	Concrete Median, Type SB-9.06	Protective Coat	
			Width	Sq Ft	Foot	Sq Ft	Sq Yd	Sq Yd	Sq Ft	Sq Yd
US 20 - Mainline										
Sta 107+18.0 - 108+18.0	LT	100			100.0					36.1
Sta 103+35.0 - 112+05.0	10' Exist. Shoulder	870	10.0	8700.0			966.7	966.7		
Median										
Sta 94+05.0 - 104+63.0		1058	4.0	4232.0		4232.0	470.2	470.2	4232.0	470.2
Sta 105+63.0 - 108+66.0		303	4.0	1212.0		1212.0	134.7	134.7		
Sta 109+48.0 - 113+75.0		427	4.0	1675.0		1675.0	186.1	186.1	1675.0	186.1
TOTAL										
				15,819.0	100.0	7119	1,757.7	1,757.7	5907	692.4