



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

February 22, 2010

SUBJECT: FAI Route 39 (I-39)  
Project ACNHI-039-1 (028) 097  
Section (103-1, 103-2) SHLD  
Lee County  
Contract No. 64F82  
Item No. 192, March 5, 2010 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Replaced the Schedule of Prices.
2. Revised the Table of Contents to the Special Provisions.
3. Added page 50 to the Special Provisions.
4. Revised sheets 2, 4, 11-17 & 54 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Scott E. Stitt, P.E.  
Acting Engineer of Design and Environment

A handwritten signature in black ink, appearing to read 'Ted B. Walschleger P.E.'.

By: Ted B. Walschleger, P. E.  
Engineer of Project Management

cc: George F. Ryan, Region 2, District 2; Mike Renner; R. E. Anderson;  
Estimates

GBW:MS:jc

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER -

64F82

State Job # - C-92-030-10  
 PPS NBR - 2-17410-0100  
 County Name - LEE - -  
 Code - 103 - -  
 District - 2 - -  
 Section Number - (103-1, 103-2)SHLD

Project Number  
 ACNHI-0391/028/097

Route  
 FAI 39

\* REVISED : FEBRUARY 16, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
* X0325519	DRAIN FOR AGG BASE CSE	SQ YD	385.000				
X0326764	COLD MILLING SPL	SQ YD	336,126.000				
* Z0005400	BREAKER-RUN CR STONE	TON	1,784.000				
Z0013798	CONSTRUCTION LAYOUT	L SUM	1.000				
Z0075300	TIE BARS	EACH	5,892.000				
20200600	EXC & GR EX SHOULDER	UNIT	3,940.000				
* 31100300	SUB GRAN MAT A 4	SQ YD	1,364.000				
44200553	CL A PATCH T2 10	SQ YD	540.000				
44200557	CL A PATCH T3 10	SQ YD	152.000				
44200559	CL A PATCH T4 10	SQ YD	8,253.000				
44213000	PATCH REINFORCEMENT	SQ YD	8,945.000				
44213200	SAW CUTS	FOOT	29,680.000				
48100100	AGGREGATE SHLDS A	TON	60,015.000				
48300300	PCC SHOULDERS 8	SQ YD	336,126.000				
63500205	REM & REP DELINEATORS	EACH	650.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 SCHEDULE OF PRICES  
 CONTRACT  
 NUMBER - 64F82

State Job # - C-92-030-10  
 PPS NBR - 2-17410-0100  
 County Name - LEE- -  
 Code - 103 - -  
 District - 2 - -  
 Section Number - (103-1, 103-2)SHLD

Project Number  
 ACNHI-0391/028/097

Route  
 FAI 39

\* REVISED : FEBRUARY 16, 2010

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
67000400	ENGR FIELD OFFICE A	CAL MO	10.000				
67100100	MOBILIZATION	L SUM	1.000				
70100420	TRAF CONT-PROT 701411	EACH	16.000				
70100800	TRAF CONT-PROT 701401	L SUM	1.000				
70100825	TRAF CONT-PROT 701456	L SUM	1.000				
70103815	TR CONT SURVEILLANCE	CAL DA	85.000				
78001110	PAINT PVT MK LINE 4	FOOT	105,600.000				
78001140	PAINT PVT MK LINE 8	FOOT	11,500.000				
78001150	PAINT PVT MK LINE 12	FOOT	250.000				

**TABLE OF CONTENTS**

LOCATION OF PROJECT ..... 1

DESCRIPTION OF PROJECT ..... 1

TRAFFIC CONTROL PLAN ..... 1

EARTH TRENCH FOR WIDENING (ROTOMILLING) ..... 4

COMPLETION DATES ..... 4

START DATE ..... 5

MAINTENANCE OF ROADWAYS ..... 5

CRITICAL PATH SCHEDULE..... 5

ENGINEER’S FIELD OFFICE TYPE A ..... 5

COLD MILLING (SPECIAL) ..... 7

WORK RESTRICTIONS ..... 8

REMOVING AND REPLACING DELINEATORS..... 8

APPROVAL OF PROPOSED BORROW AREAS, USE AREAS, AND/OR WASTE AREAS INSIDE ILLINOIS STATE BORDERS (BDE) ..... 8

CEMENT (BDE) ..... 9

CONCRETE ADMIXTURES (BDE) ..... 11

CONCRETE MIX DESIGNS (BDE) ..... 14

CONSTRUCTION AIR QUALITY - DIESEL VEHICLE EMISSIONS CONTROL (BDE) ..... 15

CONSTRUCTION AIR QUALITY - IDLING RESTRICTIONS (BDE)..... 16

DETERMINATION OF THICKNESS (BDE)..... 18

DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE) ..... 28

EQUIPMENT RENTAL RATES (BDE)..... 35

LIQUIDATED DAMAGES (BDE)..... 36

MULTILANE PAVEMENT PATCHING (BDE)..... 36

NATIONAL POLLUTANT DISCHARGE ELIMINATION SYSTEM / EROSION AND SEDIMENT CONTROL DEFICIENCY DEDUCTION (BDE) ..... 37

PARTIAL EXIT RAMP CLOSURE FOR FREEWAY/EXPRESSWAY (BDE) ..... 38

PAVEMENT PATCHING (BDE)..... 38

PAYMENTS TO SUBCONTRACTORS (BDE) ..... 38

PERSONAL PROTECTIVE EQUIPMENT (BDE) ..... 39

PUBLIC CONVENIENCE AND SAFETY (BDE) ..... 40

REFLECTIVE SHEETING ON CHANNELIZING DEVICES (BDE) ..... 40

REINFORCEMENT BARS - STORAGE AND PROTECTION (BDE)..... 41

SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) ..... 41

Revised 02/22/2010

TRUCK MOUNTED/TRAILER MOUNTED ATTENUATORS (BDE) ..... 41  
STEEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID) ..... 42  
FUEL COST ADJUSTMENT (BDE) (RETURN FORM WITH BID) ..... 46  
BREAKER RUN CRUSHED STONE ..... 50

Revised 02/22/2010

**BREAKER RUN CRUSHED STONE**

Effective: May 1, 1995

Revised: February 9, 2010

This work shall consist of placing Breaker Run Crushed Stone at locations shown in the plans. The Breaker Run Crushed Stone shall be constructed of crushed stone with the top size 150 mm (6"), with 70%-90% by weight, passing through the 4 inch sieve and 15% to 40% by weight, passing through the 2 inch sieve. Breaker Run Crushed Stone shall be reasonably uniformly graded from coarse to fine aggregate and be taken from a source capable of producing Class "D" quality aggregate. Materials resulting from the removal of the existing unsuitable and unstable materials shall be disposed of according to Article 202.03 for the sub-base under the Class A Patches and shall be included in the price for the placement of the Breaker Run Crushed Stone.

This work shall be paid for at the contract unit price per Ton for BREAKER RUN CRUSHED STONE.

Revised 02/22/2010