

SUMMARY OF QUANTITIES				100% FED.	
CODE NO.	CONSTRUCTION CODE TYPE: ITEM	UNIT	1000		
			TOTAL QUANTITY	RDWY QUANTITY	
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	6	6	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	42	42	
20101000	TEMPORARY FENCE	FOOT	1230	1230	
20101200	TREE ROOT PRUNING	EACH	36	36	
20200100	EARTH EXCAVATION	CU YD	854	854	
20400800	FURNISHED EXCAVATION	CU YD	1969	1969	
20800150	TRENCH BACKFILL	CU YD	2880	2880	
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	334	334	
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	334	334	
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	334	334	
* 25100630	EROSION CONTROL BLANKET	SQ YD	250	250	
* 25200110	SODDING, SALT TOLERANT	SQ YD	17975	17975	
* 25200200	SUPPLEMENTAL WATERING	UNIT	324	324	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	800	800	
28000305	TEMPORARY DITCH CHECKS	FOOT	115	115	
28000400	PERIMETER EROSION BARRIER	FOOT	3280	3280	
28000500	INLET AND PIPE PROTECTION	EACH	27	27	
28100109	STONE RIPRAP, CLASS A5	SQ YD	56	56	
28200200	FILTER FABRIC	SQ YD	56	56	
31100910	SUB-BASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	6379	6379	
35600724	HOT-MIX ASPHALT BASE COURSE WIDENING, 12"	SQ YD	1535	1535	
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	50	50	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2217	2217	
40600300	AGGREGATE (PRIME COAT)	TON	66	66	
40600525	LEVELING BINDER (HAND METHOD), N50	TON	10	10	
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	1540	1540	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1007	1007	
40600990	TEMPORARY RAMP	SQ YD	292	292	
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	240	240	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	1182	1182	

SUMMARY OF QUANTITIES				100% FED.	
CODE NO.	CONSTRUCTION CODE TYPE: ITEM	UNIT	1000		
			TOTAL QUANTITY	RDWY QUANTITY	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	206	206	
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	1250	1250	
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	315	315	
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	1049	1049	
42400800	DETECTABLE WARNINGS	SQ FT	128	128	
44000100	PAVEMENT REMOVAL	SQ YD	1523	1523	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	3693	3693	
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	1444	1444	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1470	1470	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	273	273	
44000600	SIDEWALK REMOVAL	SQ FT	2045	2045	
44003100	MEDIAN REMOVAL	SQ FT	621	621	
44004250	PAVED SHOULDER REMOVAL	SQ YD	1273	1273	
44201785	CLASS D PATCHES, TYPE I, 12 INCH	SQ YD	183	183	
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	105	105	
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	112	112	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	7140	7140	
50105200	REMOVE EXISTING CULVERTS	EACH	33	33	
54213693	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 48"	EACH	1	1	
54247190	GRATING FOR CONCRETE FLARED END SECTION 48"	EACH	1	1	
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	755	755	
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	137	137	
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	106	106	
550A0440	STORM SEWERS, CLASS A, TYPE 2 33"	FOOT	247	247	
550A0450	STORM SEWERS, CLASS A, TYPE 2 36"	FOOT	153	153	
550A0470	STORM SEWERS, CLASS A, TYPE 2 42"	FOOT	280	280	
550A0480	STORM SEWERS, CLASS A, TYPE 2 48"	FOOT	668	668	
550A2320	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 12"	FOOT	20	20	
550A2380	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 1 30"	FOOT	343	343	
550A2560	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 24"	FOOT	335	335	

\* SPECIALTY ITEMS

FILE NAME =	USER NAME = schwanke	DESIGNED - SPF	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ca:\pwwork\pwwork\SCHWANKE\08173918\202308500.dgn	PLLOT SCALE = 1:8000' / IN.	DRAWN - AJP	REVISED -					681	114 RS-2	LIVINGSTON	63	3
PLLOT DATE = Dec 12, 2009 - 12:26:38 PM	DATE - 09/25/09	CHECKED - JMS	REVISED -					SCALE: SHEET NO. 1 OF 2 SHEETS STA. TO STA.			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT	
		REVISIED -	REVISED -								CONTRACT NO. 66532	