

SUMMARY OF QUANTITIES

100% FED.

CODE NO.	CONSTRUCTION CODE TYPE: ITEM	UNIT	1000	
			TOTAL QUANTITY	RDWY QUANTITY
550A2570	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 27"	FOOT	212	212
550A2600	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 36"	FOOT	369	369
550A2610	STORM SEWERS, RUBBER GASKET, CLASS A, TYPE 2 42"	FOOT	135	135
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	11	11
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	13	13
60224446	MANHOLES, TYPE A, 7'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	21	21
60237470	INLETS, TYPE A, TYPE 24 FRAME AND GRATE	EACH	22	22
60240301	INLETS, TYPE B, TYPE 8 GRATE	EACH	2	2
60240345	INLETS, TYPE B, TYPE ^{B-} 24 FRAME AND GRATE	EACH	41	41
60500040	REMOVING MANHOLES	EACH	2	2
60500060	REMOVING INLETS	EACH	2	2
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	7346	7346
60625800	ISLAND PAVEMENT (SPECIAL)	SQ YD	116	116
66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	683	683
66900450	SPECIAL WASTE PLANS AND REPORT	L SUM	1	1
66900510	BETX-PNAS SOIL ANALYSIS	EACH	7	7
66900530	SOIL DISPOSAL ANALYSIS	EACH	3	3
66900610	ARSENIC AND PH SOIL ANALYSIS	EACH	3	3
66900635	LEAD TCLP SOIL ANALYSIS	EACH	9	9
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	12
67100100	MOBILIZATION	L SUM	1	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	45	45
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	385	385
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	78	78
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2726	2726
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	991	991
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	873	873

SUMMARY OF QUANTITIES

100% FED.

CODE NO.	CONSTRUCTION CODE TYPE: ITEM	UNIT	1000	
			TOTAL QUANTITY	RDWY QUANTITY
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	395	395
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	214	214
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	78	78
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2726	2726
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	991	991
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	873	873
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	395	395
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	214	214
* 78100100	RAISED REFLECTOR PAVEMENT MARKER	EACH	94	94
* 78200300	PRISMATIC CURB REFLECTOR	EACH	32	32
78300200	RAISED REFLECTOR PAVEMENT MARKER REMOVAL	EACH	50	50
81000300	CONDUIT IN TRENCH, 1" DIA., GALVANIZED STEEL	FOOT	100	100
81017510	CONDUIT IN TRENCH, 1" DIA., COILABLE NONMETALLIC CONDUIT	FOOT	100	100
81030100	CONDUIT SPLICE	EACH	6	6
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	100	100
89502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	1200	1200
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1
Z0032900	LAND SECTION MARKERS	EACH	1	1
Z0049300	REFERENCING LAND SECTION MARKERS	EACH	1	1
Z0055300	RUMBLE STRIP	EACH	11	11
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	292	292
X0322035	STORM SEWERS (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	366	366
X0322089	STORM SEWERS (WATER MAIN REQUIREMENTS) 36 INCH	FOOT	89	89
X0322090	STORM SEWERS (WATER MAIN REQUIREMENTS) 42 INCH	FOOT	390	390
X0322092	STORM SEWERS (WATER MAIN REQUIREMENTS) 48 INCH	FOOT	285	285
X0322903	SAW CUTTING, (FULL DEPTH)	FOOT	7140	7140
Z0059400	SANITARY SEWER, TYPE 2 4"	FOOT	75	75
Z0059500	SANITARY SEWER, TYPE 2 6"	FOOT	75	75
Z0059600	SANITARY SEWER, TYPE 2 8"	FOOT	75	75

* SPECIALTY ITEMS