

SCHEDULES OF QUANTITIES

PAVEMENT

LOCATION STATION TO STATION	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	PCC BASE COURSE 8"	AGGREGATE *** BASE COURSE, TYPE A 8"	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HOT-MIX ASPHALT SHOULDERS, 8"	PCC DRIVEWAY PAVEMENT, 7"	PROTECTIVE * COAT	SUB-BASE *** GRANULAR MATERIAL, TYPE A
	TON	TON	SQ. YD.	SQ. YD.	GALLON	TON	SQ. YD.	SQ. YD.	SQ. YD.	TON
FAP ROUTE 522 (IL 96)										
STA. 8+47 TO STA. 8+57	4	-	-	-	3	-	-	-	-	-
RT. STA. 8+61	-	-	-	-	-	-	-	23	23	5
RT. STA. 8+70 TO RT. STA. 9+23	-	-	-	-	-	-	45	-	-	-
STA. 8+57 TO STA. 10+00	51	-	453	-	41	-	-	-	-	377
RT. STA. 9+77 TO STA. 10+00	-	-	-	-	-	-	20	-	-	-
STA. 10+00 TO STA. 10+10	4	-	-	-	3	-	-	-	-	-
NORTH ELM STREET										
STA. 50+14.46 TO STA. 50+52	9	14	-	108	19	0.2	-	-	-	-
STA. 50+52 TO 51+31.46	15	23	-	219	18	0.3	-	-	-	-
SOUTH ELM STREET										
STA. 48+53.77 TO STA. 48+82.79	6	9	-	86	7	0.1	-	-	-	-
STA. 48+82.79 TO STA. 49+86.50	26	38	-	314	27	0.4	-	-	-	-
LOCAL TRAFFIC DETOUR PLAN										
5TH STREET & LINN STREET	280	-	-	-	299	5.0	-	-	-	-
TOTALS										
	395	84	453	727	417	6	65	23	23	382

CONCRETE CURB & GUTTER

LOCATION STATION TO STATION	COMBINATION CONCRETE CURB AND GUTTER, TYPE B - 6.24	PROTECTIVE ** COAT	CLASS SI CONCRETE (OUTLET)	AGGREGATE **** BASE COURSE, TYPE A 8"	SUB-BASE **** GRANULAR MATERIAL, TYPE A
	FOOT	SQ YD	CU YD	SQ YD	TON
FAP ROUTE 522 (IL 96)					
LT. STA. 8+60 TO STA. 8+72	-	7.2	1.2	-	1.2
LT. STA. 8+72 TO STA. 9+09.26	42.5	14.2	-	-	3.8
LT. STA. 9+33 TO STA. 9+98	70.5	23.5	-	-	6.3
LT. STA. 9+98 TO STA. 10+10	-	7.2	1.2	-	1.2
RT. STA. 8+70 TO STA. 9+38	73.5	24.5	-	-	6.6
RT. STA. 9+62 TO STA. 10+00	43.5	14.5	-	-	3.9
NORTH ELM STREET					
LT. STA. 50+29.32 TO STA. 50+40	10.5	3.5	-	4.2	-
LT. STA. 50+40 TO STA. 50+52	-	7.2	1.2	6.5	-
RT. STA. 50+30.70 TO STA. 50+40	9.5	3.2	-	3.8	-
RT. STA. 50+40 TO STA. 50+52	-	7.2	1.2	6.5	-
SOUTH ELM STREET					
LT. STA. 48+82.57 TO STA. 49+63.58	79.5	26.5	-	31.7	-
RT. STA. 48+82.79 TO STA. 49+63.49	82.0	27.3	-	32.7	-
TOTALS					
	411.5	166	4.8	85.4	23.0

- * SEE CONCRETE CURB & GUTTER SCHEDULE AND CONCRETE STRUCTURES SCHEDULE FOR ADDITIONAL QUANTITIES
- ** SEE CONCRETE STRUCTURES SCHEDULE AND PAVEMENT SCHEDULE FOR ADDITIONAL QUANTITIES
- *** SEE CONCRETE CURB & GUTTER SCHEDULE FOR ADDITIONAL QUANTITIES
- **** SEE PAVEMENT SCHEDULE FOR ADDITIONAL QUANTITIES

FILE NAME = #FILEL#	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES OF QUANTITIES			F.A.P RTE. 522	SECTION (6G-WPSO)BR	COUNTY HANCOCK	TOTAL SHEETS 41	SHEET NO. 7
		DRAWN -	REVISED -		SCALE: NTS	SHEET NO. 1 OF 4 SHEETS	STA.	TO STA.	CONTRACT NO. 68214			
		CHECKED -	REVISED -		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT							
		DATE -	REVISED -									