### **PAVING SURFACE COURSE**

CONTINUOUS PAVING OPERATIONS ON THE MAIN ROADWAY SHALL BE MAINTAINED AT ALL TIMES DURING THE CONSTRUCTION OF THE HOT-MIX ASPHALT SURFACE. NO INTERRUPTIONS FOR SIDE ROADS, ENTRANCES, TURN LANES, ETC. WILL BE ALLOWED.

### AGGREGATE FOR DRIVEWAY REPLACEMENT

THE MATERIAL FOR CONSTRUCTION OF PERMANENT AGGREGATE DRIVEWAYS SHALL BE GRAVEL OR CRUSHED STONE AS DIRECTED BY THE ENGINEER, TO REPLACE IN KIND THE EXISTING AGGREGATE DRIVEWAYS.

NO ADDITIONAL COMPENSATION SHALL BE PROVIDED FOR THIS REQUIREMENT BUT SHALL BE CONSIDERED AS INCLUDED IN THE COST OF THE PAY ITEM FOR THE AGGREGATE AS SPECIFIED ON THE PLANS.

# TRANSITION PAYMENT METHOD - NEW/OLD CONSTRUCTION

THREE METER (3 m) (10 FT.) TRANSITIONS SHALL BE USED TO MATCH PROPOSED ITEMS OF WORK TO EXISTING ITEMS IN THE FIELD UNLESS OTHERWISE SHOWN. THE TRANSITION SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE FOR THE PROPOSED ITEM OF WORK SPECIFIED.

## ENGINEER'S FIELD OFFICE

ADD THE FOLLOWING SENTENCE TO THE END OF PARAGRAPH 670.02 (i) AND 670.04 (e): ALL OF THE TELEPHONE LINES PROVIDED SHALL HAVE UNPUBLISHED NUMBERS.

### HOT-MIX ASPHALT MIXTURE REQUIREMENTS

MIXTURE USE(S):	SURFACE COURSE 1 1/2"	LEVELING BINDER 3/4"	HMA SHOULDER (SURFACE LIFT 2 1/4")	INCIDENTAL SURFACE COURSE	CLASS D PATCHES PG 64-22	
AC/PG:	SBS or SBR 70-22	SBS or SBR 70-22	PG 64-22	PG 64-22		
RAP% (MAX): **	10%	10%	30%	15%	25%	
DESIGN AIR VOIDS:	4.0% @ N=50	3.0% @ N=50	3.0%@N=30	4.0%@N=50	4.0%@N=50	
MIXTURE COMPOSITION:	11 0.5 - 11.40 5	IL 4.75	IL9.5L		IL 19.0	
(GRADATION MIXTURE)	IL 9.5 or IL12.5			IL 9.5 or 12.5		
FRICTION AGGREGATE:	MIXTURE D	N.A	MIXTURE C	MIXURE C	NA NA	

<sup>\*\*</sup> IF THE RAP OPTION IS SELECTED, THE ASPHALT CEMENT GRADE MAY NEED TO BE ADJUSTED; THIS WILL BE DETERMINED BY THE ENGINEER.

FILE NAME =	USER NAME = Johnsontv	DESIGNED -	REVISED -			F.A.P. SECTION	COUNTY TOTAL SHEET
88467 - Phase 11.dgn		ORAWN -	REVISED -	STATE OF ILLINOIS	COMMITMENTS AND GENERAL NOTES	RTE. SECTION	SHEETS NO.
	PLOT SCALE = 120.2000 ' / IN.	CHECKED -	REVISED -	DEPARTMENT OF TRANSPORTATION		317   17RS-6; 18RS-1; 35RS-8	WOODFORD 60 3
	PLOT DATE = 12/18/2009	DATE	REVISED -		SHEET NO. 2 OF 2 SHEETS		IN PROJECT