

PAVEMENT MARKING SCHEDULE

LOCATION	URETHANE PAVEMENT MARKING												PREFORMED PLASTIC PVMT MARKING, TY B		
	LINE 4"						LINE 8"		LINE 12"		LINE 24"	LETTERS & SYMBOLS, SPECIAL	LINE 6"		
	SOLID - WHITE		SOLID - YELLOW		SKIP DASH - YELLOW		WHITE		WHITE	YELLOW	FT	SQ FT	SKIP DASH - WHITE		
	WB	EB	WB	EB	WB	EB	WB	EB	WB	EB			WB	EB	
FT		FT		FT		FT		FT		FT		FT			
TAZEWELL COUNTY - MAINLINE															
STA. 99 + 17.23	TO STA. 140 + 52.09	4,600	4,052	4,180	24,021			257	700	64		94	1,034	1,034	
STA. 140 + 52.09	TO STA. 210 + 06.65	6,817	6,857	6,925	6,939			665	370	62		125	1,739	1,739	
STA. 210 + 06.65	TO STA. 228 + 97.77 (BK)	2,493	1,784	2,111	1,769			368	375	68	227	123	125	294	168
STA. 229 + 32.77 (AH)	TO STA. 265 + 56.75	3,543	3,560	1,557	1,557		651		375		280		125		
STA. 265 + 56.75	TO STA. 372 + 45.41	10,543	10,542	25,966	25,966		1,450	375			530		62		
STA. 372 + 45.41	TO STA. 425 + 87.37	5,273	5,265	1,542	1,542		1,085	375			241				
WOODFORD COUNTY - MAINLINE															
STA. 425 + 87.37	TO STA. 489 + 87.33	6,343	6,336	1,777	4,546		1,291		375		258		125		
STA. 489 + 87.33	TO STA. 515 + 37.5 (BK)	2,497	2,479	1,877	1,877		142	572			466		62		
STA. 315 + 00.00 (AH)	TO STA. 316 + 97+45	197	197	1,773	1,773						208				
NOFSINGER RD.															
STA. 8 + 21.61	TO STA. 9 + 86.79		257	116	116			144				30			
STA. 9 + 86.79	TO STA. 11 + 76.77		229	103	103				128			30			
MAIN ST.															
STA. 8 + 23.06	TO STA. 10 + 00.00		280	99	99			259				44	31		
STA. 10 + 00.00	TO STA. 11 + 77.25		279	89	89			266				44	31		
DIEBLE RD.															
STA. 6 + 50.00	TO STA. 10 + 00.00		678	117	117		50	116				33			
STA. 10 + 00.00	TO STA. 13 + 00.00		581	114	114		38		106			33			
DEE MACK RD.															
STA. 9 + 08.50	TO STA. 10 + 00.00		169	67	67			130				33			
STA. 10 + 00.00	TO STA. 10 + 91.50		169	67	67				130			33			
C.H.3/ B US 24															
STA. 18 + 56.23	TO STA. 20 + 00.00		257	115	115			121				31			
STA. 20 + 00.00	TO STA. 21 + 46.48		239	117	117				128			31			
SUB-TOTAL		86,515		119,708		4,707		6,334		2,404		460	780	6,007	
TOTAL				210,930				6,334		2,404		460	780	6,007	

FILE NAME = 68467 - Phase II.dgn
 USER NAME = johnsonv
 PLOT SCALE = 1/8" = 100.0000' / IN.
 PLOT DATE = 11/23/2009

DESIGNED -
 DRAWN -
 CHECKED -
 DATE -
 REVISED -
 REVISED -
 REVISED -
 REVISED -

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

SCHEDULES OF QUANTITIES

SHEET NO. 4 OF 7 SHEETS

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
317	17RS-6; 18RS-1; 35RS-8	TAZEWELL WOODFORD	60	22
CONTRACT NO. 68467				
ILLINOIS FED. AID PROJECT				