

**TABULATION OF RESURFACING QUANTITIES**

LOCATION	HMA SURFACE REMOVAL - BUTT JOINT	TEMPORARY RAMP	HMA SURFACE REMOVAL, 3/4 IN	HMA SURFACE REMOVAL, 1 1/2 IN	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)		AGGREGATE (PRIME COAT)	HMA SURFACE COURSE, MIX "D", N50	HMA SHOULDERS		AGGREGATE SHOULDERS, TYPE B		AGGREGATE SHOULDER REMOVAL		
					COLD-MILLED	FOG COAT			COLD-MILLED	LEFT	RIGHT	LEFT		RIGHT	
															TON
<b>IL 17 - MAINLINE</b>															
<b>MARSHALL COUNTY</b>															
STA. 65+59.00	TO STA. 77+14.37	BK	28.89	14.44	3308.85										
STA. 18+12.54	AH TO STA. 33+77.17				4520.04	1.34	0.28	6.68	281.04	210.88	210.88	32.90	32.90	171.17	
STA. 33+77.17	TO STA. 66+16.29				9357.46	1.81	0.38	9.04	380.60	285.57	285.57	44.55	44.55	231.80	
STA. 66+16.29	TO STA. 78+91.09				3682.76	3.74		18.71	787.92			184.45	184.45		
STA. 78+91.09	TO STA. 95+80.29				4879.91	1.47		7.37	310.10			72.59	72.59		
STA. 95+80.29	TO STA. 101+42.79				1625.00	1.95		9.76	410.90			96.19	96.19		
STA. 101+42.79	TO STA. 115+60.00				4094.16	0.65		3.25	136.83			32.03	32.03		
STA. 115+60.00	TO STA. 117+95.89				681.46	1.64		8.19	344.74			80.70	80.70		
STA. 117+95.89	TO STA. 121+33.39				975.00	0.27	0.06	1.36	57.38	43.05	43.05	6.72	6.72	34.95	
STA. 121+33.39	TO STA. 328+78.39				59930.00	0.39	0.08	1.95	82.10	61.60	61.60	9.61	9.61	50.00	
STA. 328+78.39	TO STA. 331+05.89				657.22	23.97	4.98	119.86	5046.22	3786.35	3786.35	590.66	590.66	3073.33	
STA. 331+05.89	TO STA. 380+26.89				14216.22	0.26	0.05	1.31	55.34	41.52	41.52	6.48	6.48	33.70	
STA. 380+26.89	TO STA. 383+09.95				817.73	5.69	1.18	28.43	1197.03	898.17	898.17	140.11	140.11	729.04	
STA. 383+09.95	TO STA. 383+39.50				124.77	0.33	0.07	1.64	68.85	51.66	51.66	8.06	8.06	41.93	
STA. 383+39.50	TO STA. 407+13.89				6859.35	0.05		0.25	10.50			1.68	1.68		
STA. 407+13.89	TO STA. 454+05.39				13553.22	2.74	0.57	13.72	577.57	433.37	433.37	67.60	67.60		
STA. 454+05.39	TO STA. 456+09.48					5.42	1.13	27.11	1141.21	856.29	856.29	133.58	133.58	695.04	
STA. 456+09.48	TO STA. 457+42.08					0.30	0.05	1.52	63.96	37.25	37.25	5.81	5.81	30.24	
STA. 457+42.08	TO STA. 459+64.79				776.34	0.27		1.34	56.44			7.55	7.55		
STA. 459+64.79	TO STA. 460+11.00		28.89	14.44	104.61	0.31	0.05	1.55	65.34	40.65	40.65	6.34	6.34	32.99	
<b>IL 89 - MAINLINE</b>															
<b>PUTNAM COUNTY</b>															
STA. 562+00.00	TO STA. 564+90.90		71.11	35.56	963.20	0.41		2.07	87.05			16.57	16.57		
STA. 564+90.90	TO STA. 566+74.90														
STA. 566+74.90	TO STA. 570+63.25		35.56	17.78		1,187.96	0.49	2.45	103.00			22.11	22.11		
STA. 570+63.25	TO STA. 619+83.07					14,212.81	5.69	1.18	28.43	1196.75	897.96	897.96	140.08	140.08	728.86
<b>MARSHALL COUNTY</b>															
STA. 619+83.07	TO STA. 667+12.96		28.89	14.44	13,635.24	5.47	1.14	27.33	1150.55	863.29	863.29	134.67	134.67	700.72	
STA. 667+12.96	TO STA. 669+97.10														
STA. 669+97.10	TO STA. 748+30.50		28.89	14.44	22,600.93	9.05	1.88	45.26	1905.47	1429.74	1429.74	223.03	223.03	1160.50	
STA. 748+30.50	TO STA. 754+20.00				2,358.00	0.94		4.72	198.42			33.57	33.57		
STA. 754+20.00	TO STA. 760+98.26				1,959.42	0.78	0.16	3.92	164.99	123.80	123.80	19.31	19.31	100.48	
STA. 760+98.26	TO STA. 778+93.00				5,184.80	2.07	0.43	10.37	436.57	327.57	327.57	51.10	51.10	265.89	
STA. 778+93.00	TO STA. 794+67.85				4,549.57	1.82	0.38	9.10	383.08	287.44	287.44	44.84	44.84	233.31	
STA. 794+67.85	TO STA. 795+66.28				284.35	0.11	0.02	0.57	23.94	17.97	17.97	2.80	2.80	14.58	
STA. 795+66.28	TO STA. 799+27.19				1,042.63	0.42	0.09	2.09	87.79	65.87	65.87	10.28	10.28	53.47	
STA. 799+27.19	TO STA. 870+00.00				20,432.56	8.17	1.70	40.87	1720.46	1290.92	1290.92	201.38	201.38	1047.82	
STA. 870+00.00	TO STA. 891+52.00				6,838.58	2.74		13.68	575.70			122.54	122.54		
STA. 891+52.00	TO STA. 910+00.00	BK			5,338.67	2.14	0.44	10.68	449.53	337.29	337.29	52.62	52.62	273.78	
STA. 39+80.00	AH TO STA. 42+70.19				348.99	0.14	0.07	0.70	29.48	52.97	52.97	8.26	8.26	42.99	
STA. 42+70.19	TO STA. 45+08.40		42.22	21.11	337.62	0.15		0.76	32.05			13.56	13.56		
<b>IL 18</b>															
<b>PUTNAM COUNTY</b>															
STA. 425+95.50	TO STA. 430+15.00		136.38	68.19	2,406.14	1.02		5.09	213.82			23.89	23.89		
<b>SUB-TOTAL</b>															
			400.82	200.41	130164.10	105112.41	94.27	16.37	471.35	19843.93	12,449.62	12,449.62	2,649.54	2,649.54	9,753.45
<b>TOTAL</b>			<b>401</b>	<b>200</b>	<b>130,164</b>	<b>105,112</b>	<b>111</b>	<b>471</b>	<b>19,844</b>	<b>24,899</b>	<b>24,899</b>	<b>5,299</b>	<b>5,299</b>	<b>9,753</b>	

FILE NAME = 68915 - Phase 11.dgn

USER NAME = johnsonv  
 PLOT SCALE = 100.0000' / IN.  
 PLOT DATE = 12/5/2008

DESIGNED -  
 DRAWN -  
 CHECKED -  
 DATE -

REVISED -  
 REVISED -  
 REVISED -  
 REVISED -

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**SCHEDULES OF QUANTITIES**

SCALE: SHEET NO. 1 OF 8 SHEETS STA. TO STA.

F.A.P. RTE. 698 649	SECTION 123RS-4,122,124RS-5,2RS-3,3RS-4	COUNTY MARSHALL PUTNAM	TOTAL SHEETS 40	SHEET NO. 11
CONTRACT NO. 68915				
ILLINOIS FED. AID PROJECT				