_	F.A.I. RTE.	SECTION	COUNTY			TOTAL	SHE			
	57	(10-30)RA-I-	2 CI	HAMPA	IGN	119				
	STA.	TO STA.								
	FED. RO.	AD DIST, NO. II	INOIS	FFD.	ATD	PROJECT				

G.N.-540

THE CONTRACTOR SHALL ASSEMBLE AND MATCH-MARK THE PRECAST BOX CULVERT SECTIONS AND END SECTIONS PRIOR TO SHIPMENT OF THESE COMPONENTS FROM THE MANUFACTURER, AND AS DIRECTED BY THE ENGINEER IN ORDER TO SECURE A PROPER FIT ON EACH JOINT. ANY SECTIONS OR END SECTIONS WHICH DO NOT PROVIDE A PROPER FIT AT THE JOINT SHALL BE REJECTED BY THE ENGINEER AND REPLACED BY THE CONTRACTOR WITH NO ADDITIONAL COMPENSATION BEING ALLOWED.

THIS WORK WILL NOT BE PAID FOR SEPARATELY, BUT SHALL BE INCLUDED IN THE CONTRACT UNIT PRICE PER FOOT FOR PRECAST CONCRETE BOX CULVERTS OF THE SIZE SPECIFIED.

G.N.-542.07

AT LOCATIONS WHERE END SECTIONS ARE SPECIFIED, CAST-IN-PLACE CONCRETE HEADWALLS WILL NOT BE ALLOWED.

G.N.-550

BEFORE ORDERING STORM SEWERS, THE CONTRACTOR SHALL CONSULT THE ENGINEER FOR THE EXACT LENGTHS.

G.N.-1004.01

COARSE AGGREGATE GRADATION CA-10 MAY BE USED WHENEVER COARSE AGGREGATE CA-6 IS SPECIFIED IN THE STANDARD SPECIFICATIONS.

THERE ARE NO COMMITMENTS ASSOCIATED WITH THIS PROJECT.

PLAN NOTES:

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUR WRITTEN PERMISSION FROM THE DEPARTMENT.

IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND EXISTING CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING MATERIALS.

THE CONSTRUCTION SHALL BE BE DONE IN STAGES. THROUGHOUT THE CONSTRUCTION PROCESS, ONLY ONE REST AREA MAY BE COMPLETELY CLOSED.

ALL WORK MUST BE COMPLETE AND THE REST AREA OPEN PRIOR TO THE CONTRACTOR BEGINNING WORK AT A SECOND LOCATION.

AT NO TIME SHALL THE CONTRACTOR BE ALLOWED TO WORK ON BOTH LOCATIONS AT THE SAME TIME.

TIE BAR AND SEALING TABLE - NORTHBOUND TRUCK PARKING LOT

	EPOXY			LENGTH		DRILL &	POUR		HGWY
PAVEMENT TYPE	COATED	DEFORMED	SIZE	(IN)	SPACING	GROUT	IN	SEAL	STAND
PCC PVT, 10" - JOINTED									420101, 420106
TRANSVERSE									
SAWED CONTRACTION JOINT	Y	N	**	18	12	N	Y	HP	420001
CONSTRUCTION JOINT	Y	N	*	13	12	N	Y	HP	420101, 420106
EXPANSION JOINT	Υ	N	*	18	12	N	Υ	PF	420001
LONGITUDNAL					30				
SAWED	Y	Y	#6	30	30	N	Υ	HP	420001
CONSTRUCTION	Υ	Υ	#6	24	24	Υ	N	**	420001
CURB AND GUTTER	Y	Y	#6	24	24	Y	_	HP	606001

** SEE TABLE STANDARD 420001

*ASTM D 3405 SEALANT

HP = HOT POUR

PF = PREFORMED

SHEET 2 OF 2

REVISIONS NAME DATE		ILLINOIS DEPARTMENT OF TRANSPORTATION						
			OOMANAITMATNITO O					
		COMMITMENTS &						
		CENEDAL NOTES						
			GENERAL NOTES					
		VERT						
		SCALE: VERT. HORIZ.	DRAWN BY					
		DATE	CHECKED BY					
1		DATE	CHECKED BY					