

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	10-30/RA-1-2	CHAMPAIGN	119	7

# SUMMARY OF QUANTITIES

LOCATION OF WORK:

FAI 57  
ILLINI  
PRAIRIE  
REST  
AREA

CONSTRUCTION TYPE CODE:

J000  
100% STATE  
TOTAL

CODE NO	ITEM	UNIT	QUANTITY
550A0050	STORM SEWERS, CLASS A, TYPE 112"	FOOT	447.0
60219000	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	2.0
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	4.0
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	2.0
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	6.0
60500060	REMOVING INLETS	EACH	2.0
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	2,689.0
60605900	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.12	FOOT	1,537.0
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	8.0
67100100	MOBILIZATION	L SUM	1.0
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2,764.0
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	28.0
* X7030070	GROOVING FOR RECESSED PAVEMENT MARKING 5"	FOOT	3,919.0
* X7800600	URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS, SPECIAL	SQ FT	9.2
* X7800630	URETHANE PAVEMENT MARKING - LINE 6"	FOOT	3,919.0
Z0017100	DOWEL BARS	EACH	816.0
Z0075300	TIE BARS	EACH	150.0

\* SPECIALTY ITEMS